

Approved Tender Schedule

Name of the Work : Construction 2 (two) No. of Additional Class
Room
Name of the School: Kolhahundula UGUP School
G.P. : Anseikala : Kolhahundula

Estimated Cost in Rs	16,20,000.00
Amount put to Tender :	Rs. 13,92,648/-
Class of Contractor	C & D
Cost of Tender Paper	Rs. 6000.0
Earnest Money Deposit 1%	Rs. 13,936/-
Time of completion	6 Months

	Qnty.	Unit	Rate	Amount
1	Earth work excavation in hard soil or gravel within 50 mtr initial lead & 1.5 mtr initial lift including rough dressing the trench etc complete as per the direction of the Engineer in charge.			
	67.12	cum	@ Rs. 182.80 Rs.	12269.54
2	Filling foundation & plinth with coarse sand well watered and rammed as per the direction of Engineer in charge etc complete as per direction of Engineer in charge.			
	81.65	cum	@ Rs. 959.57 Rs.	78348.89
3	P.C.C (1:3:6) in foundation and plinth using 25mm H.G.C.B metal including cost, conveyance, royalty etc complete as per the direction of Engineer in charge.			
	20.98	cum	@ Rs. 5216.40 Rs.	109440.07
4	R.C.C (1:1.5:3) using 12mm H.G.C.B chips including centering & shuttering cost, conveyance, royalty etc complete as per the direction of Engineer in charge.			
a	Footing			
	10.37	cum	@ Rs. 5689.55 Rs.	59000.63
b	Plinth beam			
	3.89	cum	@ Rs. 6043.21 Rs.	23508.09
c	Column & Wall			
	6.72	cum	@ Rs. 11273.93 Rs.	75760.81
d	Lintel & Sill band			
	2.05	cum	@ Rs. 9281.64 Rs.	19027.36
e	Roof slab			
	14.06	cum	@ Rs. 9748.35 Rs.	137061.80
f	Chajja			
	0.88	cum	@ Rs. 9748.35 Rs.	8578.55
5	Straightening, cutting, bending, binding of M.S rod or Tor steel, tying up the grills and placing in position including cost of binding wire with all cost conveyance. taxes etc			
	TOTAL=	33.52 Qntl	@ Rs. 7580.37 Rs.	254094.00
6	Fly ash brick masonry with cement mortar (1:6) in foundation and plinth including cost, conveyance, royalty, taxes of all materials, all labour T & P sundries etc complete as per direction of Engineer in charge.			
	16.10	cum	@ Rs. 4571.15 Rs.	73595.52