

## Approved Tender Schedule

Name of the Work : Construction 2 (two) No. of Additional Class  
Room

Name of the School: Anseikala Noda UP School

G.P. : Anseikala : Anseikala

Estimated Cost in Rs	16,20,000.00
Amount put to Tender :	Rs. 13,92,648/-
Class of Contractor	C & D
Cost of Tender Paper	Rs. 6000.0
Earnest Money Deposit 1%	Rs. 13,936/-
Time of completion	6 Months

		Qnty.	Unit		Rate		Amount	
1	Earth work excavation in hard soil or gravel within 50 mtr initial lead & 1.5 mtr initial lift including rough dressing the trench etc complete as per the direction of the Engineer in charge.	67.12	cum	@	Rs. 182.80	Rs.	12269.54	
2	Filling foundation & plinth with coarse sand well watered and rammed as per the direction of Engineer in charge etc complete as per direction of Engineer in charge.	81.65	cum	@	Rs. 959.57	Rs.	78348.89	
3	P.C.C (1:3:6) in foundation and plinth using 25mm H.G.C.B metal including cost, conveyance, royalty etc complete as per the direction of Engineer in charge.	20.98	cum	@	Rs. 5216.40	Rs.	109440.07	
4	R.C.C (1:1.5:3) using 12mm H.G.C.B chips including centering & shuttering cost, conveyance, royalty etc complete as per the direction of Engineer in charge.							
a	Footing	10.37	cum	@	Rs. 5689.55	Rs.	59000.63	
b	Plinth beam	3.89	cum	@	Rs. 6043.21	Rs.	23508.09	
c	Column & Wall	6.72	cum	@	Rs. 11273.93	Rs.	75760.81	
d	Lintel & Sill band	2.05	cum	@	Rs. 9281.64	Rs.	19027.36	
e	Roof slab	14.06	cum	@	Rs. 9748.35	Rs.	137061.80	
f	Chajja	0.88	cum	@	Rs. 9748.35	Rs.	8578.55	
5	Straightening, cutting, bending, binding of M.S rod or Tor steel, tying up the grills and placing in position including cost of binding wire with all cost conveyance. taxes etc	TOTAL=	33.52	Qntl	@	Rs. 7580.37	Rs.	254094.00
6	Fly ash brick masonry with cement mortar (1:6) in foundation and plinth including cost, conveyance, royalty, taxes of all materials, all labour T & P sundries etc complete as per direction of Engineer in charge.	16.10	cum	@	Rs. 4571.15	Rs.	73595.52	