


APPROVED TENDER SCHEDULE

Name of the work: Const. of Five nos Additioonal Class Room ,One nos Toilet, Boundery wall at Banamahuladiha U.P school GP Dumuria		Amount put to tender:Rs 46,47,556.00			
		Class of contractor: C&S B&A			
		Cost of Tender Paper : Rs. 6,000/-			
		Earnest money Deposit 1% :Rs.46476.00			
		Time of Completion: 06months			
Sl. No	Description of Item	Unit	Quantity	Rate	Amount
1	Earth work in hard soil or gravelling soil for excavation of foundation including dressing and levelling of beds and depositing the soil away from the work side with all lead & lift including cost of all labour, T & P, dewatering,shorring and shuttering for the work etc. complete & as per direction of Engineer in charge	Cum	260.59	184.59	48102.31
2	Supplying and Filling in foundation and plinth with sand , well watered and rammed with all leads and lifts, cost convenience and royalty and all taxes of materials , cost of labour, T & P, dewatering, required for the works etc, complete in all respect as directed by engineer-in-charge.	Cum	203.56	370.50	75418.98
3	Cement concrete of proportion (1:4:8) with using 40 MM size hbg metal free from weathered and skin with including cost, convenience, royalty and taxes of all materials, labour etc including curing, dewatering if required in all respect including centering and shuttering etc.complete & as per direction of Engineer in charge	Cum	74.62	3744.11	279385.49
4	R.R H.G stone Masonary in cm (1:6) in foundation and plinth with all cost conveyance Royalty etc	cum	152.48	3192.96	486862.54
5	Fly ash brick(25cmx12cmx8cm) masonry in CM(1:6)for superstructre in foundation and plinth having a crushing strength of not less than 75 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, conveyance, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering in-charge.				
a.	In foundation & plinth.	Cum	15.88	4560.03	72413.28
b.	In superstructre .	Cum	131.88	4593.36	605772.32
6	Reinforcement cement concrete M-20 grade with 20 mm nomial size down graded nomial size aggregate mechanically mixed and vibrated in foundation and bed protection of speciation for road and Bridge work & Direction of the Eng in charge the work etc complete as direction by the engineering-in-charge.	Cum	121.03	4771.27	577447.72
7	Suppling, coiled M.S rod or HYSD steel (Fe-415),cutting, bending,cracking,hooking,olding or jointing (if required) reinforcement including labour charges for cutting, bending, binding and straightening and tying the grills and placing in position including cost of binding wire 18 to 20 gauge as per drawing and technical specifacaiton as directed by the engineering-in-charge.	Qtl	115.55	6328.63	731273.20


 25.07.2021
Block Development Officer
PATNA, KEONJHAR