

## TENDER SCHEDULE

**DETAILED ESTIMATE FOR THE WORK :-CONSTRUCTION OF ONE NO ADDITIONAL CLASS ROOM AND CONSTRUCTION OF ONE OF TOILET AT DASARATHIPUR U.G.U.P.S**

**AMOUNT PUT TO TENDER :- RS.912309**


CLASS OF CONTRACTOR :- D & C

COST OF TENDER PAPER :- RS. 4000.00 (4000=00)

EARNEST MONEY DEPOSITE 1% : RS.9123.00

TIME OF COMPLETION : 4 MONTHS

SI No.	ITEM OF WORK	Quantity	Unit	Rate	Amount
1	2	3	4	5	6
1	E/W in excavation of foundation in hard soil within initial lead & lift including levelling and dressing the bed complete.	54.05	One cum	Rs. 185.90	10047.90
2	Filling F & P with sand well watered and rammed complete.	31.05	One cum	Rs. 456.50	14174.33
3	C.C.(1:4:8) with using 4cm size H.G.H B metal including all cost carriage royalty ect complete.	13.09	One cum	Rs. 3,915.42	51252.85
4	Brick work with Fly ash.Bricks in cement mortar (1:6) in Fdn & Pl of size 10"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> dimensional tolerance $\pm$ 8% with carriage and royalty	24.40	One cum	Rs. 4,160.67	101520.35
5	Reinforcement cement concrete M - 20 grade with 20mm and down grade block hard granite ( Crusher broken ) stone chips including hoisting and laying including cost, conveyance, royalties, taxes and centering and shuttering etc. complete as per the direction of the Eng. In Charge.				
	a) Column base	5.56	One cum	Rs. 4,847.74	26953.43
	b) Plinth band	3.12	One cum	Rs. 5,223.27	16300.78
	c) Lintel band	1.71	One cum	Rs. 8,591.15	14690.87
	d) Chajja	0.79	One cum	Rs.10,577.44	8356.18
	e) Column & Roof beam	3.64	One cum	Rs.10,422.15	37936.63
	f) Slab	8.51	One cum	Rs.10,577.44	90014.01
6	Providing HYSD bar reinforcement for R.C.C. work including Straightening, cutting, bending, binding, welding, tying the grills, laying and placing in proper position as per approved design and drawing including cost, conveyance of 18 to 20 gauge binding wire cost and conveyance of HYSD bars complete in all respect as per specification for road & Bridge and direction of Eng - in Charge.	23.11	One Qntl	Rs. 6,481.53	149788.16
7	Brick work with Fly Ash.B.Bricks in cement mortar (1:6) in superstructure of size 10"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance $\pm$ 8% with carriage and royalty	24.26	One cum	Rs. 4,198.62	101858.52

  
 25.07.2021  
**Block Development Officer**  
**PATNA, KEONJHAR**