


**DISTRICT RURAL DEVELOPMENT AGENCY
JHARSUGUDA**



**PR & DW DEPARTMENT, ODISHA
BID DOCUMENT**

Name of the Work : Improvement of Hirma Govt.
High School
Name of the Block : Jharsuguda
Name of the District : Jharsuguda
Estimated Cost : Rs 49,43,000.00
Tender Value : Rs 43,73,280.00

Signature of the Tenderer


Signature of the BDO

5	Fly Ash Brick masonry in cement mortar (1.6) in superstructure with best quality bricks having crushing strength no less than 75 kg/sq.cm with dimensional tolerance # 2% immersing the bricks in water for not less than 6 hours before use(the bricks shall be well burnt, free from cracks, well shaped,uniform in size and shall produce a clear ringing sound when struck) includes moulding, chamfering, corbelling etc. complete as per drawing, design and specification, watering and curing for seven days incl. cost , conveyance, and taxes of all materials, labour T&P etc. complete as directed by E.I.C.					
	(i) In Superstruture (Ground floor)	79.50	Cum	4350.50	Rupees Four Thousand Three Hundred Fifty And Paise Fifty Only	345864.75
6	R.C.C work M-20 grade concrete having minlum compressive strength 200Kg/cm2 in 15cm cubes at 28days after mixing and test conducted in accordance with IS 456 and IS 516 using 20mm &10mm size black hard crusher broken granite chips incl. hoisting lowering laying and compacting concrete by using vibrator with watering and curing for 28days centring shuttering and finishing the exposed surface smooth providing groves or beds wherever necessary including cost . conveyance royalties and all taxes and cost of all materials and labour with T&P required for the work etc. complete as directed by E.I.C.					
	i) Column Base	24.94	Cum	4647.28	Rupees Four Thousand Six Hundred Forty Seven And Paise Twenty Eight Only	115903.16
	ii) Plinth Bend	10.71	Cum	5013.65	Rupees Five Thousand Thirteen And Paise Sixty Five Only	53696.19
	iii) Column,beam (Ground floor)	19.02	Cum	11726.36	Rupees Eleven Thousand Seven Hundred Twenty Six And Paise Thirty Six Only	223035.37
	iv) Lintel Bend (Ground floor)	4.62	Cum	8219.96	Rupees Eight Thousand Two Hundred Nineteen And Paise Ninety Six Only	37976.22

Signature of the Tenderer

Signature of the BDO

7	R.C.C work M-25 grade concrete having minium compressive strength 200Kg/cm2 in 15cm cubes at 28days after mixing and test conducted in accordance with IS 456 and IS 516 using 20mm &10mm size black hard crusher broken granite chips incl. hoisting lowering laying and compacting concrete by using vibrator with watering and curing for 28days centring shuttering and finishing the exposed surface smooth providing groves or beds wherever necessary including cost . conveyance royalties and all taxes and cost of all materials and labour with T&P required for the work etc. complete as directed by E.I.C					
	ii) Roof slab & Chajja (ground floor)	52.14	Cum	10344.78	Rupees Ten Thousand Three Hundred Forty Four And Paise Seventy Eight Only	539376.83
8	Straightening, cutting,bending and binding, welding and jointing (if necessary) coiled/bentup MS Rod/HYSD rods etc.including hoisting,placing in position, tying the grills binding with 18 to 20 gauge binding wires required for R.C.C works, cost of all labours T&P etc. as required for the work complete as directed by E.I.C including cost of rod.					
	(i) Ground floor	111.00	Cum	6550.14	Rupees Six Thousand Five Hundred Fifty And Paise Fourteen Only	727065.54
9	Supplying fitting & fixing MS doors Windows incl all labours T & P etc.	39.51	Qtl.	7500.00	Rupees Seven Thousand Five Hundred Only	296325.00
10	Providing 16 mm thick cement plaster to the inside surface of brick masonry wall with cement mortar (1:6) including racking out of joints, scraping and cleaning the surface with finishing the plaster surface smooth using wooden floats only to the proper plumbs and materials & all taxes, royalties, watering & curing etc. complete as directed by E.I.C					
	(i) Ground floor	531.16	Sqm.	189.50	Rupees One Hundred Eighty Nine And Paise Fifty Only	100654.82
11	6mm thick Cement Plaster(1:4)to R.C.C.surface finished smooth including closed deep chipping and slurry treatment including cost, carriage & royalty etc. complete.					
	(i) Ground floor	334.81	Sqm.	108.10	Rupees One Hundred Eight And Paise Ten Only	36192.96
12	12 mm (½") thick cement plaster (1:6) with neat cement punning in finished smooth brick walls and skirting after racking out the joints including watering and curing complete with cost conveyance royalties and all taxes of all materials and cost of all labour with T & P required for the work etc. complete.					
	(i) Ground floor	453.22	Sqm.	132.35	Rupees One Hundred Thirty Two And Paise Thirty Five Only	59983.67

Signature of the Tenderer

Signature of the BDO

13	Providing 12mm thick grading plaster (1:4) over roof slab including watering, curing, including cost of all materials, conveyance, loading and unloading, all taxes and royalties, T&P etc. complete as required for the finished item of work as directed by E.I.C.	303.12	Sqm.	142.52	Rupees One Hundred Forty Two And Paise Fifty Two Only	43200.66
14	2.5cm. Thick grading concrete in cement concrete (1:2:2) using 6mm. Size cbhg chips including cost of all materials. Labour T&P etc. required for the work all complete as per direction of the Engineer- in- Charge					
	Ground Floor	83.79	Sqm.	279.21	Rupees Two Hundred Seventy Nine And Paise Twenty One Only	23395.01
15	Supplying, fitting and fixing Vetrified tile in floors of size 600 mm x 600 mm of approved make confirming to IS 13755 laid on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all materials. Labour T&P etc. required for the work all complete as per direction of the Engineer- in- Charge (For New work only)					
	Ground Floor	412.32	Sqm.	1281.66	Rupees One Thousand Two Hundred Eighty One And Paise Fifty Six Only	528412.82
16	Fixing ceramic Wall tiles in dadoes skirting and risers of steps on 12mm thick bed of cement mortar 1:3 jointed with neat cement slurry mixed with pigment to match the shades of tiles including rubbing & polishing complete including cost of tiles	22.95	Sqm.	1086.21	Rupees One Thousand Eighty Six And Paise Twenty One Only	24928.52
17	Priming one coat with wall primer including all cost. Conveyance, rayallity etc, completed					
	Ground Floor	1319.19	Sqm.	27.67	Rupees Twenty Seven And Paise Sixty Seven Only	36501.99
18	Distempering two coats with any approved shade over the interior surface of walls etc complete in all floors as directed by the Engineer-in-Charge over a coat of chalk washing using distemper including cost conveyance of all materials including cost of distemper with all taxes and cost of all labour with T&P required for the work etc complete in all respect					
	ground Floor	865.97	Sqm.	62.96	Rupees Sixty Two And Paise Ninety Six Only	54521.47
19	Finishing walls with water-proofing weather coat of approved shade on new work to give an even shade including cost of cement paint with conveyance, sundries T&P etc required for the work complete as directed by E.I.C	453.22	Sqm.	61.73	Rupees Sixty One And Paise Seventy Three Only	27977.27
20	Painting two coats over a coat primer with paints of approved shade over a base coat of primer of any approved primer in all floors to iron work including sand papering polishing the surface, including cost conveyance royalties and all taxes of all materials along with T & P required for the work including cost of paints etc. complete in all respect					

Signature of the Tenderer

Signature of the BDO

	ground Floor	197.25	Sqm.	131.97	Rupees One Hundred Thirty One And Paise Ninety Seven Only	26031.08
21	Costruction of Display board	1	Nos	6500.00	Rupees Six Thousand Five Hundred Only	6500.00
				Total		3912390.91
PH WORKS						
22	Earth work in excavation of foundation in all kinds of soil including dressing & levelling the bed & depositing the soil clean of the work completed within intial lead of 50 mtr & 1.5 mtr intial lift as per direction of E.I.C.	18.00	%Cur	13737.29	Rupees Thirteen Thousand Seven Hundred Thirty Seven And Paise Twenty Nine Only	2472.71
23	Supplying all materials, labour, T&P and providing and fixing to wall or ceiling and floor GI/PVC pipes, class-IV (10 k.g. F/cm) on firming I.S.4985 of the following nominal bore, tube fittings and clamps including making good the wall, ceiling and floor, testing all complete as per specification and direction of the Engineer in charge.					
a	25mm. Dia PVC ASTM pipe (Shedule 80) -inlet	65.00	Mtr	145.62	Rupees One Hundred Forty Five And Paise Sixty Two Only	9465.30
b	32mm. Dia PVC ASTM pipe (Sch-80) -Out let	115.00	Mtr	189.34	Rupees One Hundred Eighty Nine And Paise Thirty Four Only	21774.10
c	20mm. Dia PVC ASTM pipe (Sch-80)	65.00	Mtr	115.37	Rupees One Hundred Fifteen And Paise Thirty Seven Only	7499.05
24	Filling in foundation trenches with excavated materials as directed by the Engineer-in-charge of earth work for 100 cum.	17.95	%Cur	7631.83	Rupees Seven Thousand Six Hundred Thirty One And Paise Eighty Three Only	1369.91
25	Supplying all materials, labour T&P and fitting and fixing brass/CP fittings of the following nominal bore with supply of all jointing materials including cost & conveyance of all materials to worksite, payment of taxes etc. all complete as per P.H specification and direction of the Engineer-in-charge.					
a	15mm dia CP angle stop cock (Jaquar/Hindware)or equivalent make.	4	Each	695.50	Rupees Six Hundred Ninety Five And Paise Fifty Only	2782.00
b	15mm dia CP two way bib cock (Jaquar/Hindware)or equivalent make.	2	Each	975.00	Rupees Nine Hundred Seventy Five Only	1950.00
c	15mm dia CP long body bib cock (Jaquar/Hindware Make)or equivalent make.	2	Each	733.00	Rupees Seven Hundred Thirty Three Only	1466.00
d	25mm dia brass full way valve (Shakti make)	1	Each	1040.00	Rupees One Thousand Forty Only	1040.00
e	32mm dia brass full way valve (Shakti make)	1	Each	1543.00	Rupees One Thousand Five Hundred Forty Three Only	1543.00

Signature of the Tenderer

Signature of the BDO

f	25mm dia CP Health Faucet (Jaquar/Hindware Make) or equivalent make.	2	Each	635.00	Rupees Six Hundred Thirty Five Only	1270.00
g	15mm CP Extension piece	8	Each	67.50	Rupees Sixty Seven And Paise Fifty Only	540.00
h	125mm CP grating	4	Each	36.70	Rupees Thirty Six And Paise Seventy Only	146.80
26	supplying all materials, labour, T&P and cutting holes through existing brick work including making good the damages in cement mortar (1:4) for taking G.I. Pipes and fittings/ P.V.C. pipes and fittings including watering, curing, cost & conveyance of all materials to worksite, payment of royalty, taxes etc. all complete as per direction of Engineer-in-charge.	6	Each	42.60	Rupees Forty Two And Paise Sixty Only	255.60
27	Supplying all materials, labour, T&P and cutting holes in RCC floors and roofs upto 19cm thick for passing P.V.C pipes and G.I fittings etc., and repairing the holes after insertion of pipe etc. with cement concrete (1:2:4) including finishing complete so as to make it leak-proof as per P.H. specification and direction of Engineer-in-charge	2	Each	147.10	Rupees One Hundred Forty Seven And Paise Ten Only	294.20
28	Supplying all materials, labour, T&P and cutting grooves in pucca floors and walls for taking G.I./P.V.C. pipes and making good the damages including watering, curing, cost & conveyance of all materials to worksite, payment of royalty, taxes etc all complete as per direction of the Engineer-in-charge.	6.10	Mtr	157.70	Rupees One Hundred Fifty Seven And Paise Seventy Only	961.97
29	Supplying all materials, labour, T&P and fitting and fixing U-PVC SWR soil waste ventilating pipes and fittings of the following outside diameter conforming to ISI No 13592/1992 to walls with nails, bobbins and wooden plugs or laying in trenches including jointing with supply of approved rubber lubricant by non-heat application method/as per manufacturer's specification, testing, earthwork in excavation in all kinds of soil and refilling of trenches, cost & conveyance of all materials to worksite, payment of taxes etc. all complete as per P.H specification and direction of the Engineer-in-charge.					
a	110mm U-PVC SWR Pipe (Ori Plast/Finolex/Supreme Make Type-B)	40.00	Mtr.	229.30	Rupees Two Hundred Twenty Nine And Paise Thirty Only	9172.00
b	110mm U-PVC 'P' Trap(Ori Plast/Finolex/Supreme Make)	4	Each	266.00	Rupees Two Hundred Sixty Six Only	1064.00
c	110mm U-PVC 'Floor' Trap(Ori Plast/Finolex/Supreme Make)	2	Each	118.23	Rupees One Hundred Eighteen And Paise Twenty Three Only	236.46
d	110mm U-PVC door bend(Ori Plast/Finolex/Supreme Make)	2	Each	136.05	Rupees One Hundred Thirty Six And Paise Five Only	272.10

Signature of the Tenderer

Signature of the BDO

e	110mm U-PVC Plain bend(Ori Plast/Finolex/Supreme Make)	2	Each	107.33	Rupees One Hundred Seven And Paise Thirty Three Only	214.66
f	110mm U-PVC offset without ear(Ori Plast/Finolex/Supreme Make)	2	Each	115.20	Rupees One Hundred Fifteen And Paise Twenty Only	230.40
g	110mm U-PVC Cowl(Ori Plast/Finolex/Supreme Make)	2	Each	26.46	Rupees Twenty Six And Paise Forty Six Only	52.92
h	110mm U-PVC S/Jn door(Ori Plast/Finolex/Supreme Make)	2	Each	175.35	Rupees One Hundred Seventy Five And Paise Thirty Five Only	350.70
i	110mm U-PVC Plain tee(Ori Plast/Finolex/Supreme Make)	1	Each	115.20	Rupees One Hundred Fifteen And Paise Twenty Only	115.20
j	110mm U-PVC D/Jn door(Ori Plast/Finolex/Supreme Make)	2	Each	221.50	Rupees Two Hundred Twenty One And Paise Fifty Only	443.00
k	110mm U-PVC Socket(Ori Plast/Finolex/Supreme Make)	10	Each	32.90	Rupees Thirty Two And Paise Ninety Only	329.00
30	Supplying all materials, labour, T&P and fixing Rotational molded polyethylene cylindrical vertical water storage tanks conforming to IS : 12701--1996 including cutting holes through the tank and fixing mild steel tubes and fittings and providing extra sockets and jam nuts, fixing ball valve etc, all complete as per specification and direction of the Engineer in charge					
	1000 liter PVC water storage tank (roof Floor)	4	Each	10641.00	Rupees Ten Thousand Six Hundred Forty One Only	42564.00
31	Supplying all materials, labour, T&P and fixing vitreous china water closet, squatting pan (Indian type W.C pan/Orissa pattern squatting pan) duly embedded in cement concrete (1:5:10) using 4cm size hard granite metal including fixing a pair of vitreous china 250mm x 130mm x30mm footrest, fixing 100mm dia HCl 'p' or 's' trap (with/without 50mm dia horn) for water colset squatting pan including jointing the trap with pan in cement mortar (1:1) cutting the floor and mending good the damages, cost & conveyance of all materials to worksite, payment of royalty, taxes etc. all complete as per P.H specification and direction of the Engineer-in-charge.					
	580mm size Orissa pan (Hindware/Parryware/Neycer make)	2	Each	2616.00	Rupees Two Thousand Six Hundred Sixteen Only	5232.00

Signature of the Tenderer

Signature of the BDO

32	Supplying all materials, labour T&P and and fixing 12.50 liters/10 liters capacity low level flushing cistern with a pair of cast iron or M.S. brackets complete with fittings such as siphonic arrangements 15mm nominal size brass/pvc ball valve with polythene float CP brass handle, unions and couplings for connection with inlet, outlet and overflow pipes, 32mm dia CP long flush bend, 15mm dia pvc inlet connection pipe including cutting holes and making good the same and connecting the flush bend with cistern and closet and connecting the inlet pipe with supply main , cost & conveyance of all materials to worksite, payment of taxes etc. all complete as per P.H specification and direction of the Engineer-in-charge					
	10 ltr. Capacity pvc L.L. cistern with 32mm. Dia CP long flush bend (Slimline-white-Parryware make)	2	Each	1486.00	Rupees One Thousand Four Hundred Eighty Six Only	2972.00
33	Supplying all materials, labour T&P and fixing wash basins with hole for pillar taps with cast iron or M.S.brackets painted white including cutting holes in walls and making good the damages with supply of wooden plugs, screws and cement etc, fixing pedestal for wash basin recessed at the back for the reception of pipes and fittings, fixing PVC waste pipe of 32mm nominal diameter for wash basin including brass check nut complete, fixing pillar taps capstan head screw down high pressure lettered 'Hot' and 'Cold' with long screws, shanks and back nuts of 15mm dia nominal bore, fixing 15mm dia PVC inlet connection pipe and making connection with pillar cocks and supply mains for wash basin, fixing 32mm dia CP brass waste, cost & conveyance of all materials to worksite, payment of taxes etc. all complete as per P.H specification and direction of the Engineer-in-charge					
	550mmx400mm W.H.basin (Hindware/Parryware/Neycer make)with 15mm dia C.P.pillar cock (Plaza make) with pedestal	2	Each	1996.00	Rupees One Thousand Nine Hundred Ninety Six Only	3992.00
34	Supplying all materials, labour, T&P and fixing mirror of superior glass mounted on 6mm.thick A.C. sheet or ply wood sheet and fixed to wooden plugs with CP screws and washers complete as per specification and direction of Engineer in charge.					
	600mmx450mm size B.E mirror (swivelled type)	2	Each	617.60	Rupees Six Hundred Seventeen And Paise Sixty Only	1235.20
35	Supplying all materials, labour, T&P and fixing CP soap holder complete with CP brass brackets fixed to wooden plugs with CP screws as per specification and direction of the Engineer in charge					

Signature of the Tenderer

Signature of the BDO 

	CP soap holder (Jaquar/Hindware or equivalent make)	4	Each	175.00	Rupees One Hundred Seventy Five Only	700.00
36	Supplying all materials ,labour ,T&P and constructing inspection Chamber of inside size 760mmx760mmx460mm with cement concrete (1:3:6) using 40mm size crusher broken hard black granite metal on bed , KB brick work in cement mortar (1:6) in foundation and plinth, moulding and shaping the channel inside and benching with cement concrete (1:2:4) using 12mm size crusher broken hard black granite chips, 12mm thick cement plaster (1:3) with cement punning to inside, cement flush pointing (1:3) to outside, R.C.C cover slab (1:2:4) using 12mm size crusher broken hard black granite chips with R.C.C man hole cover, earth work in excavation in all kinds of soil and refilling the cavity around the chamber including watering,curing, cost of all materials, conveyance of all materials to worksite, payment of royalty, all taxes etc.all complete as per approved drawing, P.H specification and direction of Engineer-in-charge					
	Inside size 76cmx76cmx46cm with 18" dia RCC MH cover	2	Each	7523.80	Rupees Seven Thousand Five Hundred Twenty Three And Paise Eighty Only	15047.60
37	Sinking of 125x100mm. Dia deep bore well	1	Nos	87798.00	Rupees Eighty Seven Thousand Seven Hundred Ninety Eight Only	87798.00
38	Supplying,fitting,fixing of submersible pump set	1	Set	36002.50	Rupees Thirty Six Thousand Two And Paise Fifty Only	36002.50
				Total		262854.39
ELECTRICAL						
39	Recessed wiring to light/Fan/Exhaust fan/ Call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 5 Amp, 250 V piano type switch ISI marked and ceiling rose ISI marked mounted on MS box having front bakelite cover of suitable size , MS box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accesories and connection as per direction of Engineer in Charge. (Make of wire Finolex / L&T / Anchor / Havels / V Guard)					
	(a) Group-A	21	Each	417.00	Rupees Four Hundred Seventeen Only	8757.00
	(b) Group-B	18	Each	642.00	Rupees Six Hundred Forty Two Only	11556.00
	(c) Group-C	16	Each	924.00	Rupees Nine Hundred Twenty Four Only	14784.00

Signature of the Tenderer

Signature of the BDO

40	Recessed wiring to 5/6amp Plug pt. point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 5 Amp, 250 V piano type switch ISI marked and ceiling rose ISI marked mounted on MS box having front bakelite cover of suitable size , MS box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accesories and connection as per direction of Engineer in Charge. (Make of wire Finolex / L&T / Anchor / Havells / V Guard)	10	Each	423.00	Rupees Four Hundred Twenty Three Only	4230.00
41	S/F of 5/6A Switch & 3Pin 5/6A Socket On Existing Board.	16	Each	88.00	Rupees Eighty Eight Only	1408.00
42	Circuit Sub main wiring in PVC Conduit.					
a	2 x 2.5 sq.mm + 1 x 1.5 sq.mm(for extra long point	80.00	Mtr	126.00	Rupees One Hundred Twenty Six Only	10080.00
b	2 x 2.5 sq.mm + 1 x 1.5 sq.mm	290.00	Mtr	140.00	Rupees One Hundred Forty Only	40600.00
c	2 x 4 sq.mm + 1 x 1.5 sq.mm	90.00	Mtr	157.00	Rupees One Hundred Fifty Seven Only	14130.00
d	S/F of B.K.Angle Holder without Bulb	32	Nos	58.00	Rupees Fifty Eight Only	1856.00
43	S/F 10 watt LED Lamp (Bajaj/Philips)	33	Nos	156.00	Rupees One Hundred Fifty Six Only	5148.00
44	Supply of A.C Ceiling Fan (Usha/Bajaj/CG)	20	Nos	1384.00	Rupees One Thousand Three Hundred Eighty Four Only	27680.00
45	S/F of Electronic step down Fan Regulator	20	Nos	267.00	Rupees Two Hundred Sixty Seven Only	5340.00
46	Supply of Exhaust Fan 10/12" Size heavy duty (Usha/ Havells)	2	Nos	1686.00	Rupees One Thousand Six Hundred Eighty Six Only	3372.00
47	S/F of 20W Tube light.(Make- Havells/Philips/Bajaj/CG).	22	Nos	695.00	Rupees Six Hundred Ninety Five Only	15290.00
48	S/F of Earthing with copper plate 600 mm x 600mm x 3.15 mm thick ISI marked including accessories and providing masonry with cover plate having locking arrangement and watering pipe etc with charcoal & salt.	1	Nos	5596.00	Rupees Five Thousand Five Hundred Ninety Six Only	5596.00
49	S/F of 45 W LED street light (make Havells /CG)	3	Nos	6482.00	Rupees Six Thousand Four Hundred Eighty Two Only	19446.00
50	S/F of 63 Amp ICDP Main Switch.(HPL/L&T/Havells)	1	Nos	1627.91	Rupees One Thousand Six Hundred Twenty Seven And Paise Ninety One Only	1627.91
51	S/F of 4 way Double door MCB DB.	6	Nos	1189.00	Rupees One Thousand One Hundred Eighty Nine Only	7134.00
			Total			198034.91

Signature of the Tenderer

Signature of the BDO

Fifty one nos. only	Grand Total	4373280.20
	Say Rs	4373280.00

Rupees Forty Three Lakh(s) Seventy Three Thousand Two Hundred Eighty Only

[Signature]
Junior Engineer
Jharsuguda Block

[Signature]
Assistant Engineer
Jharsuguda Block

[Signature]
Block Development Officer
Jharsuguda Block

My/ our quoted rate is _____ % (both figure & words) excess over/ less than /equal to above estimated cost.

Signature of the tenderer

- 1 The contractor should not write any thing except quoting of percentage and in case of any thing else regarding tender.
- 2 Strike out which are not applicable.
- 3 Percentage quoted by the contractor shall be accurately filled in figures and words so there is no discrepancy.
- 4 If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
- 5 The percentage quoted in the tender without mentioning excess or less will be treated as excess.
- 6 The contractor will write percentage excess or less upto one decimal point only.If he writes the percentage excess or less upto two or more decimal point shall only be considered.

APPROVED
For 51(Fifty one) item Only

Signature of the tenderer

Total- 51 (Fifty one) items only.

No. of Correction

No. of Overwriting

No. of Interpolation

Approved for - 51(Fifty one) Items only.

[Signature]
Block Development Officer
Jharsuguda

Signature of Contractor

[Signature]
Block Development Officer
Jharsuguda

Signature of the Tenderer

[Signature]
Signature of the BDO