

Govt. of Odisha SSA, MALKANGIRI

BID DOCUMENT

FOR THE WORK : Construction of ACR Building at Chitapari-IV
PS Under SCA

Name of the GP : Potrel

Name of the Block: Korukonda



Office of District Project Coordinator, SSA, Malkangiri

Tender Call Notice No.4083/Dated:25.10.2018

Sealed tender in the prescribed form to be eventually drawn-up in PWD Form P-1 (Percentage Rate Bids) in conformity with detailed Tender Call Notice are invited by the District Project Coordinator, RTE-SSA, Malkangiri, on behalf of Government of Odisha for tenders for construction of Building works as detailed in the table below from eligible Contractors registered with the State Government and contractor of equivalent grade/class registered with Central Government/MES/Railways, having registration for Civil works on production of definite proof from the appropriate authority.

1. The bidders may submit bids for the following work.

Sl. No	Name of work	Tender value of work. (In ₹.)	Class of contract or	Other Places of sale & receipt	E.M.D. (₹.)	Cost of Tender Paper (₹.)	Period of completion.
1	2	3	4	5	6	7	8
1	Construction of 40 seated Primary school Hostel at Badapada PSH, GP-Badapada, Block-Chitokonda under SCA	2053708.00	"C" & "B" Class	Office of DPC, Malkangiri	20600/-	6000/-	06(Six) Calendar months
2	Construction of 40 seated Primary school Hostel at Populur PSH, GP-Populur, Block-Chitokonda under SCA	2056432.00	"C" & "B" Class	Office of DPC, Malkangiri	20600/-	6000/-	06(Six) Calendar months
3	Construction of 40 seated Primary school Hostel at Badadural Upgraded HS, GP-Badadural, Block- Khairput under SCA	2041854.00	"C" & "B" Class	Office of DPC, Malkangiri	20500/-	6000/-	06(Six) Calendar months
4	Construction of Addl. Class Room Building at Kodigandhi PS, GP-Andrapalli, Block-Chitokonda under SCA	999361.00	"D" & "C" Class	Office of DPC, Malkangiri	10000/-	4000/-	04(Four) Calendar months
5	Construction of Addl. Class Room Building at Badabel PS, GP-Andrahal, Block- Khairput under SCA	994545.00	"D" & "C" Class	Office of DPC, Malkangiri	10000/-	4000/-	04(Four) Calendar months
6	Construction of Addl. Class Room Building at Mondapalli PUPS, GP-Raleguda, Block-Chitokonda under SCA	999361.00	"D" & "C" Class	Office of DPC, Malkangiri	10000/-	4000/-	04(Four) Calendar months
7	Construction of Addl. Class Room Building at Buduguda PS, GP-Kalimela, Block- Kalimela under SCA	997453.00	"D" & "C" Class	Office of DPC, Malkangiri	10000/-	4000/-	04(Four) Calendar months
8	Construction of Teachers Complex at Populur, GP- Populur, Block-Chitokonda under SCA	3185421.00	"C" & "B" Class	Office of DPC, Malkangiri	31900/-	6000/-	08(Eight) Calendar months
9	Construction of Labour Room at Jodambo PHC with internal Electrification and running water supply with provision of AC (350 Sq Ft) GP-Jodambo, Block-Chitokonda under SCA	529062.00	"D" & "C" Class	Office of DPC, Malkangiri	5300/-	4000/-	04(Four) Calendar months
10	Construction of multipurpose patient observation room at popular, GP-Populur, Block-Chitokonda under SCA	667921.00	"D" & "C" Class	Office of DPC, Malkangiri	6700/-	4000/-	04(Four) Calendar months
11	Construction of multipurpose patient observation room at Jodambo, GP-Jodambo, Block-Chitokonda under SCA	669230.00	"D" & "C" Class	Office of DPC, Malkangiri	6700/-	4000/-	04(Four) Calendar months
12	Construction of Addl. Class Room Building at Bondapada PS, GP-Mudulipada, Block-Khairput under SCA	557211.00	"D" & "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months

13	Construction of Addl. Class Room Building at Bandiguda PS, GP- Mudulipada, Block- Khairput under SCA	554602.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
14	Construction of Addl. Class Room Building at Naringijhola PS, GP- Nakamamudi, Block-Chitrokonda under SCA	554407.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
15	Construction of Addl. Class Room Building at Dumuripada PS, GP- Andrahal, Block- Khairput under SCA	556984.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
16	Construction of Addl. Class Room Building at Bihangudi PS, GP- Jodambo, Block-Chitrokonda	554403.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
17	Construction of Addl. Class Room Building at Korukundi PS, GP- Bhejangiwada, Block-Kalimela under SCA	556867.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
18	Construction of Addl. Class Room Building at Sunapadar PS, GP- Temurpalli, Block- Mathili under SCA	555593.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
19	Construction of Addl. Class Room Building at Kamarpalli PS, GP- Kamarpalli, Block- Mathili under SCA	554970.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
20	Construction of Addl. Class Room Building at Purlubandha PS, GP- Papermetla, Block- Chitrokonda under SCA	556710.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
21	Construction of Addl. Class Room Building at MPV 54 PS, GP- Bhubanpalli, Block- Podia under SCA	555798.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
22	Construction of Addl. Class Room Building at Nuaguda PS, GP- Korukonda, Block- Korukonda under SCA	554229.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
23	Construction of Addl. Class Room Building at Batriatal PS, GP- Sindhrimal, Block- Malkangiri under SCA	556169.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
24	Construction of Addl. Class Room Building at Kaliaguda PS, GP- Mecca, Block- Mathili under SCA	556028.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
25	Construction of Addl. Class Room Building at Batanwada PS, GP- Matteredu, Block- Podia under SCA	556911.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
26	Construction of Addl. Class Room Building at Banur PS, GP- Tarlakota, Block- Korukonda under SCA	554396.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
27	Construction of Addl. Class Room Building at Tangnitang PS, GP- Serpalli, Block- Malkangiri under SCA	556759.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
28	Construction of Addl. Class Room Building at Dangarkhali PS, GP- Pangam, Block- Mathili under SCA	557319.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
29	Construction of Addl. Class Room Building at Valampalli PS, GP- Similibancha, Block- Podia under SCA	555319.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
30	Construction of Addl. Class Room Building at Namkonda PS, GP- Koimetla, Block- Kalimela under SCA	556704.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months

31	Construction of Addl. Class Room Building at Chitapari IV PS, GP- Potrel, Block- Korukonda under SCA	553755.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
32	Construction of Addl. Class Room Building at Satiguda PS, GP- Sindhrimal, Block- Malkangiri under SCA	556270.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
33	Construction of Addl. Class Room Building at Gorasethu PUPS, GP- Panasput, Block- Chitrokonda under SCA	554403.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
34	Construction of Addl. Class Room Building at Gangalaguda PS, GP- Potrel, Block- Korukonda under SCA	554189.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
35	Construction of Addl. Class Room Building at Tangapalli PS, GP- Udupa, Block- Malkangiri under SCA	556847.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months

1. Bid documents consisting of plans, specifications, the schedule of quantities and the set of terms and conditions of contract and other necessary documents can be seen in all the offices issuing the documents and office of the under signed during office hours every day except on Sundays and Public Holidays till last date of sale and receipt of tender papers. The bid documents will also be available in the district website www.malkangiri.nic.in from **25.10.2018 to 08.11.2018 (up to 5.00 PM)**. Interested bidders may also obtain further information at the same address.
2. **Cost of Tender Paper**-Bids must be accompanied by paper cost of the amount specified for the work in the table (Col No.7) above column in shape of Demand Draft (non-refundable) drawn in any Nationalized Bank **favour of District Project Coordinator, RTE-SSA, Malkangiri.**
3. **Earnest Money Deposit**-The bid must be accompanied by Earnest Money Deposit (EMD) of the amount @ 1% of the bid value in shape of **N.S.C/K.V.P/Postal time deposit pass book/Term Deposit receipt of any scheduled Bank** duly pledged in **favour of District Project Coordinator, RTE-SSA, Malkangiri. (N.B:- Bank draft /pay orders or Banker's cheque from any scheduled bank in favour of District Project Coordinator, shall not be considered as EMD.)**
4. **Sale and Receipt of Tender Paper**-The sale and receipt of the Bid documents shall start from **25.10.2018 to 08.11.2018 up to 5.00 P.M.** On working days. Bid documents in a sealed envelope should be received in the office of District Project Coordinator, RTE-SSA, Malkangiri through **Registered Post & Speed Post only** (No tender paper will received by hand or courier service.) and super scribed the **NAME OF WORK** **“(written in Capital letter)** on the Body of cover. Bidding documents will be Despatched by registered/speed post only. The authority will not held responsible for the postal delay if any, in the delivery of the documents or non-receipt of the same.
5. **Date of Opening of the tender Paper**-The Bids will open on **09.11.2018 at 10.00 A.M.** in the office Chamber of Collector, Malkangiri in the presence of the bidders who wish to attend. If the office happens to be closed (holiday) on the date of receipt/opening of the bids as specified, the bids will be received/opened on the next working day at the same time and venue without further notice. However, date of tender paper opening may be postponed as per the convenience of the authority by intimating all the concerned tenderers through notice affixing to notice board at Office of DPC, Malkangiri.
6. **Additional Performance Security Deposit**- Additional Performance Security shall be obtained from the bidders, When the bid amount is less than the estimated cost put to tender. In such an event, only successful bidders who have quoted less bid price/rates than the estimated cost put to tender shall have to furnish the exact amount of differential cost. i.e, Estimated cost minus the quoted amount as Additional Performance Security Deposit in shape of **N.S.C/K.V.P/ Postal time deposit pass book/Term Deposit receipt** duly pledged in **favour of District Project Coordinator, RTE-SSA, Malkangiri**, within seven days otherwise the bid shall be cancelled and security deposit shall be forfeited further proceeding for black listing shall be initiated against (as per Govt of Odisha works department office memorandum no. 14299 dtd.03.10.2017 and amendment of para no 3.5.5 (V) of OPWD code volume 1).
7. Bid documents can be downloaded for the work from the Dist website of Malkangiri District (www.malkangiri.nic.in) on payment of tender cost of ₹.10000.00 (Rupees Ten thousand) only for in shape of Demand Draft in any nationalise Bank in favour of **DPC, SSA, Malkangiri** (Non refundable). And submit the Demand Draft in a separate envelope marked "COST OF TENDER DOCUMENT DOWNLOADED FROM INTERNET" along with the tender.
8. **The following Documents should be furnished with the tender paper failing which the tender is liable for Rejection.**
 - A) EMD Pledged in favour of DPC, Malkangiri.

- B) Attested copy of valid Contractor Registration Certificate.
C) Attested copy of valid Pan Card & GST No.
D) SC/ST Contractors submit original Affidavit in support of caste certificate and attested copy off Caste certificate.
E) Original money receipt/Bank Draft towards cost of Tender paper.
F) Original Affidavit Support of the authenticity of Documents including EMD etc.
G) No Relation Certificate Signature of Tenderer.
9. Engineering Contractors desiring to avail the exemption facility of EMD should submit an original affidavit as regards, the fact of availing award of work without submission of EMD/ISD during the current financial year. He should also produce original contract licence at the time of opening of tender document to make necessary entry to that effect as such facilities are limited to three participation in tender during a financial year. Otherwise their tender will be liable for rejection.
10. The SC/ST Contractors desirous of availing preference should submit an original affidavit in support of caste certificate and attested copy of caste certificate, Otherwise their tender will be liable for rejection.
11. Short fall of any required documents, Tender paper is liable for rejection.
12. A bidder can submit only one tender paper for a particular work. Submission of more than one tender paper by a bidder for a particular tender will liable for rejection of all such tender papers.
13. Other details can be seen in the bidding document.
14. The authority reserves the right to reject any or all the tenders without assigning any reason thereof.

By order of Collector

**District Project Coordinator
RTE-SSA, Malkangiri**

Memo No.4084

Dated. 25.10.18

Copy to the Notice Board of the office of DPC, Malkangiri/ Collector, Malkangiri/ PD, DRDA, Malkangiri/ Executive Engineer. R&B / Executive Engineer RWD-I&II/ Block Development Officer, Malkangiri / Project Administrator I.T.D.A. Malkangiri/ DIPRO Malkangiri for information and wide publicity.

**Sd/-
District Project Coordinator
RTE-SSA, Malkangiri**

Memo No.4085

Dated. 25.10.18

Copy to PA to Collector, Malkangiri for kind information of Collector, Malkangiri.

**Sd/-
District Project Coordinator
RTE-SSA, Malkangiri**

CONTRACT DATA

A. GENERAL INFORMATIONS

Sl. No	Item	Details
1	Bid Identification No.	4083/SSA, / CIVIL/2018-19
2	Name of the Work	Construction of Addl. Class Room Building at Chitapari IV PS, GP- Potrel, Block- Korukonda under SCA
3	Officer Inviting Tender	District Project Coordinator, RTE-SSA, Malkangiri
4	Engineer-in-charge of work.	Sr. Technical Consultant, RTE-SSA, Malkangiri
4	Estimated Cost :	₹. 553755.00
	Amount put to tender	₹. 553755.00

B. BID INFORMATION

6	Intended completion period/Time period assigned for Completion	4 Calendar Months
7	Last Date & time of submission of Bid	Date.08.11.2018 up to 5.00 PM
8	Cost of Bid Document	
	i Bank draft amount separately (Cost of tender paper)	₹. 4000/-
	ii Downloaded from website	₹. 10,000/-
	iii in favour of	District Project Coordinator, RTE-SSA, Malkangiri
	iv payable at	Malkangiri
9	Bid Security	
	i Amount	₹. 5600/-
	ii in favour of	District Project Coordinator, RTE SSA, Malkangiri
	iii payable at	Malkangiri
	iv Type of instrument	As specified in the bid document
11	Bid validity period	90 days
12	Minimum period of contract / agreement	04 (Four) Months
13	Currency of payment for Contract	Indian Rupee
14	Language of Contract	English

OFFICE OF THE DISTRICT PROJECT COORDINATOR, MALKANGIRI.

INVITATIONS FOR BIDS (IFB)

Tender Call Notice No. 4083

Date:-25.10.2018

The District Project Coordinator, RTE-SSA, Malkangiri invites percentage rate for the construction works detailed in the table.

Sl. No	Name of work	Tender value of work. (In ₹.)	Class of contract or	Other Places of sale & receipt	E.M.D. (₹.)	Cost of Tender Paper (₹.)	Period of completion.
1	2	3	4	5	6	7	8
1	Construction of 40 seated Primary school Hostel at Badapada PSH, GP-Badapada, Block- Chitokonda under SCA	2053708.00	"C" & "B" Class	Office of DPC, Malkangiri	20600/-	6000/-	06(Six) Calendar months
2	Construction of 40 seated Primary school Hostel at Populur PSH , GP-Populur, Block-Chitrokonda under SCA	2056432.00	"C" & "B" Class	Office of DPC, Malkangiri	20600/-	6000/-	06(Six) Calendar months
3	Construction of 40 seated Primary school Hostel at Badadural Upgraded HS, GP-Badadural, Block- Khairput under SCA	2041854.00	"C" & "B" Class	Office of DPC, Malkangiri	20500/-	6000/-	06(Six) Calendar months
4	Construction of Addl. Class Room Building at Kodigandhi PS, GP-Andrapalli, Block-Chitrokonda under SCA	999361.00	"D" & "C" Class	Office of DPC, Malkangiri	10000/-	4000/-	04(Four) Calendar months
5	Construction of Addl. Class Room Building at Badabel PS, GP-Andrahal, Block- Khairput under SCA	994545.00	"D" & "C" Class	Office of DPC, Malkangiri	10000/-	4000/-	04(Four) Calendar months
6	Construction of Addl. Class Room Building at Mondapalli PUPS, GP-Raleguda, Block-Chitrokonda under SCA	999361.00	"D" & "C" Class	Office of DPC, Malkangiri	10000/-	4000/-	04(Four) Calendar months
7	Construction of Addl. Class Room Building at Buduguda PS, GP-Kalimela, Block- Kalimela under SCA	997453.00	"D" & "C" Class	Office of DPC, Malkangiri	10000/-	4000/-	04(Four) Calendar months
8	Construction of Teachers Complex at Populur, GP- Populur, Block-Chitrokonda under SCA	3185421.00	"C" & "B" Class	Office of DPC, Malkangiri	31900/-	6000/-	08(Eight) Calendar months
9	Construction of Labour Room at Jodambo PHC with internal Electrification and running water supply with provision of AC (350 Sq Ft) GP-Jodambo, Block-Chitrokonda under SCA	529062.00	"D" & "C" Class	Office of DPC, Malkangiri	5300/-	4000/-	04(Four) Calendar months
10	Construction of multipurpose patient observation room at popular, GP-Populur, Block-Chitrokonda under SCA	667921.00	"D" & "C" Class	Office of DPC, Malkangiri	6700/-	4000/-	04(Four) Calendar months
11	Construction of multipurpose patient observation room at Jodabmo, GP-Jodambo, Block-Chitrokonda under SCA	669230.00	"D" & "C" Class	Office of DPC, Malkangiri	6700/-	4000/-	04(Four) Calendar months
12	Construction of Addl. Class Room Building at Bondapada PS, GP-Mudulipada, Block-Khairput under SCA	557211.00	"D" & "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
13	Construction of Addl. Class Room Building at Bandiguda PS, GP-Mudulipada, Block- Khairput under SCA	554602.00	"D" & "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months

14	Construction of Addl. Class Room Building at Naringijhola PS, GP- Nakamamudi, Block-Chitrokonda under SCA	554407.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
15	Construction of Addl. Class Room Building at Dumuripada PS, GP- Andrahal, Block- Khairput under SCA	556984.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
16	Construction of Addl. Class Room Building at Bihangudi PS, GP- Jodambo, Block-Chitrokonda	554403.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
17	Construction of Addl. Class Room Building at Korukundi PS, GP- Bhejangiwada, Block-Kalimela under SCA	556867.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
18	Construction of Addl. Class Room Building at Sunapadar PS, GP- Temurpalli, Block- Mathili under SCA	555593.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
19	Construction of Addl. Class Room Building at Kamarpalli PS, GP- Kamarpalli, Block- Mathili under SCA	554970.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
20	Construction of Addl. Class Room Building at Purlubandha PS, GP- Papermetla, Block- Chitrokonda under SCA	556710.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
21	Construction of Addl. Class Room Building at MPV 54 PS, GP- Bhubanpalli, Block- Podia under SCA	555798.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
22	Construction of Addl. Class Room Building at Nuaguda PS, GP- Korukonda, Block- Korukonda under SCA	554229.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
23	Construction of Addl. Class Room Building at Batriatal PS, GP- Sindhrimal, Block- Malkangiri under SCA	556169.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
24	Construction of Addl. Class Room Building at Kaliaguda PS, GP- Mecca, Block- Mathili under SCA	556028.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
25	Construction of Addl. Class Room Building at Batanwada PS, GP- Matteredu, Block- Podia under SCA	556911.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
26	Construction of Addl. Class Room Building at Banur PS, GP- Tarlakota, Block- Korukonda under SCA	554396.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
27	Construction of Addl. Class Room Building at Tangnitang PS, GP- Serpalli, Block- Malkangiri under SCA	556759.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
28	Construction of Addl. Class Room Building at Dangarkhali PS, GP- Pangam, Block- Mathili under SCA	557319.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
29	Construction of Addl. Class Room Building at Valampalli PS, GP- Similibancha, Block- Podia under SCA	555319.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
30	Construction of Addl. Class Room Building at Namkonda PS, GP- Koimetla, Block- Kalimela under SCA	556704.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
31	Construction of Addl. Class Room Building at Chitapari IV PS, GP- Potrel, Block- Korukonda under SCA	553755.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months

32	Construction of Addl. Class Room Building at Satiguda PS, GP- Sindhimal, Block- Malkangiri under SCA	556270.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
33	Construction of Addl. Class Room Building at Gorasethu PUPS, GP- Panasput, Block- Chitrokonda under SCA	554403.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
34	Construction of Addl. Class Room Building at Gangalaguda PS, GP- Potrel, Block- Korukonda under SCA	554189.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months
35	Construction of Addl. Class Room Building at Tangapalli PS, GP- Udupa, Block- Malkangiri under SCA	556847.00	"D"& "C" Class	Office of DPC, Malkangiri	5600/-	4000/-	04(Four) Calendar months

- i. The sale and receipt of the bid document shall start from the date **25.10.2018 to 08.11.2018** up to 5.00 P.M. during the Working days. Bids will be sold and receipt in the office of the District Project Coordinator, RTE-SSA, Malkangiri.
- ii. Other details can be seen in the website www.malkangiri.nic.in

Sd/-
**District Project Coordinator,
RTE-SSA, Malkangiri**

DETAILED TENDER CALL NOTICE

1. Sealed Percentage Rate Bids are invited from D/C class contractors registered with the State Government and contractors of equivalent Grade / class registered with Central Government / MES / Railways for execution of Civil works on production of definite proof from the appropriate authority in prescribed form to be eventually drawn in P.W.D. FORM P-1 for the work-“ **Construction of Addl. Class Room Building at Chitapari IV PS.**” at an estimated cost of **₹.553755.00 (Rupees Five lakh fifty three thousand seven hundred fifty five) only.**
(a) This detailed Tender Call Notice along with the clauses mentioned here in shall form a part of the contract and agreement.
2. The sale and receipt of the bid document shall start from the date **25.10.2018 to 08.11.2018** up to 5.00 P.M. during the Working days. Bids will be sold and receipt in the office of the District Project Coordinator, RTE-SSA, Malkangiri.
3. The tender will be opened in the Office chamber of Collector, Malkangiri at 10.00 P.M. on dated **09.11.2018** in the presence of the Bidders or their authorised representatives having written authorization for the purpose.
4. The Bid document can be purchased from as mentioned under Para-2 against a non-refundable fee of **₹.4,000/- (Rupees Four thousand)** only towards cost of bid documents in the form of Demand Draft issued by any nationalized/ scheduled bank in favour of District Project Coordinator, RTE-SSA, Malkangiri and payable at State Bank of India, Malkangiri.
5. The authority will not be responsible if any portion of the bid document is modified and in all cases the conditions stipulated in the original document kept in the Office of the undersigned shall prevail.
6. Bidding documents will be Despatched by registered/speed post only. The Department will not be held responsible for the postal delay if any, in the delivery of the documents or non-receipt of the same.
7. If the tender documents sent through registered / speed post do not reach in the concerned office by the above date and time, the offer will not be considered on any account even if the tender documents were despatched by the tenderer before the due date.
8. The tender is to be submitted with AFFIDAVIT, EMD, DTCN duly filled in and signed by the contractor, attested copy of valid registration certificate, attested copy PAN card, attested copy GST No, attested copy of cast certificate with original AFFIDAVIT, No relation certificate, The envelope is to be sealed and super scribed as “**Construction of Addl. Class Room Building at Chitapari IV PS.**”, The Tenderers are not required to write their name on the outer cover containing the bid documents. They are only required to write the name of the work and authority who had issued the tenders. The tender should be submitted **through Registered Post/ Speed Post only.**
9. No tender paper will received by hand or courier service.
10. The contractors registered with State Government and contractors of equivalent Grade / class registered with Central Government / MES / Railways having registration for Civil, works having competency and expertise in Civil works need put tenders for this work.
11. The contract will be drawn in P.W.D. P-1 contract form.
The contract shall be drawn & signed by District Project Coordinator, on behalf of the Government of Odisha.
12. No tender documents will be sold to the intending tenderer beyond the date and time of sale mentioned in the tender notice.
13. No tenderers will be permitted to furnish their tender in their own manuscript papers. No letter should accompany the tender.
14. The tender should be strictly in accordance with the provisions as mentioned in the tender schedule. Any change in the wordings will not be accepted.
15. The work is to be completed in all respects within **4 (four)** calendar months from the date of issue of work order.
16. All tenders received will remain valid for a period of 90 days from the last date prescribed for receipt of tenders and validity of tenders can also be extended if agreed by the tenderers and the Department.
17. The bidder shall quote rate on % (percentage) basis only (% excess over / less than / equal) both in figure and words at appropriate place of Tender Schedule.
 - i. In case of percentage (%) rate tenders, only percentage quoted shall be considered. Percentage quoted by the Contractor shall be accurately filled in figures and words, so that there is no discrepancy.
 - ii. If any discrepancy is found in the percentage quoted in words and figures, then the percentage quoted by the Contractor in words shall be taken as correct.
 - iii. If any discrepancy is found in the percentage quoted in percentage excess / less and total rate quoted by the Contractor than percentage will be taken as correct.
 - iv. The percentage quoted in the tender without mentioned excess or less and not supported with the corresponding amount will be treated as excess. Where the Contractor has omitted to quote the rates either in figures and words, the officer opening the tender should record the omission.
 - v. Bills for percentage rate tenders shall be prepared at the estimated rates for individual items only and the percentage excess or less shall be added or subtracted from the gross amount of the bill.

- vi. No excess over and above the estimated rates shall be allowed in case the lowest tenderer fails to negotiate his rates to estimate rates, the documents shall be forwarded to higher authority for approval.

Amendment to Appendix-IX, Clause-36 of OPWD Code, Vol-II by inclusion

17.1 If the rate quoted the bidder is less than 15% of the tendered amount then such a bid shall be rejected and the tender shall be finalized basing on merits of rest bids. But if more than one bid is quoted at 14.99% (Decimals up to two numbers will be taken for all practical purposes) less than the estimated cost, the tender accepting authority will finalize the tender through a transparent lottery system. Where all bidders/their authorized representatives with other official members nominated for the purposes.

Amendment to Para-3.2.8 Note-II of OPWD Code, Vol-I by inclusion

17.2 In case of tender accepted below schedule of rate the tender amount excluding percentages shall be treated as sectioned amount and allotment will be limited to that extent any deviation in scope of work affecting the agreement amount in such an agreement will be governed by the relevant provision of OPWD Code.

Amendment to Para-3.5.18 Note-VIII of OPWD Code, Vol-I

17.3 Before acceptance of tender the successful bidder will be required to submit a work programme and milestone basing on the financial achievement so as to complete the work within the stipulated time and in case of failure on the part of the agency to achieve the milestone liquidated damage will be imposed.

18. Every page of the D.T.C.N. and tender paper should be signed by the tenderer failing, which the tender will be rejected.
19. The tenderer shall carefully study the tentative drawings and specifications applicable to the contract and all the documents, which will form a part of the agreement to be entered in to, by the accepted tenderer and detailed specifications for Odisha, and other relevant specifications and drawings, which are available. Complaint at a future date that the tenderers have not seen plans and specifications cannot be entertained.
20. The drawings furnished with the tender are tentative and subject to revision or modification as tendered during the execution as per actual necessity and detail test conducted. But the tendered rates quoted by the tenderer will hold good in case of such modification of drawings during the time of execution and shall in no way invalidate the contract and no extra monetary compensation will be entertained. The work shall however be executed as per final approved drawing to be issued by the Engineer-in-Charge as and when required. by admission of a tender for the work, a tenderer will be deemed to have satisfied himself by actual inspection of the site and locality of the work, about the quality and availability of the required quantity of material including the wheat/ rice referred to above, medical aid, labour and food stuff etc. and that rates quoted by him in the tender will be adequate to complete the work according to the specifications attached there to and that he had taken in to account all conditions and difficulties that may be encountered during its progress and to have quoted rates including labour and materials with taxes, octroi, other duties, lead, lifts, loading and unloading, freight for all materials and all other charges necessary for the completion of the work, to the entire satisfaction of the Engineer-in-Charge of the work and his authorised subordinates. After acceptance of the contract rate Government will not pay any extra charges for any reason in case the contractor claims later on to have misjudged as regard availability of materials, labour and other factors.
21. The bid must be accompanied by Earnest Money Deposit (EMD) of the amount @ 1% (One percent) of the estimated cost put to tender rounded to nearest hundred rupees i.e. **₹. 5600/-(Rupees Five thousand six hundred)** only along with tender in shape of **National Savings Certificate / Kissan Vikash Patra / Postal time deposit pass book/Term Deposit Receipt of any Schedule Bank** duly pledged in **favour of District Project Coordinator, RTE-SSA, Malkangiri**, as per the terms and conditions laid down in OGFR and in no other form. Bidders desirous to hire machineries or equipments from outside the State are required to furnish 2% (Two percent) of the amount put to tender in form of above shape and as per the above terms and conditions. Tenders not accompanied with EMD as specified above shall be liable for rejection. (N.B.: - Bank draft / Pay orders or Banker's cheque from any Scheduled Bank in favour of District Project Coordinator, shall not be considered as EMD).
22. The tender should be accompanied with the attested true copies of the valid Registration certificate, Valid G.S.T. No. and PAN card which are mandatory and the original certificates are to be produced within 3(three) days of opening of the tender before District Project Coordinator, Malkangiri for verification otherwise his/her bid shall be declared as non-responsive and thus liable for rejection.
23. The tender containing extraneous conditions not covered by the tender notice are liable for rejection and quotations should be strictly in accordance with the items mentioned in the Call Notices. Any change in the wording will not be accepted.
24. Letters found in the envelope or lowering the rates or dealing with any point in connection with the tender and regarding adjustment of E.M.D. or any other matter will not be considered.
25. The department reserves the right of authority to reject any or all tenders received without assigning any reason whatsoever.
26. The earnest money will be retained in the case of successful tenderers and will be dealt with as per terms

- and condition of O.P.W.D. Code the earnest money will be refunded to the unsuccessful tenderers on application after intimation is sent for rejection of their tenders. The retention of E.M.D. with the Department will carry no interest.
27. The Engineer-in-charge will notify the bidder / tenderer whose bid has been accepted for the award prior to expiration of the validity period by cable, telex or facsimile confirmed by registered letter. This letter (hereinafter and in the conditions of Contract called the "Letter of Acceptance") will state the sum that the Engineer-in-charge will pay the contractor in consideration of the execution, completion and maintenance of the Works by the contractor as prescribed by the contract (Hereinafter and in the contract called the "Contract Price").
- The Notification of award will constitute the formation of the contract, subject to only to the furnishing of a performance security and (Initial Security Deposit) in form of **N.S.C/K.V.P/ postal time deposit pass book/ Term Deposit Receipt of any Schedule Bank** duly pledged in favour of the **District Project Coordinator, RTE-SSA, Malkangiri** and in no other form which including the amount already deposited as bid security (earnest money) shall be 2% of the value of the tendered amount and sign the agreement in the P.W.D. form No.P-1 (Schedule XLV No. 61) for the fulfilment of the contract in the office of the District Project Coordinator, RTE-SSA, Malkangiri as directed. The security deposit together with the earnest money and the amount withheld according to the provision of P-1 agreement shall be retained as security for the due fulfilment of this contract and additional performance security in accordance with the provisions of the agreement. The agreement will incorporate all agreements between the officer inviting the bid/Engineer-in-Charge and the successful bidder within 15 days following the notification of award along with the Letter of Acceptance. The successful bidder will sign the agreement and deliver it to the Engineer-in-Charge. Following documents shall form part of the agreement
- a) The notice-inviting bid, all the documents including additional conditions, specifications and drawings, if any, forming the bid as issued at the time of invitation of bid and acceptance thereof together with any correspondence leading thereto & required amount of performance security including additional performance security.
 - b) Standard P.W.D. Form P-1 with latest amendments.
- Failure to enter in to the required agreement and to make the security deposit as above shall entail forfeiture of the Bid Security (earnest money). No contract (tender) shall be finally accepted until the required amount of initial security money is deposited. The security will be refunded after (12) twelve months of completion of the work and payment of the final bill and will not carry any interest (As per order No. 17823 dtd. 11.10.2006 of Works Department.
28. The contractor should be liable to fully indemnify the Department for payment of compensation under workmen compensation act. VIII of 1923 on account of the workmen employed by the contractor and full amount of compensation paid will be recovered from the contractor.
29. Tenderers are required to liable by fair wages clause as introduced by the latest Govt. of Odisha, Works Department.
30. The contractor shall bear cost of various incidentals, sundries and contingencies necessitated by work in full within the following or similar category.
- a) Rent royalties, cess and other charges of materials, Octroi and all other taxes including prevailing sale tax / GST from time to time. Ferry tolls, conveyance-charges and other cost on account of land buildings including temporary building required by the tenderer for collection of materials, storage, housing of staff or other purpose of the work are to be borne by the contractor at his own cost. No rent will be payable to Govt. for temporary occupation of land owned by govt. at the site of the work for bonafied use of the land for work and all such construction of temporary nature by the contractor shall be done after obtaining written permission from the Engineer-in-Charge of Civil portion of the work and all such construction shall have to be demolished and debris removed and ground made good and cleared after completion of the work at no extra cost.
 - b) Royalty will be recovered from each bill as notified by Govt. from time to time unless K-Forms are enclosed. Refund of royalty at later date after passing of the bills cannot be entertained as the recovery of royalty is being credited to revenue.
 - c) Labour camps or huts necessary to a suitable scale including conservancy and sanitary arrangements therein to the satisfaction of the local labour laws and health authorities shall have to be provided by the Contractor.
 - d) Arrangement of suitable water supply including pipe water supply where available for the staff and labour as well as for the execution of the work is sole responsibility of the Contractor and no extra cost for carriage of water will be entertained.
 - e) All fees and dues levied by Municipal, Canal or Water Supply Authorities are to be borne by the Contractor.
 - f) Suitable safety equipments and dresses, gloves, life belts etc. for the labour engaged in risky operations are to be supplied by the contractor at his own cost.
 - g) Suitable fencing barriers, signals including paraffin and electric signals where necessary at work and approaches in order in project the public and employees from accident has to be provided by the

Contractor at his own cost.

- h) Compensation including cost of any legal suit for injury to persons or property arising out of execution of the work and also any sum, which may become payable due to operation of the workmen compensation act, shall have to be borne by the contractor.
 - i) The contractor has to arrange adequate lighting arrangements for the work wherever necessary at his own cost.
31. No payment will be made for layout, benchmark, level pillars, profiles and benching and levelling the ground required, which has to be carried out by the contractor at his own cost. The rates to be quoted should be for finished items of work inclusive of carriage of all materials and all incidental items of work.
 32. After the work is finished all surplus materials should be removed from the site of work, preliminary work such as vats, mixing platforms, etc. should be dismantled and all materials removed from the site and premises left neat and his should be inclusive in the rates. No extra payment will be made to the Contractor in this account.
 33. It should be understood clearly that no claim what-so-ever will be entertained to extra items of works quantity of any item besides estimate amount unless written order is obtained from the competent authority and rate settled before the extra items of work or extra quantity of any items of work is taken up.
 34. No part of the contract shall be sublet without written permission to the concerned District Project Coordinator, RTE-SSA, Malkangiri or transfer be made by the power of attorney authorising others to receive payment on contractors behalf.
 35. Bid documents consisting of plans, specifications, the schedule of quantities and the set of terms and conditions of contract and other necessary documents can be seen in all the offices issuing the documents and office of the under signed during office hours every day except on Sundays and Public Holidays till last date of sale and receipt of tender papers. Interested bidders may obtain further information at the same address. But it must be clearly understood that tenders must be received in order and according to instructions in complete shape. Incomplete tender is liable for rejection.
 36. No Relation certificate.
The contractor shall furnish a certificate along with the tender to the effect that he is not related to any officer in the rank of an Senior Technical Consultant & above in the state P.W.D. or Assistant/Under Secretary & above in the Works Department. If the fact subsequently proved to be false, the contract is liable to be rescinded. The earnest money & the total security will be forfeited & he shall be liable of make good to damages the loss or damages resulting for such cancellations. The proforma for no relationship certificate is contained in a separate sheet vide Schedule-A.
 37. All items of work as per schedule of quantities of this tender should confirm to Odisha Detailed Standard Specification, as per the PWD specification and latest provisions of relevant clauses.
 38. Shuttering & centring shall be with suitable steel shutters in side of which shall be lined with suitable sheeting and made leak proof and watertight. All joints in formwork shall be properly sealed preferably with P.V.C. joints sealing tapes & compounds.
 39. Form work including complete false work shall be designed by the Contractor without any extra cost to employer and the Department will have the right to inspect the scaffolding, centring and shuttering made for the work and can reject partly or fully such structures, if found defective in their opinion. Any eventually such as loss of lives or property due to failure of centring and shuttering shall be the responsibility of the Contractor regarding compensation of all claims thereof.
 40. Cement Concrete should be machine mixed by weight by means of concrete mixture/batching plant confirming to relevant grade and approved by the Engineer-in-charge for all types of concrete works. The Contractor should arrange his own batching plant concrete mixer appropriate vibrators, pumps, etc. for this purpose at his own cost and departmental machinery If available only may be utilised on payment of necessary hire charges as detailed in clause of recovery sheet on necessary requisition.
 41. Cement shall be used by bags and weight of one bag of Cement should be 50 (fifty) Kg. net & the Engineer-in-Charge or his representative shall have the right to test the weight & quality from time to time.
 42. The tenderers shall make all arrangements for proper storage of materials but no cost for raising shed for store and pay of security guard etc. will be borne by the Department. The department is not responsible for any theft or loss of materials at site. It is contractor's risk. Under any such plea, if the tenderer stops the work he shall have to pay the full penalty as per clauses of the contract.
 43. Approach road to site of work for transport of materials to site of work is sole responsibility of the Contractor. Statutory traffic restriction in the town area for Transport of construction material to site of work is to be taken in to consideration before tendering and no consideration for extra time or compensation thereof shall be considered.
 44. The contractor should at his own cost arrange necessary tools and plants required for efficient execution of work and the rates quoted should be inclusive of transportation, hire and running charges of such plant and cost of consumables.

45. The machineries if available, with the department may be supplied on hire as per charges noted in the enclosed statement and may be changed from time to time subject to the condition that the contractor will execute in advance an agreement with the Engineer-in-Charge.
46. No claim whatsoever will be entertained for supply of machineries.
47. An applicant or any of its constituent partners of whose contract for any work has been rescinded or who has abandoned any work in the last three years, prior to the date of the bid, shall be debarred from qualification. The tenderer must submit the required information of the DTCN. The tenderer is to furnish an affidavit in the specified format as per the DTCN. Regarding authentication of tender documents & information about any litigation & Bank guarantee etc. Non-furnishing of the information and required affidavit, the tender will be liable for rejection.
48. It should be clearly understood that:
- a) The joints of the bars are to be provided with lapping, welds or bolts nuts as well be directed by the Engineer-in-charge.
 - b) Concrete test specimens 150mm × 150mm × 150mm in size (whether plain or reinforced concrete) for the testing shall be taken for each structural member by a representative of the contractor in the presence of responsible officer of the rank not lower than that of an Senior Technical Consultant/ Sub-Divisional Officer. The contractor shall bear the cost so involved in testing. The test specimen in cube should be carried out in the Departmental Control and Zonal Laboratory at Berhampur. Test should be carried out in accordance with the stipulation in Bridges code section-III.
 - c) Test specimens shall be formed carefully in accordance with the standard method of taking test specimen and no plea shall be entertained later on the grounds that the casting of the test specimen was faulty and that the result of the specimen did not give a correct indication of the actual quality of concrete.
 - d) Plain concrete and reinforced concrete specimens will be tested in Government Test Houses at Alipore or Zonal Laboratory at Berhampur. Cost of testing of all specimens and samples will be borne by the Contractor.
49. The rates quoted should be inclusive of carriage of water required in connection with execution of the work. No claim for carriage of water whatsoever will be entertained.
50. It is the responsibility of the contractor to procure and store explosive required for blasting operation. Department may render necessary possible help for procuring license.
51. For submission of a tender for the work, the tenderer will be deemed to have satisfied himself by actual inspection of the site and locality of the work about the quality and availability of the required quantity of materials, Medical aid, labour and Flood stuff etc. And that the rates quoted by him in the tender will be adequate to complete the work according to the specifications attached thereto and that he had taken in to account all conditions and difficulties that may be encountered during its progress and to have quoted labour rates and materials with taxes, Octroi and other duties lead, lifts, loading and unloading freight for materials and all other charges necessary for the completion of the work to the entire satisfaction of the Engineer-in-charge of the work and his authorised subordinates. After acceptance of the contract rates Government will not pay any extra charges for any reason in case the contractor finds later on to have misjudged the conditions as regards the availability of materials, labour and other factors.
52. The contractor will be responsible for any misuse, loss or damages due to any reasons whatsoever of any departmental material during the execution of work. In case of loss, damage or misuse, recovery at the rate at 5 times the cost of the materials will be deducted from the bills or his other dues.
54. The prevailing percentage of I.T. Department of the gross amount of the bill towards income tax will be deducted from the contractor's bill.
55. Prevailing rate of GST on the gross amount of the bill will be deducted from the contractor's bill, It must be clearly understood that under no circumstances any interest is chargeable for the dues or additional dues if any payable for the work executed and final bill pending disposal due to any reason whatsoever.
56. No extra payment will be made for removing spreading and consolidating salvaged metals and materials.
57. Under section 12 of contractors labour (Regulation and Abolition) Act. 1970 the contractor who undertakes execution of work through labour should produce valid license from licensing authorities of labour Department. Within one month of starting the work.
58. **Performance Security**
Amendment to Para-3.5.5(V) of OPWD Code, Vol-I by modification
59. **Additional Performance Security Deposit-** Additional Performance Security shall be obtained from the bidders, when the bid amount is less than the estimated cost put to tender. In such an event, only successful bidders who have quoted less bid price/rates than the estimated cost put to tender shall have to furnish the exact amount of differential cost. ie, Estimated cost minus the quoted amount as Additional Performance Security Deposit in shape of **N.S.C/K.V.P/ Postal time deposit pass book/Term Deposit receipt** duly pledged in **favour of District Project Coordinator, RTE-SSA, Malkangiri**, within seven days otherwise the bid shall be cancelled and security deposit shall be forfeited further proceeding for black listing shall be initiated against (as per Govt of Odisha works department office memorandum no. **14299 dtd.03.10.2017** and amendment of para no 3.5.5 (V) of OPWD code volume 1).

60. Sample of all material - The contractor shall supply sample of all materials fully before procurement for the work for testing and acceptance as may be requiring by the concerned Sr. TC, RTE-SSA, Malkangiri.
61. An engineering personnel of the executing agency should be present at work site at the time of visit of High level Inspecting officers.
62. All reinforced cement work should conform to Odisha Detailed specification and should be of proportion M-15 and M-20 having a minimum compressive strength (in work test) 150Kg/200Kg: per Cm² in 15 Cm cubes at 28days, after mixing and test conducted in accordance with IS 456/2000 and IS 516 using 12mm to 20mm. size hard black crusher broken granite chips (20mm size not be exceed 25%).
63. Bailing out of water from the foundation, pipeline trenches S. Tanks/Soak pits/Sumps/M.H. etc. either rainwater or sub-soil water if necessary should be borne by the contractor. No payment will be made for benchmarks. Level pillars, profiles and benching and levelling the ground wherever required. The rates quoted should be for finished items of works inclusive of these incidental items of work.
64. It should be understood clearly that no claims whatsoever would be entertained.
65. The tenderer shall have to abide by the C.P.W.D. safety code rules introduced by the Government of India, Ministry of work Housing and Supply in their standing order No-44150 dtd.25.11.57.
66. The Contractor will have to submit to the District Project Coordinator, RTE-SSA, Malkangiri monthly return of labour both skilled and unskilled employed by him on the work.
67. All fittings for doors and windows as supplied by the Contractor should be of best quality and conform to relevant I.S. specification and should be got approved by the Engineer-in-charge before they are used on the work.
68. After completion of the work the contractor shall arrange at his own cost all requisite equipments for testing buildings, if found necessary and bear the entire cost of such test.
69. All reinforced cement concrete works should be finished smooth Extra charges for plastering if required to any R.C.C. structures like roof slab, Columns, Chajjas, fins, parapets, shelves etc. shall not be paid.
70. The tenderer may at his option quote reasonable rate for each item of work carefully so that the rate for one item should not be unworkably low and for others too high.
71. If there is any damage to the work due to natural calamities like flood or cyclone or any other cause during the course of execution of work or up to 12 months after completion of work or if any, imperfection becomes apparent to the work within 12 months from the date of final certificate of completion of work the contractor shall make good of all such damages at his own cost with no extra cost to the Department. No claims, whatsoever, in this regard will be entertained.
72. The C.B. bricks should be well burnt and of good qualities. The bricks should be approved by the Engineer-in-charge before use in the work and should conform to the minimum strength as per National Building Code.
73. Under Section 1 of contract labour Regulation and Abolition Act 1970 the contractor who undertakes execution of work through labour should produce valid licence from the licensing authority of labour Department. Within one month of starting the work.
74. Standard co-efficient for linear measurement will be adopted while calculating consumption of steel and no claim whatsoever regarding difference in co-efficient of steel will be entertained. The rates quoted shall be inclusive of any eventuality of difference for co-efficient for linear measurements.
75. Engineering Contractors desiring to avail the exemption facility of EMD should submit an original affidavit as regards, the fact of availing award of work without submission of EMD/ISD during the current financial year. He should also produce original contract licence at the time of opening of tender document to make necessary entry to that effect as such facilities are limited to three participation in tender during a financial year. Otherwise their tender will be liable for rejection.
76. That for the purpose of jurisdiction in the event of disputes if any of the contract would be deemed to have been entered in to within the State of Odisha and it is agreed that neither party to the contract will be competent to bring a suit in regard to the matter by this contract at any place outside the State of Odisha.
77. SPECIAL CONDITIONS (PART OF THE CONTRACT)
 - (i) All materials before they are being used in the items of works as per this Schedule of quantities and also the finished items of work where tests are applicable shall have to be tested through the Engineer-in-charge of the respective wing at appropriate Laboratories according to the relevant I.S. specifications of the materials and the said items of works and the cost of all such tests shall have to be borne by the Contractor and the rates of the items of works should be inclusive of cost of such tests.
 - (ii) The tests have to be planned & carried out such that the progress of work is not hampered
 - (iii) The tests are mandatory as per the prescribed frequencies and I.S. specifications. However, these are not exhaustive and the Engineer-in-charge has the right to prescribe other required test if any as will be considered from time to time.
78. In case of ambiguity between clauses of this D.T.C.N. and the P-1 contract form, the relevant Clauses of the P-1 contract form shall prevail over the D.T.C.N. The clauses not covered under P-1 contract form shall be governed by the clauses of the D.T.C.N.
79. It must be definitely understood that the Government does not accept any responsibility for the correctness and completeness of the trial borings shown in the Cross Section.

80. Schedule of quantities is accompanied in the Bid. It shall be definitely understood that the Government does not accept any responsibility for the correctness or completeness of this schedule and that this schedule is liable for alternation or omissions, deductions or alternations set forth in the conditions of the contract and such omissions, deductions, additions or alternations shall no way invalidate the contract and no extra monetary compensation, will be entertained.
81. In case of any complaint by the labour working about the non payment or less payment of his wages as per latest minimum Wages Act, the Senior Technical Consultant, RTE-SSA, Malkangiri will have the right to investigate and if the contractor is found to be in default, he may recover such amount due from the contractor and pay such amount to the labour directly under intimation to the local labour office of the Govt. The contractor shall not employ child labour. The decision of the DPC, Malkangiri is final and binding on the contractor.
82. The contractor should arrange the materials like Steel, Cement, paint and bitumen etc. of approved quality and specification at his own cost for completion of the work with the time schedule. No extension of time will be granted on the application of the contractor due to delay in procurement of materials.
83. If the contractor removes Government materials supplied to him from the site of work with a view to dispose of the same dishonestly, he shall be in addition to any other liability civil or criminal arising out of his contract be liable to pay a penalty equivalent to five times of the price of the materials according to the stock issue rate or market rate whichever is higher. The penalty so imposed shall be recovered at any time from any sum that may then or at any time thereafter become due to the contractor or from his security deposit or from the proceeds of sale thereof.
84. Though Departmental issue of cement and steel has indicated, it may not be taken as binding. The contractor must have to arrange by themselves cement, steel, bitumen and every sort of materials from approved manufacturer, get it tested in the Departmental Laboratory and approved by the Department before use. No extension of time or escalation of price on such account shall be entertained in future.
85. TOR rods, plates and structural members will be supplied in quantity, length and size available in the stock. For payment of reinforcement, the steel including plates etc. shall be measured in length of different diameter, size and specification as actually used (including hooks and cranks) in the work correct to an inch or cm. and their weight calculated as per sectional weight prescribed by the Indian Standard Specification or as directed by the Engineer-in-Charge (Wastage of bars and unnecessary lapping will not be considered for measurement and payment).
86. The contractor should at his own cost arrange necessary tools and plants required for the efficient execution of work and the rates quoted should be inclusive of the running charges of each plant and cost of conveyance.
87. The contractor is required to pay royalty to Govt. as fixed from time of time and produce such documents in support of their payment to the concerned Senior Technical Consultant with their bills, falling which the amount towards royalties of different materials as utilised by them in the work will be recovered from their bills and deposited in the revenue of concerned department.
88. Under no circumstances interest is chargeable for the dues or additional dues if any payable for the work.
89. Trial Boring - The foundation level as indicated in the body of the departmental drawing is purely tentative and for the general guidance only. The Department has no responsibility for the suitability of actual strata at the foundation level. The contractor has to conduct his own boring before starting the work and get the samples tested at his own cost to ascertain the S.B.C. and credibility of the strata at founding level while quoting his rates for tender the contractor shall take in to account of the above aspects.
90. Any defects, shrinkage or other faults which may be noticed within 12 (Twelve) months from the completion of the work arising out of defective or improper materials or workmanship timing are upon the direction of the Engineer-in-Charge to be amended and made good by the contractor at his own cost unless the Engineer for reasons to be recorded in writing shall be decided that they ought to be paid for and in case of default Department may recover from the contractor the cost of making good the works. The contractor is also required to maintain the road/ building for 12 (Twelve) months from the date of successful completion of the work.
91. From the commencement of the works to the completion of the same, they are to be under the contractors charge. The contractor is to be held responsible to make good all injuries, damages and repairs occasioned or rendered necessary to the same by fire or other causes and they hold the Govt. of Odisha harmless for any claims for injuries to person or structural damage to property happening from any neglect, default, want of proper care or misconduct on the part of the contractor or any one in his employment during the execution of the work. Also no claim shall be entertained for loss due to earthquake, flood, cyclone, epidemic, riot or any other calamity whether natural or incidental damages so caused will have to be made good by the contractor at his own cost.
92. Gradation of ingredients: The coarse and fine aggregate shall meet the grade requirement as per the latest provision of relevant I.S. Code / I.R.C. code / MORT&H specifications.

93. Where it will be found necessary by the Department, the Officer-in-Charge of the work shall issue an order book to the contractor to be kept at the site of the work with pages serially numbered. Orders regarding the work whenever necessary are to be entered in this book by the Senior Technical Consultant, RTE-SSA, Malkangiri with their dated signatures and duly noted by the contractor or his authorised agents with their dated signature. Orders entered in this book and noted by the contractor's agent shall be considered to have been duly given to the contractor for following the instructions of the Department. The order Book shall be the property of the DPC, Malkangiri and shall not be removed from the site of work without written permission of the Engineer (Sr. TC) and to be submitted to the Engineer-in-charge every month.
94. The contractor should attach the certificate in token of payment deposit with the registration authority as per recent circular of the Government relating to his registration.
95. The rates quoted by the contractor shall cover the latest approved rates of labours, materials, P.O.L. and Royalties. Arrangement of borrows areas; land, approach road to the building site etc. are the responsibility of the contractor.
96. The rate for each work of concrete items wherever dewatering is imperatively necessary the term dewatering shall mean the execution or operation of the items due to standing water as well as due to percolation of water. The quoted rates will be inclusive of this.
97. In case the 1st lowest tenderer or even the next lowest tenderers withdraw in series one by one, thereby facilitating a particular tender for award, then they shall be penalized with adequate disincentives with forfeiture of EMD unless adequate justification for such back out is furnished. Appropriate action for black listing the tenderers shall also be taken apart from disincentivising the tenderer.
98. ELIGIBILITY CRITERIA: To be eligible for qualification, applicants shall furnish the followings.
- a. Required E.M.D as per the Clause No. 22.
 - b. Copy of valid Registration Certificate, Valid GST Registration No, PAN card along with the tender documents and furnish the Original Registration certificate and Pan card for verification within 3 (three) days of opening of the tender before District Project Coordinator, RTE-SSA, Malkangiri as per Clause No. 23.
 - c. Information regarding current litigation, debarring / expelling of the applicant or abandonment of work by the applicant and affidavit to that effect including authentication of tender documents as per clause 49.
 - d. License criteria as per Clause No.10
 - e. Authority to seek references from the Bidder's bankers;
 - f. The proposed methodology and programme of construction backed with equipment and material planning and deployment, duly supported with broad calculations and Quality Management Plan proposed to be adopted, justifying their capability of execution and completion of the work as per technical specifications and within the stipulated period of completion.
99. AMMENDMENT TO THE CONDITION OF F2 CONTRACT
Clause-2(a) of F2 Contract:-TIME CONTROL:-
- 2.1. Progress of work and Re-scheduling programme.
 - 2.1.1. The District Project Coordinator, RTE-SSA, Malkangiri shall issue the letter of acceptance to the successful contractor. The issue of the letter of acceptance shall be treated as closure of the Bid process and commencement of the contract.
 - 2.1.2. Within 15 days of issue of the letter of acceptance, the contractor shall submit to the Engineer-in-Charge for approval a Programme commensurate to Clause no.15 showing the general methods, arrangements, and timing for all the activities in the Works along with monthly cash flow forecast.
 - 2.1.3. To ensure good progress during the execution of the work the contractors shall be bound in all cases in which the time allowed for any work exceeds one month to complete, 1/4th of the whole time allowed under the contract has elapsed, 1/2 of the whole of the work before 1/2 of the whole time allowed under the contract has elapsed, 3/4th of the whole of the work before 3/4th of the whole time allowed under the contract has elapsed.
 - 2.1.4. If at any time it should appear to the Engineer-in-Charge that the actual progress of the work does not conform to the programme to which consent has been given the Contractor shall produce, at the request of the Engineer-in-Charge, a revised programme showing the modifications to such programme necessary to ensure completion of the works within the time for completion. If the contractor does not submit an updated Programme within this period, the Engineer-in-Charge may withhold the amount of 1% of the contract value from the next payment certificate and continue to withhold this amount until the next payment after the date on which the overdue Programme has been submitted.
 - 2.1.5. An update of the Work Programme shall be a programme showing the actual progress achieved, on each activity and the effect of the progress achieved on the timing of the remaining work including any changes to the sequence of the activities.
 - 2.1.6. The Engineer-in-Charge's approval of the Programme shall not alter the Contractor's obligations. The Contractor may revise the Programme and submit it to the Engineer-in-Charge again at any time. A revised Programme is to show the effect of Variations and Compensation Events.
 - 2.2. Extension of the Completion Date.

- 2.2.1. The time allowed for execution of the works as specified in the Contract data shall be the essence of the Contract. The execution of the works shall commence from the 15th day or such time period as mentioned in letter of Award after the date on which the DPC, Malkangiri issues written orders to commence the work or from the date of handing over of the site whichever is later. If the Contractor commits default in commencing the execution of the work as aforesaid, Government shall without prejudice to any other right or remedy available in law, be at liberty to forfeit the earnest money & performance guarantee / Security deposit absolutely.
- 2.2.2. As soon as possible after the Agreement is executed, the Contractor shall submit the Time & Progress Chart for each milestone and get it approved by the Department. The Chart shall be prepared in direct relation to the time stated in the Contract documents for completion of items of the works. It shall indicate the forecast of the dates of commencement and completion of various trades of sections of the work and may be amended as necessary by agreement between the DPC Malkangiri and the Contractor within the limitations of time imposed in the contract documents, and further to ensure good progress during the execution of the work, the contractor shall in all cases in which the time allowed for any work, exceeds one month (save for special jobs for which a separate programme has been agreed upon) complete the work as per milestone given in contract data.
- 2.2.3. In case of delay occurred due to any of the reasons mentioned below, the Contractor shall immediately give notice thereof in writing to the DPC, Malkangiri but shall nevertheless use constantly his best endeavours to prevent or make good the delay and shall do all that may be reasonably required to the satisfaction of the Engineer-in-Charge to proceed with the works.
- i) Force major, or
 - ii) Abnormally bad weather, or
 - iii) Serious loss or damage by fire, or
 - iv) Civil commotion, local commotion of workmen, strike or lockout affecting any of the trades employed on the work, or.
 - v) Delay on the part of other contractors or tradesmen engaged by Engineer-in-Charge in executing work not forming part of the Contract.
 - vi) In case a Variation is issued which makes it impossible for Completion to be achieved by the Intended Completion Date without the Contractor taking steps to accelerate the remaining work and which would cause the Contractor to incur additional cost, or Any other cause, which, in the absolute discretion of the authority mentioned, in Contract data is beyond the Contractors control.
- 2.2.4. Request for reschedule and extension of time, to be eligible for consideration, shall be made by the Contractor in writing within fourteen days of the happening of the event causing delay. The Contractor may also, if practicable, indicate in such a request the period for which extension is desired.
- 2.2.5. In any such case a fair and reasonable extension of time for completion of work may be given. Such extension shall be communicated to the Contractor by the DPC Malkangiri in writing, within 3 months of the date of receipt of such request. Non-application by the contractor for extension of time shall not be a bar for giving a fair and reasonable extension by the DPC, Malkangiri and this shall be binding on the contractor.
- 2.3. Compensation for Delay.
- 2.3.1. If the contractor fails to maintain the required progress in terms of clause 2 or to complete the work and clear the site on or before the contract or extended date of completion, he shall, without prejudice to any other right or remedy available under the law to the Government on account of such breach, pay as agreed compensation the amount calculated at the rates stipulated below as the Superintending Engineer (whose decision in writing shall be final and binding) may decide on the amount of tendered value of the work for every completed day / month (as applicable) that the progress remains below that specified in Clause 2 or that the work remains incomplete.
- This will also apply to items or group of items for which a separate period of completion has been specified. Compensation @ 1.5% per month of for delay of work, delay to be completed on per Day basis. Provided always that the total amount of compensation for delay to be paid under this condition shall not exceed 10% of the Tendered Value of work or to the Tendered Value of the item or group of items of work for which a separate period of completion is originally given.
- The amount of compensation may be adjusted or set-off against any sum payable to the Contractor under this or any other contract with the Government. In case, the contractor does not achieve a particular milestone mentioned in contract data, or the rescheduled milestone(s) in terms of Clause 2.5, the amount shown against that milestone shall be withheld, to be adjusted against the compensation levied at the final grant of extension of time. Withholding of this amount on failure to achieve a milestone shall be automatic without any notice to the contractor. However, if the contractor catches up with the progress of work on the subsequent milestone(s), the withheld amount shall be released. In case the contractor fails to make up for the delay in subsequent milestone(s), amount mentioned against each milestone missed subsequently also shall be withheld. However no interest whatsoever shall be payable on such withheld amount.

2.4. Incentive for early completion

Amendment to Para-3.5.5(V) Note-III of OPWD Code, Vol-I by modification

2.4.1 For availing incentive clause in any project which is completed before the stipulated date of completion. Subject to other stipulations it is mandatory on the part of the concerned Executive Engineer to report the actual date of completion of the project as soon as possible through fax or e-mail so that the report is received within 7 (seven) days of such completion by the concerned Superintending Engineer, Chief Engineer & the Administrative Department. The incentive for timely completion should be on a graduated scale of 1 (one) percent to 5 (five) percent of the contract value. Assessment of incentives may be worked out for earlier completion of the work in all respect in the following scale;

Before 30% of contract period	=5% of Contract Value
Before 20% to 30% of contract period	=4% of Contract Value
Before 10% to 20% of contract period	=3% of Contract Value
Before 5% to 10% of contract period	=2% of Contract Value
Before 5% of contract period	=1% of Contract Value

2.5 Management Meetings

2.5.1 Either the Engineer or the Contractor may require the other to attend a management meeting. The business of management meetings shall be to review the plans for remaining work and to deal with matters raised in accordance with the early warning procedure.

2.5.2 The Engineer shall record the business of management meetings and is to provide copies of his record to those attending the meeting and to the Employer. The responsibility of the parties for actions to be taken to be decided by the Engineer either at the management meeting or after the management meeting and stated in writing to all who attended the meeting.

Clause-2 (b) of Percentage Rate P-1 Agreement:- Rescission of Contract (Amendment as per letter No.8310 dt 17.05.2006 of Works Department, Odisha):-

To rescind the contract (of which rescission notice in writing to the contractor under the hand of the Executive Engineer shall be conclusive evidence), 20% of the value of left over work will be realised from the contractor as penalty.

100. The tenderers are required to go through each clause of Form P-1 includes existing provisions of PWD Code and amendments made there to carefully in addition to the clauses mentioned here in before tendering.

Total No. of Clauses 100 (One hundred only)

SCHEDULE-A

CERTIFICATE OF NO RELATIONSHIP

I/We hereby certify that I/We* am/are* related/not related(*) to any officer of DPC office Malkangiri of the rank of Senior Technical Consultant & above and any officer of the rank of Assistant / Under Secretary and above of the Works Department, Govt. of Odisha I/We* am/are* aware that, if the facts subsequently proved to be false, my/our* contract will be rescinded with forfeiture of E.M.D and security deposit and I/We* shall be liable to make good the loss or damage resulting from such cancellation.

I/We also note that, non-submission of this certificate will render my / our tender liable for rejection.

(*) - Strike out which is not applicable

Signature of the Tenderer

Date:-

SCHEDULE-“C”

INFORMATION REGARDING CURRENT LITIGATION, DEBARRING EXPELLING OF TENDERED OR
ABANDONMENT OF WORK BY THE TENDERER

1. a) Is the tenderer currently involved in any litigation relating to the works. Yes / No
b) If yes: give details:
2. a) Has the tenderer or any of its constituent partners been debarred/ expelled by any agency in India during the last 5 years. Yes / No
3. a) Has the tenderer or any of its constituent partners failed to perform on any contract work in India during the last 3 years. Yes / No
b) If yes, give details:

Note:

If any information in this schedule is found to be incorrect or concealed, qualification application will be summarily be rejected.

Signature of the Tenderer

SCHEDULE -D

AFFIDAVIT

- 1.The undersigned, do hereby certify that all the statements made in the required attachments are true and correct.
- 2.The undersigned also hereby certifies that neither our firm M/s _____ nor any of its constituent partners have abandoned any road/ bridge/Irrigation /Buildings or other project work in India nor any contract awarded to us for such works have been rescinded during the last three years prior to the date of this bid.
- 3.The undersigned hereby authorised and request (s) any bank, person, firm or Corporation to furnish pertinent information as deemed necessary and as requested by the Department to verify this statement or regarding my (our) competency and general reputation.
- 4.The undersigned understands and agrees that further qualifying information may be requested and agree to furnish any such information at the request of the Department.

(Signed by an Authorised Officer of the firm)

Title of Officer

Name of Firm

Date:

101. Sold for the work as “**Construction of Addl. Class Room Building at Chitapari IV PS**” at an estimated cost of ₹. **553755.00/- (Rupees Five lakh fifty three thousand seven hundred fifty five)** only on payment of ₹.**4000/- (Rupees four thousand)** only vide Money Receipt No. _____ Dt. _____ against Demand Draft No. _____ Dt _____ payable at Malkangiri.

For official use only

01. E.M.D.	Furnished / Not furnished
	Rs. _____
	in shape of _____
	Pledged/Not Pledged
02. Valid Registration certificate :-	copy furnished/Not furnished
03. PAN Card :-	copy Furnished/Not furnished
04. G.S.T No :-	copy Furnished/Not furnished.
05. Nos. of Tender paper: -	_____

Total :-24 (Twenty four) Sheets only

APPROVED

-sd-

District Project Coordinator,
RTE-Malkangiri

TENDER SCHEDULE

NAME OF THE WORK:- CONSTRUCTION OF ADDL. CLASS ROOM BUILDING AT CHITAPARI IV PS

Sl. No	Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
1	Earth work in excavation of foundation trenches in ordinary soil except sheet rock and boulders (requiring blasting) including dressing and leveling the bed upto the required depth and depositing the excavated materials away from the site with all leads and lifts. T & P shoring and shuttering if required etc. complete as directed by engineer- in charge.	Cum	37.50	134.40	5040.00
2	Supplying and filling in foundation and ditches with sand well watered and rammed in layers not exceeding 23 cm in depth with all lead and lift including cost, conveyance, loading and unloading , royalties and taxes of all materials and cost of all labour, sundries. T & P required for the work etc complete in all respect as per direction of Engineer incharge.	Cum	32.25	325.10	10484.48
3	Providing & laying plain cement concrete 1:4:8 (1 cement 4 coarse and 8 graded stone aggregate fo 40 mm nominal size) in foundation and pinth including cost of hoisting, lowering laying concrete, ramming , watering and curing etc. complete to required levels laid in layers not exceeding 15cm thick including cost. Conveyance, loading and unloading, royalties and taxes all materials and cost of all labours, sundnes, T & P required for the work complete including dewatering if required as epr instrucion of Engineer-in- charge.	Cum	8.99	3323.70	29880.06
4	RR stonemasonay in cemnet mortar of (1.6) with portland slag cement , watering and curing etc. including cost, conveyance, loading and unloading, royalties and taxes of all materials and cost of all lbaour sundries T& P required for the works etc complete in all respect as directed by the Enginner -in-charge.	Cum	13.87	2508.40	34791.51
5	Providing and laying C.B brick masonry work in super structure throughly soked in water with cement mortora (1:6) including necessary scaffolding, racking out joints, curing, etc. complete. As per specification and direction of the Engineer-in -charge.	Cum	18.57	3278.60	60883.60
6	i. Providing , lifting hoisting laying Reinforced cement concrete of M20 grade in column footings , as per approved designs and drawings having a munimum compressive strength (in work test) 200 Kg./ Square cm in 15cm. Cubes at 28 days after mixing and tests conducted in accordance with I.S. 416 using 12mm to 20 mm size black hard crusher broken granite stone ships of approved quality from approved quarry washed and cleaned (20mm size not to exceeds 25%) to be mixed in concrete mixture with ordinary protland cement (OPC) including noisting, lowering lying an dcompacting concrete by susing vibrators, watering and curing for 28 days centering and shuttering and finishing the exposed surface smooth proving grooves or beads wherever necessary including cost conveyance, loading and unloading royalties and taxes of all materials and cost of all labours sunones , T & P required fo rthe work ect complete in all respect excluding cost and conveyance of HYS/MS steel and binding wires, and labour charges for straighttaining, cutting, bending etc of M.S. rods of for steel and binding				
a	Column Base	Cum	6.40	4762.50	30480.00
b	Column Up to Plinth	Cum	1.54	9018.60	13888.64
c	Grade Beam	Cum	2.11	5873.80	12393.72
d	Lintel Beam	Cum	1.41	7672.80	10818.65
f	Ring Beam	Cum	2.73	9018.60	24620.78
g	Chajja	Cum	0.58	10175.60	5901.85
h	Roof Slab	Cum	8.04	8095.40	65087.02

7	Cutting, bending binding and placing in position of reinforcement steel for RCC work including cost of binding wire, steel, tools etc. complete.	Qntl	20.05	6546.70	131236.13
8	25mm thick grading plaster with C.M. (1:4) over roof slab complete in all respect.	Cum	63.15	220.90	13949.84
9	Supplying, fitting and fixing of M.S Door, M. S grill for windows and ventilators including cost of labour, material transportation etc. complete.				
	a) Door	Kg	167.86	81.00	13596.34
	b) Window	Kg	167.25	78.50	13129.13
10	Labour for Fitting fixing of doors/windows etc complete.	Sqm	9.66	67.40	651.08
11	12mm thick cement plaster in cement mortar (1:6) over the out side wall surface including necessary scaffolding, curring, etc. completed.	Sqm	77.14	99.20	7652.29
12	16mm thick cement plaster in cement mortar (1:6) over the inside wall surface urface including necessary scaffolding, curring, etc. completed.	Sqm	73.11	141.60	10352.38
13	Fixing of Virfified tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1cement : 1sand) jointed with neat cement slury mixed with pigment o match the shades of the tiles including rubbing and polishing complete excluding cost of precast TILES	Sqm	34.80	1154.70	40183.56
14	Fixing Chequred tiles in floors on 25 mm thick bed of cement mortar (1:1) jointed with neat cement slurry mixed with pigment to match the shades of the tiles incl. rubbing and polishing complete incl. cost of tile etc all complete.	Sqm	5.33	861.20	4590.20
15	20 mm thick cement plaster (1:4) over Stone work with cost of all materials and all labour etc.complete.	Sqm	17.39	150.40	2615.46
16	25mm thick A.S. flooring with C.C (1:2:4) with neat punning & finishing, using 12mm size h.b.g. chips complete in all respect.	Sqm	17.09	226.00	3862.34
17	Finishing walls with water proofing cement paint of approved shade on new work 2 coats to give an even shade including cost of brushes and putty and including cost of paint (Details for 10 Sqm)	Sqm	217.89	24.80	5403.67
18	Providing two coat of enamel paint over the grill work including cost of all materials and labour etc. complete	Sqm	23.97	94.40	2262.77
				TOTAL	553755.47
				Or Say	553755.00

(Rupees Five lakh fifty three thousand seven hundred fifty five) only

Total-18 Nos (Eighteen) items only

My/ Our quoted rate is% (both in figure and words) excess over/ less then / equal to the above estimated cost.

1. The Contractor should not write anything excepting quoting of percentage and in any case anything else regarding tender rate is mentioned, the tender is liable for refecton.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figures and words so there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
5. The percentage quoted in the tender without mentioning excess or less will be treated as excess.
6. The contractor will write percentage excess or less up to one decimal point only. If he writes the percentage excess or less up to two or more decimal point, the first decimal point shall only be considered.

APPROVED
For 18 (Eighteen) items only.