

OFFICE OF THE  
PROJECT ADMINISTRATOR  
INTEGRATED TRIBAL DEVELOPMENT AGENCY  
RAYAGADA

DETAILED TENDER CALL NOTICE  
WITH SCHEDULE OF QUANTITIES

*Name of Work* : "Improvement of Rural Haat at K.Singpur, K.Singpur Block"

*Amount put to Tender* : Rs 7,22,636/-

*Amount of bid security* : Rs 7,300/-

*Class of Contractor* : "D" & "C"

*Name of the Tenderer* : .....


*Last Date of receipt of Tender*: 24-09-2019 upto 5.30PM.



**BILLS OF QUANTITY****NAME OF THE WORK:- IMPROVEMENT OF RURAL HAAT AT K.SINGPUR**

SL. NO.	ITEMS	QUANTITY	UNIT	RATE	Amount
1	2	3	4	5	6
1	Earth work in excavation of foundation trenches & Columns in all kinds of soil within all lead and lifts including dressing the sides, shoring (if necessary), bailing out water and leveling the bed and depositing the excavated materials away from the work site including all costs of labour, sundries, tools & plants required for the work etc. complete as per direction of Engineer-in-Charge.	114.00 Cum.	100 Cum.	18297.33	20,858.95
2	Filling in foundation and Plinth with sand well watered and rammed & dressed & level to proper gradient including all cost, conveyance, royalty taxes of all materials, labour, T & P required for the work etc. complete and as per direction of Engineer in Charge.	24.36 Cum.	1 Cum.	280.80	6,840.27
3	Cement concrete (1:3:6) with 4 cm. size hand broken hard granite metals of approved quality including mixing with concrete mixture, lowering & laying in layers not exceeding 300 mm. in depth, ramming compacting to proper thickness, watering, curing for required period including all cost, conveyance, royalty, taxes of all materials etc. complete as per the direction of Engineer-in-Charge.	44.16 Cum.	1 Cum.	3788.78	1,67,312.60
4	Cement concert (1:2:4) using 12mm size crusher broken hard granite chips of approved quality including mixing with concrete mixture, including hoisting and laying in position & compacting with vibrator to proper design section including all the cost, conveyance, royalty & taxes of all materials, labour, rigid smooth centering, shuttering and dismantling the same after 28 days of casting, watering, curing etc. complete as per the direction of Engineer-in-Charge.	16.14 Cum.	1 Cum.	5580.52	90,069.56
5	Reinforced cement concert M-20 grade using 20mm and downgraded size crusher broken hard granite chips of approved quality including mixing with concrete mixture, including hoisting and laying in position & compacting with vibrator to proper design section including all the cost, conveyance, royalty & taxes of all materials, labour, rigid smooth centering, shuttering and dismantling the same after 28 days of casting, watering, curing etc. complete as per the direction of Engineer-in-Charge.				
i)	Column Base and Footing	6.98 Cum.	1 Cum.	4789.27	33,450.64
ii)	Column and Beam	4.35 Cum.	1 Cum.	10103.17	43,918.50
iii)	Plinth Band	4.00 Cum.	1 Cum.	5093.05	20,372.19
iv)	slab	15.84 Cum.	1 Cum.	8129.63	1,28,773.31

CONTRACTOR


PROJECT ADMINISTRATOR  
I.T.D.A., RAYAGADA


6	Supplying HYSD/Tor steel reinforcement from SAIL,VIZAG STEEL OR TATA STEEL brand of required diameter of approved quality including Labour charges for cutting, bending, binding and tying the grills and placing in position including cost, conveyance & taxes of reinforcements conforming to ISI standard and binding wire 18 to 20 gauge and as per drawing, design etc. complete as per the direction of Engineer-in-Charge.(including septic tank)	31.86	Qtls.	1	Qtls.	5355.86	1,70,651.34
7	9" thick Brick work with fly ash Bricks in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 kg/cm2 immersing the bricks in water not less than six hours before use in masonry including watering and curing for required period with all cost conveyance, royalty, taxes of all materials etc. complete as per the direction of Engineer-in-Charge.	2.99	Cum.	1	Cum.	4042.42	12,086.84
8	12 mm thick cement plaster (1:6) over brick work including racking out joints finishing smooth with proper plumb and line watering curing for seven days with cost, conveyance, royalty taxes of all materials, labour, T & P required for the work etc. Complete as per the direction of Engineer-in-Charge.	57.08	Sqm.	1	Sqm.	122.28	6,979.59
9	16 mm thick cement plaster (1:6) over brick work including racking out joints finishing smooth with proper plumb and line watering curing for seven days with cost, conveyance, royalty taxes of all materials, labour, T & P required for the work etc. Complete as per the direction of Engineer-in-Charge.	49.08	Sqm.	1	Sqm.	174.26	8,552.85
10	Primer 1 coat with any approved primers over plastered surface to make to the outer surface after scraping and cleaning the surface including all cost of materials, scaffolding, labour, watering & curing T&P etc complete as per direction of Engineer-in-charge.	106.16	Sqm.	1	Sqm.	54.08	5,741.52
11	Providing & Painting with two coats to the entire outside surface with silicon based weather coat paint before one coat of primer of any approved make to the outer surface after scraping and cleaning the surface including all cost of materials, scaffolding, labour, watering & curing T&P etc complete as per direction of Engineer-in-charge.	106.16	Sqm.	1	Sqm.	66.21	7,028.69

Total 11 (Eleven) Nos. items only.

Total cost of Civil work 7,22,636.85

Amount Put to Tender Rs. 7,22,636.00

(Rupees Seven lakh twenty two thousand six hundred thirty six) only

Rate quoted by the Contractor.....%(both figure and

words) less than /Excess Over the amount put to Tender

Signature of the Contractor

Project Administrator,  
I.T.D.A.,Rayagada

CONTRACTOR

22/01/19

PROJECT ADMINISTRATOR  
I.T.D.A., RAYAGADA