

# जिल्हा परिषद सिंचन विभाग यवतमाळ

दालन क्र.२०७, दुसरा माळा, जिल्हा परिषद प्रशासकिय इमारत आर्णी रोड, यवतमाळ ४४५००३  
दूरध्वनी क्र.०७२३२-२४५२५८ फॅक्स क्र.०७२३२-२४४३९७ ई-मेल eezpirytl@gmail.com

क्रमांक/यजिप/सिंचन/भुस/वशि/१२५७/२०१६

दिनांक :- ११/११/२०१६

प्रति,

उपजिल्हाधिकारी (भुसंपादन)  
रस्ते प्रकल्प यवतमाळ

विषय :- अनुसुचितील विहीर व इतर बांधकामाचे मुल्यांकन अहवाल सादर करण्याबाबत.

संदर्भ :- १.आपले पत्र क्र. विभुअ/ला.क्षे/कावि/७५५/दि.५.८.२०१६

उपरोक्त संदर्भाकित विषयाचे अनुषंगाने अनुसुचितील विहीर व इतर बांधकामाचे मुल्यांकन अहवाल खालील प्रमाणे

अ.क्र	भसुपादन प्रकरण क्र.	गावाचे नाव	गट क्र जुना/ नवीन	शेतमालकाचे नाव	संबंधिताचे शेतीतील बाब
१.	१८/४७/२००९-१०	कळंब खंड-२	६६९/६४ ✓	शै .रफिक शे. आंमद	१ विहीर
२.	१८/४७/२००९-१०	कळंब खंड-२	६८४/१०८ ✓	शै .रफिक शे. मुनाफ	१ विहीर
३.	१८/४७/२००९-१०	कळंब खंड-२	१०४/१ ✓	वासुदेव सुरेशराव निमकर	१ विहीर
४.	७/४७/२०१५-१६	घोटी	७८	दशरथ राघु सोयाम	१ विहीर
५.	७/४७/२०१५-१६	घोटी	७९	अजाबराव सखाराम कुंभरे	१ विहीर

सहपत्र:- वरील लाभार्थ्यांचे विहीरीचे मुल्यांकन १ प्रतीत सादर करण्यात येत आहे.  
विहीरीचे मुल्यांकन १ प्रतीत

दिनांक १६/११/०१६  
वि.मु.ब.१.प्र.बी.१)

कार्यकारी अभियंता  
जि.प.सिंचन विभाग यवतमाळ

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT KALAMB KHAND 2

NAME OF OWNER - SHRI SY.RAFIK GAFFUR AAMAD AND OTHER SURVEY NO 669 / NEW SURVEY NO 64

TQ - KALAMB

DIST - YAVATMAL

Year of Construction - 2011-12

Sr No		Qty	Rate	Per	Total
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION In Soft Strata				
	LIFT - 0 to 1.50 M	52.86	269.00	Cum	14219.00
	LIFT - 1.5 to 3.00 M	52.86	291.00	Cum	15382.00
	LIFT - 3.00 to 4.50 M	52.86	313.00	Cum	16545.00
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION In Hard Strata				
	LIFT - 4.50 to 6.00 M	16.02	633.00	Cum	10141.00
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4 For Bed Concrete	1.85	4968.00	Cum	9191.00
4	Providing and Constructing B B Masonary in CM 1.6 MJP CSR 2015-16 Item NO 2a P.No.45 For WELL Staining	31.91	4500.00	Cum	143595.00
5	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48	1.11	4978.30	Qt	5526.00
6	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	13.88	61.00	Cum	847.00
	TOTAL				215446.00

Deduction Depreciation Cost

3 Years @ 5 %

NET VALUTATION

32317

Assistant Engineer(Grade-I)

M.I.Sub-Divison

Z.P.Yavatmal)

Executive Engineer  
(Irrigation Division)

183129.00

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT KALAMB KHAND 2

NAME OF OWNER - SHRI SY.RAFIK GAFFUR AAMAD AND OTHER SURVEY NO 669 / NEW SURVEY NO 64

TQ - KALAMB

DIST - YAVATMAL

Year of Construction - 2011-12

Sr No		No	L	B	D	Quantity
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION					
	LIFT - 0 to 1.50 M	0.785	6.70	6.70	1.50	52.86
	LIFT - 1.5 to 3.00 M	0.785	6.70	6.70	1.50	52.86
	LIFT - 3.00 to 4.50 M	0.785	6.70	6.70	1.50	52.86
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION					
	LIFT - 4.50 to 6.00 M	0.785	5.40	5.40	0.70	16.02
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4 For Bed Concrete	0.785	6.70	5.40	0.15	1.85
4	Providing and Constructing B B Masonary in CM 1.6 MJP CSR 2015-16 Item NO 2a P.No.45 For WELL Staining	0.785	6.40	5.70	4.80	31.91
5	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48	60 Kg / Cum of concrete 1.85 x 0.60			QT	1.11
6	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	0.785	6.70	6.40	4.50	13.88

*[Handwritten signature]*

*[Handwritten signature]*

Assistant Engineer (Grade-I)  
M.I. Sub-Divison  
Z.P. Yavatmal

*[Handwritten signature]*  
Executive Engineer  
(Irrigation Division)  
Z.P. Yavatmal

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT KALAMB KHAND 2  
 NAME OF OWNER - SHRI SHEKH SHAFI SHIKH MUNAF SURVEY NO 684 / NEW SURVEY NO 108

TQ - KALAMB

DIST - YAVATMAL

Year of Construction - 2013-14

Sr No		Qty	Rate	Per	Total
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION In Soft Strata				
	LIFT - 0 to 1.50 M	99.66	269.00	Cum	26809.00
	LIFT - 1.5 to 3.00 M	79.73	291.00	Cum	23201.00
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) · MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION In Hard Strata				
	LIFT - 3.00 to 4.50 M	27.69	633.00	Cum	17528.00
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4	10.23	4968.00	Cum	50823.00
5	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48	6.14	4978.30	Qt	30567.00
6	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	10.66	61.00	Cum	650.00
	<b>TOTAL</b>				<b>149578.00</b>

Deduction Deprission Cost

7479

1 Years @ 5 %

NET VALUTATION

142099.00

*[Handwritten signature]*

*[Handwritten signature]*  
 Assistant Engineer (Grade-I)  
 M.I. Sub-Division  
 Z.P. Yavatma Executive Engineer  
 (Irrigation Division)  
 Zila Parishad Yavatmal

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT KALAMB KHAND 2  
 NAME OF OWNER - SHRI SHEKH SHAFI SHIKH MUNAF SURVEY NO 684 / NEW SURVEY NO 108

TQ - KALAMB

DIST - YAVATMAL

Year of Construction - 2013-14

Sr No		No	L	B	D	Quantity
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION					
	LIFT - 0 to 1.50 M	0.785	9.20	9.20	1.50	99.66
	LIFT - 1.5 to 3.00 M	0.785	9.20	9.20	1.20	79.73
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION					
	LIFT - 3.00 to 4.50 M	0.785	8.40	8.40	0.50	27.69
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4 For Bed Concrete	0.785	9.20	8.40	0.15	1.66
	For WELL Staining	0.785	8.90	8.70	3.10	8.57
						10.23
4	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48	60 Kg / Cum of concrete 10.23	x 0.60		QT	6.14
5	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	0.785	9.20	8.90	2.50	10.66

*Handwritten signature*

*Handwritten signature*  
 Assistant Engineer (Grade-I)  
 M.I. Sub-Division  
 Z.P. Yavatmal

*Handwritten signature*  
 Executive Engineer  
 (Irrigation Division)  
 Zilla Parishad Yavatmal

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT KALAMB KHAND 2

NAME OF OWNER - SHRI WASUDEO SURESHRAO NIMKAR SURVEY NO 717/2 NEW SURVEY NO 104/1

TQ - KALAMB

DIST - YAVATMAL

Year of Construction - 2009-10

Sr No		Qty	Rate	Per	Total
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION In Soft Strata				
	LIFT - 0 to 1.50 M	57.70	269.00	Cum	15521.00
	LIFT - 1.5 to 3.00 M	57.70	291.00	Cum	16791.00
	LIFT - 3.00 to 4.50 M	57.70	313.00	Cum	18060.00
	LIFT - 4.50 to 6.00 M	19.23	335.00	Cum	6442.00
	LIFT - 4.50 to 6.00 M	29.21	335.00	Cum	9785.00
	LIFT - 6.00 to 7.50 M	43.81	357.00	Cum	15640.00
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION In Hard Strata				
	LIFT - 7.50 to 9.00 M	43.81	677.00	Cum	29659.00
	LIFT - 9.00 to 10.50 M	23.37	699.00	Cum	16336.00
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4	14.2	4968.00	Cum	70546.00
5	Providing and laying M.S.reinforcement including cutting,bending,hooking, binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48	8.52	4978.30	Qt	42415.00
6	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	18.75	61.00	Cum	1144.00
	<b>TOTAL</b>				<b>242339.00</b>

Deduction Deprission Cost

5 Years @ 5 %

60585

NET VALUTATION

181754.00

*(Signature)*

Assistant Engineer (Grade-I)

M.I. Sub-Division

Z.P. Yavatmal

Executive Engineer

(Irrigation Division)

Zilla Parishad Yavatmal