

जिल्हा परिषद सिंचन विभाग यवतमाळ

दालन क्र.२०७, दुसरा माळा, जिल्हा परिषद प्रशासकिय इमारत आर्णी रोड, यवतमाळ ४४५००१
दूरध्वनी क्र.०७२३२-२४५२५८ फॅक्स क्र.०७२३२-२४४३९७ ई-मेल eezpirytl@gmail.com

क्रमांक/यजिप/सिंचन/भुस/वशि/ ८१७/२०१७

दिनांक :- १२/४/२०१७

प्रति,

उपजिल्हाधिकारी (भुसंपादन)
रस्ते प्रकल्प यवतमाळ

विषय :- वर्धा-नांदेड (रेल्वे) प्रकल्पाकरीता अनुसुचितील विहीर व इतर बांधकामाचे मुल्यांकन अहवाल सादर करण्याबाबत.

संदर्भ :- १. आपले पत्र क्र. अका/भु.स/रस्ते प्रकल्प/कावि/१०१३/दि.२७.१२.२०१६ प्राप्त दि.२.१.२०१७
२. सहाय्यक अभियंता (श्रेणी-१) जि.प.सिंचन उपविभाग यवतमाळ यांचे पत्र क्र Q/दि.१८.४.२०१७

उपरोक्त संदर्भांकित विषयाचे अनुषंगाने अनुसुचितील विहीर व इतर बांधकामाचे मुल्यांकन अहवाल खालील प्रमाणे

अ. क्र	भसुपादन प्रकरण क्र.	गावाचे नाव	गट क्र जुना/ नवीन	शेतमालकाचे नाव	संबंधिताचे शेतीतील बाब
१.	४४/४७/२००९-२०१०	तळेगाव ता. यवतमाळ	२८/१ अ	महादेव लटाये	१ विहीर
२	४४/४७/२००९-२०१०	तळेगाव ता. यवतमाळ	१८	संतोष फालगुनमल लालवाणी	१ विहीर

वरील २ लाभार्थ्यांचे विहीरीचे मुल्यांकन १ प्रतीत सादर करण्यात येत आहे.

सहपत्र:-

१. २ लाभार्थ्यांचे विहीरीचे मुल्यांकन १ प्रतीत

कार्यकारी अभियंता

जि.प.सिंचन विभाग यवतमाळ

प्रतिलिपी:-

उप अभियंता लघु सिंचन उप विभाग यवतमाळ यांना माहिती करीता अर्पित.

बोदणी क्रमांक दिनांक १२/४/२०१७
श्री.
yamega
माळ
वि.सू.ख.र.प्र.जी.प.

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT TALEGAON
 NAME OF OWNER - SHRIMATI YAMUNABAI MAHADEV LATAYE SURVEY NO 28/1A

TQ - YAVTAMAL

DIST - YAVATMAL

Year of Construction - 2013-14

Sr No		Qty	Rate	Per	Total
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION In Soft Strata				
	LIFT - 0 to 1.50 M	48.23	269.00 ✓	Cum	12974.00
	LIFT - 1.5 to 3.00 M	48.23	291.00 ✓	Cum	14035.00
	LIFT - 3.00 to 4.50 M	19.29	313.00 ✓	Cum	6038.00
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION In Hard Strata				
	LIFT - 4.50 to 6.00 M	38.26	633.00 ✓	Cum	24219.00
	LIFT - 6.00 to 7.50 M	12.75	655.00 ✓	Cum	8351.00
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4				
	For Bed Concrete	0.71	4968.00 ✓	Cum	3527.00
	Bottom beam	0.85	4968.00 ✓	Cum	4223.00
	For WELL Staining	12.86	4968.00 ✓	Cum	63888.00
	Top beam	0.91	4968.00 ✓	Cum	4521.00
4	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48	6.13	4978.30 ✓	Qt	30517.00
5	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	12.31	61.00 ✓	Cum	751.00
TOTAL					173044.00

Deduction Depreciation Cost
 5 Years @ 5 %
 NET VALUTATION

8652

164392.00

(Handwritten signature)

सहाय्यक अभियंता श्रेणी-9
 जि.प.लघुसिंचन उपविभाग
 यवतमाल

Executive Engineer
 (Irrigation Division)
 Jila Parishad Yavatmal

(Handwritten signature)

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT TALEGAON
 NAME OF OWNER - SHRIMATI YAMUNABAI MAHADEV LATAYE SURVEY NO 28/1A
 DIST - YAVATMAL Year of Construction - 2013-14

TQ - YAVTAMAL

Sr No	No	L	B	D	Quantity	
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION					
	LIFT - 0 to 1.50 M	0.785	6.40	6.40	1.50	48.23
	LIFT - 1.5 to 3.00 M	0.785	6.40	6.40	1.50	48.23
	LIFT - 3.00 to 4.50 M	0.785	6.40	6.40	0.60	19.29
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION					
	LIFT - 4.50 to 6.00 M	0.785	5.70	5.70	1.50	38.26
	LIFT - 6.00 to 7.50 M	0.785	5.70	5.70	0.50	12.75
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4					
	For Bed Concrete	0.785	6.40	5.65	0.10	0.71
	Bottom beam	0.785	6.11	5.65	0.20	0.85
	For WELL Staining	0.785	6.05	5.65	3.50	12.86
	Top beam	0.785	6.30	5.65	0.15	0.91
4	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48					
	60 Kg / Cum of concrete 15.33 x 0.40			6.05	QT	6.13
5	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41					
	0.785	6.40	6.05	3.60	12.31	

 
 सहाय्यक अभियंता श्रेणी-9
 जि.प.लातूर जिल्हा उपविभाग
 तालुका

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT TALEGAON
 NAME OF OWNER - SHRI SANTOSH FALGUNMAL LALWANI SURVEY NO 18

TQ - YAVATMAL

DIST - YAVATMAL

Year of Construction - Approximately 40 year old

Sr No		Qty	Rate	Per	Total
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION In Soft Strata				
	LIFT - 0 to 1.50 M	71.42	269.00	Cum	19212.00
	LIFT - 1.5 to 3.00 M	71.42	291.00	Cum	20783.00
	LIFT - 3.00 to 4.50 M	14.28	313.00	Cum	4470.00
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION In Hard Strata				
	LIFT - 3.00 to 4.50 M	55.49	611.00	Cum	33904.00
	LIFT - 4.50 to 6.00 M	54.45	633.00	Cum	34467.00
	LIFT - 6.00 to 7.50 M	54.45	655.00	Cum	35665.00
	LIFT - 7.50 to 9.00 M	10.89	677.00	Cum	7373.00
	Providing uncoursed rubble masonry of trap/granite/quartzite/ gneiss stones in cement mortar 1:6 in foundations and plinth of inner walls / in plinth of external walls including bailing out water, striking joints on unexposed faces and watering complete.				
3	PWD C.S.R.Item No.1 P.No.	25.146	1700.00	Cum	42748.00
6	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	9.108	61.00	Cum	556.00
	TOTAL				199178.00


Deduction Depreciation Cost

39836

Depreciation shall be 20% for construction 40 year old

159342.00

NET VALUTATION


 सहाय्यक अभियंता श्रेणी-9
 जि.प.लक्ष्मिनगर उपविभाग
 यवतमाळ


 Executive Engineer
 (Irrigation Division)
 Talgaon Taluka Parishad Yavatmal

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT TALEGAON
 NAME OF OWNER - SHRI SANTOSH FALGUNMAL LALWANI SURVEY NO 18

TQ - YAVATMAL

DIST - YAVATMAL

Year of Construction - Approximately 40 year old

Sr No	No	L	B	D	Quantity	
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION					
	LIFT - 0 to 1.50 M	1	6.90	6.90	1.50	71.42
	LIFT - 1.5 to 3.00 M	1	6.90	6.90	1.50	71.42
	LIFT - 3.00 to 4.50 M	1	6.90	6.90	0.30	14.28
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION					
	LIFT - 3.00 to 4.50 M	1	6.80	6.80	1.20	55.49
	LIFT - 4.50 to 6.00 M	0.785	6.80	6.80	1.50	54.45
	LIFT - 6.00 to 7.50 M	0.785	6.80	6.80	1.50	54.45
	LIFT - 7.50 to 9.00 M	0.785	6.80	6.80	0.30	10.89
3	Providing uncoursed rubble masonry of trap/granite/quartzite/ gneiss stones in cement mortar 1:6 in foundations and plinth of inner walls / in plinth of external walls including bailing out water, striking joints on unexposed faces and watering complete.					
	PWD C.S.R.Item No.1 P.No.					
		2	6.80	0.30	3.30	13.464
		2	5.9	0.3	3.3	11.682
				Total	25.146	
6	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41					
	4	6.90	0.10	3.30	9.108	

Valuation prepared by :-

सहायक अभियंता श्रेणी-१
 जि.प.लघुसिंचन उपविभाग
 यवतमाळ