

# जिल्हा परिषद सिंचन विभाग यवतमाळ

दालन क्र.२०७, दुसरा माळा, जिल्हा परिषद प्रशासकिय इमारत आर्णी रोड, यवतमाळ ४४५००१  
दूरध्वनी क्र.०७२३२-२४५२५८ फॅक्स क्र.०७२३२-२४४३९७ ई-मेल eezpirrytl@gmail.com

क्रमांक/यजिप/सिंचन/भुस/वशि/५८७२०१७

दिनांक :- २५/३/१७

प्रति,

उपजिल्हाधिकारी (भुसंपादन)  
रस्ते प्रकल्प यवतमाळ

विषय :-

वधरू-नांदेड (रेल्वे) प्रकल्पाकरीता अनुसुचितील विहीर व इतर बांधकामाचे मुल्यांकन अहवाल सादर करण्याबाबत.

संदर्भ :-

१. आपले पत्र क्र. अका/भु.स/रस्ते प्रकल्प/कावि/३३३/१७/१६७/दि.२१.२.२०१७  
२. सहाय्यक अभियंता(श्रेणी-१) जि.प.सिंचन उपविभाग यवतमाळ यांचे पत्र क्र.१५७/दि.२३.३.२०१७

उपरोक्त संदर्भांकित विषयाचे अनुषंगाने अनुसुचितील विहीर व इतर बांधकामाचे मुल्यांकन अहवाल खालील प्रमाणे

अ.क्र	भसुपादन प्रकरण क्र.	गावाचे नाव	गट क्र जुना/ नवीन	शेतमालकाचे नाव	संबंधिताचे शेतीतील बाब
१.	१७/४७/२०१२-१३	<u>बोरजई</u> ता. यवतमाळ	५८	श्री निलेश राजेंद्र राठोड	१ विहीर

वरील लाभार्थ्यांचे विहीरीचे मुल्यांकन १ प्रतीत सादर करण्यात येत आहे.

सहपत्र:-

१. मुल्यांकन १ प्रतीत

कार्यकारी अभियंता

जि.प.सिंचन विभाग यवतमाळ

प्रतिलिपी:-

उप अभियंता लघु सिंचन उप विभाग यवतमाळ यांना माहिती करीता अग्रेषित.

५८७  
दिनांक २५/३/१७  
वि.सू.व.प.सो.प.

अ.स.सि.स.प.  
जि.प.सिंचन विभाग  
यवतमाळ  
दि. २५/३/१७

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT BORJAI  
NAME OF OWNER - SHRI. NILESH RAJENDRA RATHOD SURVEY NO 58

Q - YAVATMAL

DIST - YAVATMAL


Year of Construction - 2010-11


Sr No		Qty	Rate	Per	Total
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION In Soft Strata LIFT - 0 to 1.50 M	70.85	269.00	Cum	19059.00
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION In Hard Strata LIFT - 0 to 1.50 M LIFT - 0 to 1.50 M LIFT - 1.5 to 3.00 M LIFT - 3.00 to 4.50 M LIFT - 4.50 to 6.00 M LIFT - 6.00 to 7.50 M LIFT - 7.50 to 9.00 M LIFT - 9.00 to 10.50 M	21.25 9.55 71.64 71.64 71.64 71.64 71.64 23.88	567.00 567.00 589.00 611.00 633.00 655.00 677.00 699.00	Cum Cum Cum Cum Cum Cum Cum Cum	12049.00 5415.00 42196.00 43772.00 45348.00 46924.00 48500.00 16692.00
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4 For Bed Concrete Bottom beam For WELL Staining Top beam	1.33 1.6 3.47 1.22	4968.00 4968.00 4968.00 4968.00	Cum Cum Cum Cum	6607.00 7949.00 17239.00 6061.00
4	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48	4.57	4978.30	Qt	22751.00
5	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	16.62	61.00	Cum	1014.00
TOTAL					341576.00


Deduction Depreciation Cost  
5 Years @ 5 %  
NET VALUTATION

85394

256182.00

Valuation Prepared by  


  
Assistant Engineer (Grade-I)  
M.I. Sub-Division  
Z P Yavatmal

  
Executive Engineer  
(Irrigation Division)  
Zilla Parishad Yavatmal

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT BORJAI  
 NAME OF OWNER - SHRI. NILESH RAJENDRA RATHOD SURVEY NO 58


Q - YAVATMAL

DIST - YAVATMAL

Year of Construction - 2010-11

Sr No		No	L	B	D	Quantity
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION LIFT - 0 to 1.50 M	0.785	9.50	9.50	1.00	70.85
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION LIFT - 0 to 1.50 M LIFT - 0 to 1.50 M LIFT - 1.5 to 3.00 M LIFT - 3.00 to 4.50 M LIFT - 4.50 to 6.00 M LIFT - 6.00 to 7.50 M LIFT - 7.50 to 9.00 M LIFT - 9.00 to 10.50 M	0.785 0.785 0.785 0.785 0.785 0.785 0.785	9.50 7.80 7.80 7.80 7.80 7.80 7.80	9.50 7.80 7.80 7.80 7.80 7.80 7.80	0.30 0.20 1.50 1.50 1.50 1.50 0.50	21.25 9.55 71.64 71.64 71.64 71.64 23.88
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4 For Bed Concrete Bottom beam For WELL Staining Top beam	0.785 0.785 0.785 0.785	9.00 8.80 8.60 8.85	8.00 8.20 8.40 8.40	0.10 0.20 1.30 0.20	1.33 1.6 3.47 1.22
4	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48	60 Kg / Cum of concrete 7.62	x 0.60		QT	4.57
5	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	0.785	9.50	8.60	1.30	16.62

Measurement taken by  


  
 Assistant Engineer (Grade-I)  
 M.I. Sub-Divison  
 Z.P.Yavatmal