

# जिल्हा परिषद सिंचन विभाग यवतमाळ

दालन क्र.२०७, दुसरा माळा, जिल्हा परिषद प्रशासकिय इमारत आर्णी रोड, यवतमाळ ४४५००३  
दूरध्वनी क्र.०७२३२-२४५२५८ फॅक्स क्र.०७२३२-२४४३९७ ई-मेल eezpirytl@gmail.com

क्रमांक/यजिप/सिंचन/भुस/वशि/२२७९/२०१६

दिनांक :- १९/११/२०१६

प्रति,

✓ उपजिल्हाधिकारी (भुसंपादन)  
रस्ते प्रकल्प यवतमाळ

विषय :- अनुसुचितील विहीर व इतर बांधकामाचे मुल्यांकन अहवाल सादर करण्याबाबत.

संदर्भ :- १. आपले पत्र क्र. अका/भु.स/रस्ते प्रकल्प/कावि/७५६/दि.५.८.२०१६  
२. सहाय्यक अभियंता(श्रेणी-१) जि.प.सिंचन उपविभाग यवतमाळ यांचे पत्र क्र.८४३/दि.१८.११.२०१६

उपरोक्त संदर्भांकित विषयाचे अनुषंगाने अनुसुचितील विहीर व इतर बांधकामाचे मुल्यांकन अहवाल खालील प्रमाणे

अ.क्र	भसुपादन प्रकरण क्र.	गावाचे नाव	गट क्र जुना/ नवीन	शेतमालकाचे नाव	संबंधिताचे शेतीतील बाब
१.	४२/४७/२००९-१०	पारवा	८०	सौ शोभा पदमचंद बाफना आरीफ खॉन	१ विहीर
२.	४४/४७/२००९-१०	तळेगाव	१००	फैजलअली खॉन काजी	१ विहीर
३.	४४/४७/२००९-१०	तळेगाव	१०८	पुंडलिक नागोराव खोब्रागडे	१ विहीर
४.	४४/४७/२००९-१०	तळेगाव	१०८	रुखमाबाई देवराव कांबळे	१ विहीर
५.	४१/४७/२००९-१०	कार्ली	१२३ ✓	महेश यशवं देशमुख	१ विहीर ✓
६.	४१/४७/२००९-१०	कार्ली	१२१ ✗	प्रशांत रामराव जिरापुणे +३	१ विहीर ✗
७.	४१/४७/२००९-१०	कार्ली	१२२ ✗	दत्ता शंकरराव गाढवे	१ विहीर ✗
८.	४१/४७/२००९-१०	कार्ली	१२८ ✗	सुर्यभान मुकिंदा यदमल	१ विहीर ✗
९.	४४/४७/२००९-१०	तळेगाव	१३०	सिताबाई सुरेश चारमलकर	१ विहीर
१०.	४४/४७/२००९-१०	तळेगाव	१३०	मारोती सखाराम गोंडे	१ विहीर
११.	४४/४७/२००९-१०	तळेगाव	१४३	श्रीमती गोदाबाई अजाबराव गदई	१ विहीर कच्ची

वरील लाभार्थ्यांचे विहीरीचे मुल्यांकन १ प्रतीत सादर करण्यात येत आहे.

सहपत्र:-

११ विहीरीचे मुल्यांकन १ प्रतीत

नोंदणी क्रमांक ९२२ दिनांक १९/११/०९६

बी. शर्मा, उपजिल्हाधिकारी

वि.प.सिंचन विभाग यवतमाळ

कार्यकारी अभियंता  
जि.प.सिंचन विभाग यवतमाळ

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT TALEGAON KARLI

NAME OF OWNER - SHRI MAHESH YASHWANT DESHMUKH GUT NO 123

TQ - YAVATMAL

DIST - YAVATMAL

Year of Construction - 2008

LA-CASE NO.44/47/2009-10

Sr No		Qty	Rate	Per	Total
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION In Soft Strata				
	LIFT - 0 to 1.50 M	95.38	269.00	Cum	25657.00
	LIFT - 1.5 to 3.00 M	82.66	291.00	Cum	24054.00
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION In Hard Strata				
	LIFT - 1.5 to 3.00 M	9.55	589.00	Cum	5625.00
	LIFT - 3.00 to 4.50 M	71.64	611.00	Cum	43772.00
	LIFT - 4.50 to 6.00 M	66.86	633.00	Cum	42322.00
	LIFT - 6.00 to 7.50 M	19.1	655.00	Cum	12511.00
	LIFT - 7.50 to 9.00 M	0	677.00	Cum	0.00
	LIFT - 9.00 to 10.50 M	0	699.00	Cum	0.00
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4 For Bed Concrete	1.75	4968.00	Cum	8694.00
4	Providing and Constructing U C R Masonary in CM 1.6 MJP CSR 2015-16 Item NO 2a P.No.45 For WELL Staining	30.89	1800.00	Cum	55602.00
5	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48	1.05	4978.30	Qt	5227.00
6	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	8.18	61.00	Cum	499.00
	TOTAL				223963.00

Deduction Depreciation Cost

89585

8 Years @ 5 %

NET VALUTATION

134377.80

SECTIONAL ENGINEER

ASSITANT ENGINEER (GR.I)

Z.P.M.SUB DN.YAVATMAL


Executive Engineer  
EXECUTIVE ENGINEER  
(Irrigation Division)  
Z.P.M.S. DN.YAVATMAL  
Zilla Parishad Yavatmal

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT TALEGAON KARLI  
NAME OF OWNER - SHRI MAHESH YASHWANT DESHMUKH GUT NO 123  
DIST - YAVATMAL Year of Construction - 2008

TQ - YAVATMAL  
LA-CASE NO.44/47/2009-10

Sr No		No	L	B	D	Quantity
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION					
	LIFT - 0 to 1.50 M	0.785	9.00	9.00	1.50	95.38
	LIFT - 1.5 to 3.00 M	0.785	9.00	9.00	1.30	82.66
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION					
	LIFT - 1.5 to 3.00 M	0.785	7.80	7.80	0.20	9.55
	LIFT - 3.00 to 4.50 M	0.785	7.80	7.80	1.50	71.64
	LIFT - 4.50 to 6.00 M	0.785	7.80	7.80	1.40	66.86
	LIFT - 6.00 to 7.50 M	0.785	7.80	7.80	0.40	19.1
	LIFT - 7.50 to 9.00 M	0.785	0.00	0.00	0.00	0
	LIFT - 9.00 to 10.50 M	0.785	0.00	0.00	0.00	0
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4 For Bed Concrete	0.785	8.70	7.80	0.15	1.75
4	Providing and Constructing U C R Masonary in CM 1.6 MJP CSR 2015-16 Item NO 2a P.No.45 For WELL Staining	0.785	8.70	7.80	2.65	30.89
5	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48					
			60 Kg / Cum of concrete 1.75 x 0.60		QT	1.05
6	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	0.785	9.00	8.70	2.65	8.18

  
SECTIONAL ENGINEER

  
ASSITANT ENGINEER (GR.I)  
Z.P.M.I.SUB DN.YAVATMAL