

जिल्हा परिषद सिंचन विभाग यवतमाळ

दालन क्र.२०७, दुसरा माला, जिल्हा परिषद प्रशासनाचे कार्यालय,
दूरध्वनी क्र.०६२३२-२४५२५८ फॅक्स क्र.०६२३२-२४५२५८

आर्जो रोड, यवतमाळ ४४५००३
मेल eezpirytl@gmail.com

क्रमांक/यजिप/सिंचन/भुस/वशि/२२७९/२०१६

दिनांक :- १९/११/२०१६

प्रति,

✓ उमजिन्हाधिकारी (भुसंपादन)
रस्ते प्रकल्प यवतमाळ

विषय :- अनुसूचितोत्त विहीर व इतर बांधकामाचे मुल्यांकन अहवाल सादर करण्याबाबत.

संदर्भ :- १. आणखी पत्र क्र. अका भु.म.रस्ते प्रकल्प कावि ७५६ दि.७.८.२०१६
२. सहाय्यक अभियंता (श्रेणी-१) जि.प.सिंचन उपविभाग यवतमाळ यांचे पत्र क्र.८४३ दि.१८.११.२०१६

उपरोक्त संदर्भांकित विषयाचे अनुषंगाने अनुसूचितोत्त विहीर व इतर बांधकामाचे मुल्यांकन

अहवाल खालील प्रमाणे

अ.क्र	भसुपादन प्रकरण क्र.	गावाचे नाव	गट क्र जुना/ नवीन	शेतमालकाचे नाव	संबंधिताचे शेतीतील बाब
१.	४२/४७/२००९-१०	पारवा ✓	८० ✓	सौ शोभा पदमचंद वाफना आरीफ खॉन	१ विहीर
२.	४४/४७/२००९-१०	तळेगाव ✓	१००	फैजल अली खॉन काजी	१ विहीर
३.	४४/४७/२००९-१०	तळेगाव ✓	१०८	पुंडलिक नागोराव खोब्रागडे	१ विहीर
४.	४४/४७/२००९-१०	तळेगाव ✓	१०८	सखुभावाड उदयराव कांबळे	१ विहीर
५.	४१/४७/२००९-१०	काली ✓	१२३	महेश यशवंत दशमुख	१ विहीर
६.	४१/४७/२००९-१०	काली	१२१	प्रशांत रामराव जिगपुरे +३	१ विहीर
७.	४१/४७/२००९-१०	काली	१२२	दत्ता शंकरराव गाढवे	१ विहीर
८.	४१/४७/२००९-१०	काली	१२८	सुर्यभान मुकिंदा यदमल	१ विहीर
९.	४४/४७/२००९-१०	तळेगाव ✓	१३०	सिताबाई सुरेश चारमलकर	१ विहीर
१०.	४४/४७/२००९-१०	तळेगाव ✓	१३०	मारांती सखाराम गोंड	१ विहीर
११.	४४/४७/२००९-१० ५१/५१/१५-१६	तळेगाव कारवी	१३३	श्रीमती गोदाबाई अजाबराव गडई	१ विहीर कच्ची

वरील लाभार्थ्यांचे विहीरीचे मुल्यांकन १ प्रतीत सादर करण्यात येत आहे.

सहपत्र:-

११ विहीरीचे मुल्यांकन १ प्रतीत

नोदणी क्रमांक - १२२

दिनांक १९/११/०१६

बी. राम

प्रकल्प विभाग

कार्यकारी अभियंता

जि.प.सिंचन विभाग यवतमाळ

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT TALEGAON

NAME OF OWNER - SMT.GODABAI AJABRAO GADAI GUT NO 143

LA-CASE NO.44/47/2009-10 41/47/15-16 कारसी.

Q - YAVATMAL

DIST - YAVATMAL

Year of Construction - 2014

Sr No		Qty	Rate	Per	Total
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION In Soft Strata				
	LIFT - 0 to 1.50 M	137.34	269.00	Cum	36944.00
	LIFT - 1.5 to 3.00 M	100.72	291.00	Cum	29310.00
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION In Hard Strata				
	LIFT - 1.5 to 3.00 M	30.78	589.00	Cum	18129.00
	LIFT - 3.00 to 4.50 M	107.71	611.00	Cum	65811.00
	LIFT - 4.50 to 6.00 M	0	633.00	Cum	0.00
	LIFT - 6.00 to 7.50 M	0	655.00	Cum	0.00
	LIFT - 7.50 to 9.00 M	0	677.00	Cum	0.00
	LIFT - 9.00 to 10.50 M	0	699.00	Cum	0.00
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4 For Bed Concrete	0	4968.00	Cum	0.00
4	Providing and Constructing B B Masonary in CM 1.6 MJP CSR 2015-16 Item NO 2a P.No.45 For WELL Staining	0.00	4500.00	Cum	0.00
5	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48	0	4978.30	Qt	0.00
6	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	0	61.00	Cum	0.00
TOTAL					150194.00

Deduction Depreciation Cost

2 Years @ 5 %

NET VALUTATION

15180

135014.00

SECTIONAL ENGINEER

ASSITANT ENGINEER (GR.I)

Z.P.M.I.SUB DN.YAVATMAL

Executive Engineer
EXECUTIVE ENGINEER
(Irrigation Division)
Zilla Parishad Yavatmal

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT TALEGAON
NAME OF OWNER - SMT.GODABAI AJABRAO GADAI GUT NO 143

LA CASE NO.44/47/2009-10


Q - YAVATMAL

DIST - YAVATMAL

Year of Construction - 2014

Sr No		No	L	B	D	Quantity
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION					
	LIFT - 0 to 1.50 M	0.785	10.80	10.80	1.50	137.34
	LIFT - 1.5 to 3.00 M	0.785	10.80	10.80	1.10	100.72
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION					
	LIFT - 1.5 to 3.00 M	0.785	9.90	9.90	0.40	30.78
	LIFT - 3.00 to 4.50 M	0.785	9.90	9.90	1.40	107.71
	LIFT - 4.50 to 6.00 M	0.785	9.90	9.90	0.00	0
	LIFT - 6.00 to 7.50 M	0.785	0.00	0.00	0.00	0
	LIFT - 7.50 to 9.00 M	0.785	0.00	0.00	0.00	0
	LIFT - 9.00 to 10.50 M	0.785	0.00	0.00	0.00	0
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4 For Bed Concrete	0.785	0.00	0.00	0.00	0
4	Providing and Constructing B B Masonary in CM 1.6 MJP CSR 2015-16 Item NO 2a P.No.45 For WELL Staining	0.785	0.00	0.00	0.00	0
5	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48	60 Kg / Cum of concrete 0.00 x 0.60			QT	0
6	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	0.785	0.00	0.00	0.00	0


SECTIONAL ENGINEER


ASSITANT ENGINEER (GR.I)
Z.P.M.I.SUB DN.YAVATMAL