

उपजिल्हाधिकारी (भूसंपादन) रस्ते प्रकल्प यवतमाळ यांचे कार्यालय
जिल्हाधिकारी कार्यालय, नविन प्रशासकीय ईमारत सिव्हील लाईन्स यवतमाळ ४४५००१
दुरध्वनी क्र. ०७२३२-२४०८१८ फॅक्स क्र. ०७२३२२४२२११ ई-मेल - dycorpzp@gmail.com

क्रमांक/ क.लि./भु.सं.रस्ते प्रकल्प/कावि/ 500 /2017

दिनांक 19 /04/2017

तात्काळ /महत्वाचे

प्रति,

कार्यकारी अभियंता
जिल्हा परिषद सिंचन विभाग, यवतमाळ

विषय - अनुसुचितील विहिरीचे मुल्यांकन अहवाल सादर करण्याबाबत.

-000-

वर्धा - नांदेड रेल्वे लाईन प्रकल्प संबंधात या कार्यालयात मौजा- तिवसा , ता., जिल्हा-यवतमाळ येथील भूसंपादन प्रकरण क्रमांक 21/47/2015-16 मध्ये भूसंपादनाची कार्यवाही सुरु आहे. सदर प्रकल्प हा मा. मुख्यमंत्री यांचे वॉर रुम मधिल असल्याने प्रकरणात निवाड्याची कार्यवाही तात्काळ करावयाची आहे. करिता सदर गांवातील खाली निर्देशीत केलेल्या शेतातील विहिरीचे मुल्यांकन अहवाल तात्काळ या कार्यालयास सादर करावे. सदर कामामध्ये हयगय व विलंब होणार नाही याची दक्षता घ्यावी व प्रथम प्राधान्याने पुर्तता करावी.

गट क्र.	भूसंपादन प्रकरण क्रमांक	गावाचे नांव	गट क्र.	शेत मालकाचे नांव	शेतातील बाब
1	21/47/2015-16	तिवसा ता. जिल्हा यवतमाळ	292	बबन राठोड व ईतर	विहिर - 1

सहपत्र - संयुक्त मोजणी अहवालाची प्रत.

(विजय स.भाकरे)

उपजिल्हाधिकारी (भूसंपादन)
रस्ते प्रकल्प यवतमाळ

प्रतिलिपी :- उप मुख्य अभियंता (निर्माण) मध्य रेल्वे वर्धा यांना उचित कार्यवाहीस अग्रेषित आपण विषयांकीत प्रकरणी पाठपुरावा करुन मुल्यांकन अहवाल या कार्यालयास तात्काळ सादर करण्याबाबत उचित कार्यवाही करावी.

(विजय स.भाकरे)

उपजिल्हाधिकारी (भूसंपादन)
रस्ते प्रकल्प यवतमाळ

ole

जिल्हा परिषद सिंचन विभाग यवतमाळ

दालन क्र.२०७, दुसरा माळा, जिल्हा परिषद प्रशासकिय इमारत आर्णी रोड, यवतमाळ ४४५००१
दूरध्वनी क्र.०७२३२-२४५२५८ फॅक्स क्र.०७२३२-२४४३९७ ई-मेल eezpirytl@gmail.com

क्रमांक/यजिप/सिंचन/भुस/वशि/ ८५०/२०१७

दिनांक :- २४/४/२०१७

प्रति,

उपजिल्हाधिकारी (भुसंपादन)
रस्ते प्रकल्प यवतमाळ

विषय :- वर्धा-नांदेड (रेल्वे) प्रकल्पाकरीता अनुसुचितील विहीर व इतर बांधकामाचे मुल्यांकन अहवाल सादर करण्याबाबत.

संदर्भ :- १. आपले पत्र क्र. अका/भु.स/रस्ते प्रकल्प/कावि/५०० /दि.१९.४.२०१७
२. सहाय्यक अभियंता(श्रेणी-१) जि.प.सिंचन उपविभाग यवतमाळ यांचे पत्र क्र २५३/दि.२१.४.२०१७

उपरोक्त संदर्भाकित विषयाचे अनुषंगाने अनुसुचितील विहीर व इतर बांधकामाचे मुल्यांकन अहवाल खालील प्रमाणे

अ. क्र	भसुपादन प्रकरण क्र.	गावाचे नाव	गट क्र जुना/ नवीन	शेतमालकाचे नाव	संबंधिताचे शेतीतील बाब
१.	२१/४७/२०१५-२०१६	तिवसा ता. यवतमाळ	२९२	बबन राठोड व ईतर	सादर सर्वे नं. मध्ये विहीर आढळून आलेली नाही
२	२१/४७/२०१५-२०१६	तिवसा ता. यवतमाळ	२९१/२	नारायण दुरसिंग राठोड	१ विहीर

वरील १ लाभार्थ्यांचे विहीरीचे मुल्यांकन १ प्रतीत सादर करण्यात येत आहे.

सहपत्र:- १. १ लाभार्थ्यांचे विहीरीचे मुल्यांकन १ प्रतीत

कार्यकारी अभियंता

जि.प.सिंचन विभाग यवतमाळ

प्रतिलिपी:- उप अभियंता लघु सिंचन उप विभाग यवतमाळ यांना माहिती करीता अग्रेषित.

मादणा क्रमांक --- दिनांक २४/४/२०१७
खी. ---
यवतमाळ
वि.भ.उ.र.प्र.डी.व.
०६

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT TIWSA
 NAME OF OWNER - SHRI NARAYAN DULSINGH RATHOD SURVEY NO 291/1

TQ - YAVATMAL

DIST - YAVATMAL

Year of Construction - 2008-09

Sr No		Qty	Rate	Per	Total
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION In Soft Strata				
	LIFT - 0 to 1.50 M	42.39	269.00	Cum	11403.00
	LIFT - 1.5 to 3.00 M	42.39	291.00	Cum	12335.00
	LIFT - 3.00to 4.50 M	5.65	313.00	Cum	1768.00
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION In Hard Strata				
	LIFT - 3.00to 4.50 M	28.67	611.00	Cum	17517.00
	LIFT - 4.50 to 6.00 M	33.08	633.00	Cum	20940.00
	LIFT - 6.00 to 7.50 M	33.08	655.00	Cum	21667.00
	LIFT - 7.50 to 9.00 M	33.08	677.00	Cum	22395.00
	LIFT - 9.00 to 10.50 M	22.05	699.00	Cum	15413.00
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4				
	For Bed Concrete	0.62	4968.00	Cum	3080.00
	Bottom beam	0.78	4968.00	Cum	3875.00
	For WELL Staining	4.92	4968.00	Cum	24443.00
	Top beam	0.97	4968.00	Cum	4819.00
	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48	2.19	4978.30	Qt	10902.00
5	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	2.99	61.00	Cum	182.00
TOTAL					170739.00

Deduction Depreciation Cost @ 5% slab bet 0 to 10
 5 Years @ 5 %
 NET VALUTATION

(Signature)
 Assistant Engineer (Grade-I)
 M.J. Sub-Divison
 Z.P Yavatmal

(Signature)
 Executive Engineer
 (Irrigation Division)
 Z.P. Parishad Yavatmal

8537 42685

162202.00 1,28,054/-


NAME OF WORK - VALUTATION OF IRRIGATION WELL AT TIWSA
 NAME OF OWNER - SHRI NARAYAN DULSINGH RATHOD SURVEY NO 291/1

TQ - YAVATMAL

DIST - YAVATMAL

Year of Construction - 2008-09

Sr No		No	L	B	D	Quantity
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION					
	LIFT - 0 to 1.50 M	0.785	6.00	6.00	1.50	42.39
	LIFT - 1.5 to 3.00 M	0.785	6.00	6.00	1.50	42.39
	LIFT - 3.00to 4.50 M	0.785	6.00	6.00	0.20	5.65
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION					
	LIFT - 3.00to 4.50 M	0.785	5.30	5.30	1.30	28.67
	LIFT - 4.50 to 6.00 M	0.785	5.30	5.30	1.50	33.08
	LIFT - 6.00 to 7.50 M	0.785	5.30	5.30	1.50	33.08
	LIFT - 7.50 to 9.00 M	0.785	5.30	5.30	1.50	33.08
	LIFT - 9.00 to 10.50 M	0.785	5.30	5.30	1.00	22.05
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4					
	For Bed Concrete	0.785	6.00	5.30	0.10	0.62
	Bottom beam	0.785	5.75	5.30	0.20	0.78
	For WELL Staining	0.785	5.50	5.30	2.90	4.92
	Top beam	0.785	5.90	5.35	0.20	0.97
	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48			5.76		
		60 Kg / Cum of concrete				
		7.29 x 0.30			QT	2.19
5	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	0.785	6.00	5.90	3.20	2.99


 Assistant Engineer (Grade-1)
 M.I. Sub-Divison
 Z.P Yavatmal