

क्रमांक/यजिप/सिंचन/भुस/वशि/ ८०६/२०१७

दिनांक :- १८/१२/२०१७

प्रति,

उपजिल्हाधिकारी (भुसंपादन)
रस्ते प्रकल्प यवतमाळ

विषय :- वर्धा-नांदेड (रेल्वे) प्रकल्पाकरीता अनुसुचितील विहीर व इतर बांधकामाचे मुल्यांकन अहवाल सादर करण्याबाबत.

संदर्भ :- १. आपले पत्र क्र. अका/भु.स/रस्ते प्रकल्प/कावि/१०१३/दि.२७.१२.२०१६ प्राप्त दि.२.१.२०१७
२. सहाय्यक अभियंता(श्रेणी-१) जि.प.सिंचन उपविभाग यवतमाळ यांचे पत्र क्र Q/दि.१८.४.२०१७

उपरोक्त संदर्भाकित विषयाचे अनुषंगाने अनुसुचितील विहीर व इतर बांधकामाचे मुल्यांकन अहवाल खालील प्रमाणे

अ. क्र	भुसुपादन प्रकरण क्र.	गावाचे नाव	गट क्र जुना/ नवीन	शेतमालकाचे नाव	संबंधिताचे शेतीतील बाब
१.	२१/४७/२०१५-१६	तिवसा ता. यवतमाळ	२७१	सुधाकर गणपत राउत	१ विहीर
२	२१/४७/२०१५-१६	तिवसा ता. यवतमाळ	१८४	राजश्री आनंदराव सुभेदार	१ विहीर
३	२१/४७/२०१५-१६	तिवसा ता. यवतमाळ	२६२ पै	बहिणाबाई केशव राठोड व इतर	१ विहीर
४	२१/४७/२०१५-१६	तिवसा ता. यवतमाळ	२६१	निर्मला मुकुंदराव सुभेदार व इतर	२ विहीर
५	२१/४७/२०१५-१६	तिवसा ता. यवतमाळ	२००	योगेश वामनराव राठोड	१ विहीर
६	२१/४७/२०१५-१६	तिवसा ता. यवतमाळ	१९९	स्मिता मोहन सुभेदार	१ विहीर
७	२१/४७/२०१५-१६	तिवसा ता. यवतमाळ	१९८ १९८	मोहन मुकुंद सुभेदार मोहन मुकुंद सुभेदार	१ विहीर १ विहीर
८	२१/४७/२०१५-१६	तिवसा ता. यवतमाळ	२९१	बबन राठोड	विहीर आढळून आलेली नाही
९	२१/४७/२०१५-१६	तिवसा ता. यवतमाळ	१७३	रविकांत मोहन राठोड	विहीर आढळून आलेली नाही
१०	२१/४७/२०१५-१६	तिवसा ता. यवतमाळ	१७२	नारायण परसराम राठोड	विहीर आढळून आलेली नाही
११	४१/४७/२००९-१०	कार्ली ता. यवतमाळ	१२२/३	विनोद काशीनाथ मलाडे	१ विहीर
१२	४१/४७/२००९-१०	कार्ली ता. यवतमाळ	१४३/१	गोदाबाई गदई	विहीर आढळून आलेली नाही
१३	१०/४७/२०१५-२०१६	बोथबोडन ता. यवतमाळ	१५५	हरिदास परसराम दाभेकर	१ विहीर
१४	१०/४७/२०१५-२०१६	बोथबोडन ता. यवतमाळ	१७	गनु बाबु राठोड	१ विहीर
१५	१०/४७/२०१५-२०१६	बोथबोडन ता. यवतमाळ	२१/४८	श्रीकृष्ण तुळशीराम तडसे	१ विहीर

वरील १३ लाभार्थ्यांचे विहीरीचे मुल्यांकन १ प्रतीत सादर करण्यात येत आहे.

सहपत्र:-

१. १३ लाभार्थ्यांचे विहीरीचे मुल्यांकन १ प्रतीत

कार्यकारी अभियंता

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT BOTHBODAN
NAME OF OWNER - SHRI HARIDAS PARSHRAM DABHEKAR SURVEY NO.155 BOTHBODAN

TQ - YAVATMAL

DIST - YAVATMAL

Year of Construction - 1999-2000

Sr No		Qty	Rate	Per	Total
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION In Soft Strata				
	LIFT - 0 to 1.50 M	45.26	269.00	Cum	12175.00
	LIFT - 1.5 to 3.00 M	33.19	291.00	Cum	9658.00
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION In Hard Strata				
	LIFT - 1.5 to 3.00 M	10.20	589.00	Cum	6008.00
	LIFT - 3.00 to 4.50 M	38.26	611.00	Cum	23377.00
	LIFT - 4.50 to 6.00 M	38.26	633.00	Cum	24219.00
	LIFT - 6.00 to 7.50 M	12.75	655.00	Cum	8351.00
3	Providing uncoursed rubble masonry of trap/granite/quartzite/ gneiss stones in cement mortar 1:6 in foundations and plinth of inner walls / in plinth of external walls including bailing out water, striking joints on unexposed faces and watering complete.				
	Bed concrete	0.798	4968.00	Cum	3964.00
	Wall Staining	18.29	1700.00	Cum	31093.00
4	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	4.98	61.00	Cum	304.00
TOTAL					119149.00

Deduction Depreciation Cost

8936

For 10 to 20 years depreciation shall be 7.5%

NET VALUTATION

110213.00

सहाय्यक अभियंत श्रेणी-९
जि.प.लघुसिंचन उपविभाग
यवतमाळ

Executive Engineer
(Irrigation Division)
Zilla Parishad Yavatmal

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT BOTHBODAN

NAME OF OWNER - SHRI HARIDAS PARSHRAM DABHEKAR SURVEY NO.155 BOTHBODAN

TQ - YAVATMAL

DIST - YAVATMAL

Year of Construction - 1999-2000

Sr No		Qty	Rate	Per	Total
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION In Soft Strata				
	LIFT - 0 to 1.50 M	45.26	269.00	Cum	12175.00
	LIFT - 1.5 to 3.00 M	33.19	291.00	Cum	9658.00
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION In Hard Strata				
	LIFT - 1.5 to 3.00 M	10.20	589.00	Cum	6008.00
	LIFT - 3.00 to 4.50 M	38.26	611.00	Cum	23377.00
	LIFT - 4.50 to 6.00 M	38.26	633.00	Cum	24219.00
	LIFT - 6.00 to 7.50 M	12.75	655.00	Cum	8351.00
3	Providing uncoursed rubble masonry of trap/granite/quartzite/ gneiss stones in cement mortar 1:6 in foundations and plinth of inner walls / in plinth of external walls including bailing out water, striking joints on unexposed faces and watering complete.				
	Bed concrete	0.798	4968.00	Cum	3964.00
	Wall Staining	18.29	1700.00	Cum	31093.00
4	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	4.98	61.00	Cum	304.00
	TOTAL				119149.00

Deduction Depreciation Cost

For 10 to 20 years depreciation shall be 7.5%

NET VALUTATION

8936

110213.00

सहाय्यक अभियंता श्रेणी-९
जि.प.लघुसिंचन उपविभाग
यवतमाळ

Executive Engineer
(Irrigation Division)
Zilla Parishad Yavatmal

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT BOTHBODAN
 NAME OF OWNER - SHRI SHRIKRUSHNA TULSHIRAM TADSE SURVEY NO 21/4/A

TQ - YAVATMAL

DIST - YAVATMAL

Year of Construction - 2010-11

Sr No		Qty	Rate	Per	Total
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION In Soft Strata				
	LIFT - 0 to 1.50 M	93.62	269.00	Cum	25184.00
	LIFT - 1.5 to 3.00 M	93.62	291.00	Cum	27243.00
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION In Hard Strata				
	LIFT - 3.00 to 4.50 M	75.62	611.00	Cum	46204.00
	LIFT - 4.50 to 6.00 M	75.62	633.00	Cum	47867.00
	LIFT - 6.00 to 7.50 M	75.62	655.00	Cum	49531.00
	LIFT - 7.50 to 9.00 M	65.53	677.00	Cum	44364.00
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4				
	For Bed Concrete	0.94	4968.00	Cum	4670.00
	Bottom beam	1.06	4968.00	Cum	5266.00
	For WELL Staining	14.23	4968.00	Cum	70695.00
4	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48	4.59	4978.30	Qt	22850.00
5	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	14.51	61.00	Cum	885.00
	TOTAL				344759.00

Deduction Depreciation Cost

For 10 to 20 years depreciation shall be 7.5%

NET VALUTATION

25857

318902.00

सहाय्यक अभियंता श्रेणी-9
 जि.प.लघुसिंचन उपविभाग
 यवतमाल

Executive Engineer
 (Irrigation Division)
 Zilla Parishad Yavatmal

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT BOTHBODAN
NAME OF OWNER - SHRI SHRIKRUSHNA TULSHIRAM TADSE SURVEY NO 21/4/A

TQ - YAVATMAL

DIST - YAVATMAL

Year of Construction - 2010-11

Sr No		No	L	B	D	Quantity	
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION	LIFT - 0 to 1.50 M	1	7.90	7.90	1.50	93.62
		LIFT - 1.5 to 3.00 M	1	7.90	7.90	1.50	93.62
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION	LIFT - 3.00 to 4.50 M	1	7.10	7.10	1.50	75.62
		LIFT - 4.50 to 6.00 M	1	7.10	7.10	1.50	75.62
		LIFT - 6.00 to 7.50 M	1	7.10	7.10	1.50	75.62
		LIFT - 7.50 to 9.00 M	1	7.10	7.10	1.30	65.53
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4	For Bed Concrete	0.785	7.90	7.10	0.10	0.94
		Bottom beam	0.785	7.56	7.10	0.20	1.06
		For WELL Staining	0.785	7.50	7.10	2.80	12.84
		Top beam	0.785	7.70	7.10	0.20	1.39
							14.23
4	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48	60 Kg / Cum of concrete 15.29 x 0.50			QT	4.59	
5	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	0.785	7.90	7.50	3.00	14.51	



सहाय्यक अभियंत श्रेणी-9
जि.प.लघुसिंचन उपविभाग
यवतमाळ

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT BOTHBODAN
NAME OF OWNER - SHRI GANU BABU RATHOD SURVEY NO.17 BOTHBODAN

TQ - YAVATMAL

DIST - YAVATMAL

Year of Construction - 1999-2000

Sr No		No	L	B	D	Quantity
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION					
	LIFT - 0 to 1.50 M	0.785	8.50	8.50	1.50	85.07
	LIFT - 1.5 to 3.00 M	0.785	8.50	8.50	0.75	42.54
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION					
	LIFT - 1.5 to 3.00 M	0.785	7.80	7.80	0.75	35.82
	LIFT - 3.00 to 4.50 M	0.785	7.80	7.80	1.50	71.64
	LIFT - 4.50 to 6.00 M	0.785	7.80	7.80	1.50	71.64
	LIFT - 6.00 to 7.50 M	0.785	7.80	7.80	0.70	33.43
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4					
	For Bed Concrete	0.785	8.40	7.80	0.10	0.76
	Bottom beam	0.785	8.26	7.80	0.20	1.16
	For WELL Staining	0.785	7.80	7.40	2.25	10.74
	Top beam	0.785	8.40	7.80	0.20	1.53
						14.19
	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48					
		40 Kg / Cum of concrete				
		14.19 x 0.60			QT	4.26
5	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41					
		0.785	8.50	7.80	2.25	50.94

JK

(Signature)

सहाय्यक अभियंता श्रेणी-9
जि.प.लघुसिंचन उपविभाग
यवतमाल

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT BOTHBODAN
NAME OF OWNER - SHRI GANU BABU RATHOD SURVEY NO.17 BOTHBODAN

TQ - YAVATMAL

DIST - YAVATMAL

Year of Construction - 1999-2000

Sr No		Qty	Rate	Per	Total
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION In Soft Strata				
	LIFT - 0 to 1.50 M	85.07	269.00	Cum	22884.00
	LIFT - 1.5 to 3.00 M	42.54	291.00	Cum	12379.00
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION In Hard Strata				
	LIFT - 1.5 to 3.00 M	35.82	589.00	Cum	21098.00
	LIFT - 3.00 to 4.50 M	71.64	611.00	Cum	43772.00
	LIFT - 4.50 to 6.00 M	71.64	633.00	Cum	45348.00
	LIFT - 6.00 to 7.50 M	33.43	655.00	Cum	21897.00
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4				
	For Bed Concrete	0.76	4968.00	Cum	3776.00
	Bottom beam	1.16	4968.00	Cum	5763.00
	For WELL Staining	10.74	4968.00	Cum	53356.00
	Top beam	1.53	4968.00	Cum	7601.00
		14.19			
4	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48	4.26	4978.30	Qt	21208.00
5	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	50.94	61.00	Cum	3107.00
TOTAL					262189.00

Deduction Depreciation Cost

For 10 to 20 years depreciation shall be 7.5%

NET VALUTATION

19664

242525.00

(Signature)

सहाय्यक अभियंता श्रेणी-9
जि.प.लघुसिंचन उपविभाग
यवतमाल

Executive Engineer
(Irrigation Division)
Zilla Parishad Yavatmal