



महाराष्ट्र शासन

वरिष्ठ भूवैज्ञानिक यांचे कार्यालय, भूजल सर्वेक्षण आणि विकास यंत्रणा

महाराष्ट्र जिवन प्राधिकरण इमारत, १ला माळा, गोधणी रोड, यवतमाळ-४४५००१

दुरध्वनी क्र-०७२३२-२४५३१०.२४४६८९ Email Id : sg\_yavatamal@rediffmail.com

जा.क्र.वभूवै/भूसवियं/यवत/तां/ २२५/ २०१७.

दि. १४/०३/ २०१७

प्रती

उपजिल्हाधिकारी (भूसंपादन)  
रस्ते प्रकल्प यवतमाळ.

विषय-वर्धा नांदेड रेल्वे प्रकल्प भूसंपादन विंघन विहिरीचे मुल्यमापन सादर करणेबाबत.

- संदर्भ- १) आपले कार्यालयीन पत्र क्र./कालि/भू.स. रस्ते.प्रकल्प/कावि/१५/२०१७ दि.२४.०१.२०१७.  
२) आपले कार्यालयीन पत्र क्र./कालि/भू.स. रस्ते.प्रकल्प/कावि/९२/२०१७ दि.२०.०१.२०१७.  
३) उपअभियंता (यांत्रिकी) उपविभाग जिल्हा परिषद,यवतमाळ यांचे पत्र क्र. उपअ(यां) उपवि  
जिप/यवत/१५७/२०१७,दि.१०.०३.२०१७.

उपरोक्त संदर्भिय पत्र क्र. १ व २ च्या अनुषंगाने वर्धा-नांदेड रेल्वे प्रकल्पाकरिता यवतमाळ तालुक्यातील मौजा-तळेगाव व कळंब तालुक्यातील मौजा-कळंब येथील संबधीत शेतक-यांच्या एकुण २ विंघन विहिरीचे या कार्यालयामार्फत मोजमाप करण्यात आलेले असुन संदर्भिय पत्र क्र.३ अन्वये सदरच्या विंघन विहिरीचे मुल्यांकन आपले माहितीस्तव सादर करण्यात येत आहे.  
माहिती तथा पुढील कार्यवाहीस्तव सादर करण्यात येत आहे.


सहपत्र

२) संदर्भिय पत्र क्र.३ ची प्रत

  
वरिष्ठ भूवैज्ञानिक  
भूजल सर्वेक्षण आणि विकास यंत्रणा  
यवतमाळ

प्रतिलिपी

- ३) मा.जिल्हाधिकारी ,यवतमाळ यांना माहितीस्तव सविनय सादर.  
४) उप मुख्य अभियंता(निर्माण)मध्य रेल्वे वर्धा यांना माहितीस्तव सादर.

४६२  
नीरगो वरिष्ठ  
जी.   
यवतमाळ  
१६-३-१७  
दि. भू.व.र.व.सो,स

जा.क्रं/उपअ(यां)उपवि/जिप/यवत/१५७/२०१७  
कार्यालय:-उपअभियंता(यांत्रिकी) उपविभाग  
जिल्हा परिषद,यवतमाळ दिनांक-१०/३/२०१७

प्रती,


वरिष्ठ भूवैज्ञानिक,  
भूजल सर्वेक्षण आणि विकास यंत्रणा,  
यवतमाळ

विषय:- वर्धा-नांदेड रेल्वे प्रकल्प भूसंपादन विंघन विहिरीचे मूल्यामापन सादर करणेबाबत

संदर्भ:- १. आपले कार्यालयीन पत्र क्रं भूसवियं/वभूवै/यवत/१९१०दनांक ७-३-२०१७.

उपरोक्त संदर्भिय विषयान्वये सादर करण्यात येते की, गाव निहाय शेत/जमिनधारकाचे नांव निहाय संदर्भिय पत्रामध्ये दिलेल्या विंघनविहिरीच्या खोली नूसार व केंसींग पाईप मिटर नूसार मूल्याकन करून सहपत्रात सादर करण्यात येत आहे.


सहपत्र:-एकूण २ गावाचे मूल्यांकन.

  
उपअभियंता(यांत्रिकी)  
उपविभाग जिल्हा परिषद, यवतमाळ.  
रिता



विंघन विहिरीचे मुल्यांकन अहवाल प्रपत्र.

अ.क्र.	गावाचे नांव	शेत/जमिनधधारकाचे नांव सर्वश्री	गट क्रमांक	विंघन विहिरीची प्रत्यक्ष खोली मिटर मध्ये	दर	किंमत	केसिंग खोली मिटर मध्ये	दर	किंमत	एकूण	शेरा
१.	कंळब	दिगांबर दत्तात्रय उन्नतकर	३१३	११.५०	३१०	२८३६५	१३.००	११६०	१५०८०	४३४४५	लोखंडी केसिंग
२.	तळेगाव	मूलराजसिंह जगत बहादूर सोमवंशी	२१/१	८५.३४	३१०	२६४५५	२४.३८	६२०	१५११६	४१५७१	पी.व्ही.सी.केसिंग

  
 सप अभियंता (धा.)  
 यांत्रिकी उप विभाग  
 जि. प. यवतमाञ्ज

HCL Satpute Tech.- 1780 -

## जिल्हा परिषद सिंचन विभाग यवतमाळ

दालन क्र.२०७, दुसरा माळा, जिल्हा परिषद प्रशासकिय इमारत आर्णी रोड, यवतमाळ ४४५००१  
दूरध्वनी क्र.०७२३२-२४५२५८ फॅक्स क्र.०७२३२-२४४३९७ ई-मेल eezpirrytl@gmail.com

७४७

क्रमांक/यजिप/सिंचन/भुस/वशि/१२४/२०१७

दिनांक :- १९/११/१७

प्रति,

उपजिल्हाधिकारी (भुसंपादन)  
रस्ते प्रकल्प यवतमाळ

विषय :- अनुसुचितील विहीर व इतर बांधकामाचे मुल्यांकन अहवाल सादर करण्याबाबत.

संदर्भ :- १. आपले पत्र क्र. अका/भु.स/रस्ते प्रकल्प/कावि/१०६०/दि.२२.१२.२०१६  
२. सहाय्यक अभियंता(श्रेणी-१) जि.प.सिंचन उपविभाग यवतमाळ यांचे पत्र क्र.३१/दि.१७.१.२०१७

उपरोक्त संदर्भांकित विषयाचे अनुषंगाने अनुसुचितील विहीर व इतर बांधकामाचे मुल्यांकन


अहवाल खालील प्रमाणे

अ.क्र	भसुपादन प्रकरण क्र.	गावाचे नाव	गट क्र जुना/ नवीन	शेतमालकाचे नाव	संबंधितांचे शेतातील बाब
१.	१९/४७/२००९-१०	कळंब -१	३१३	दिगांबर उमरकर	दत्तराव १ विहीर

वरील लाभार्थ्यांचे विहीरीचे मुल्यांकन १ प्रतीत सादर करण्यात येत आहे.

सहपत्र:-

१. विहीरीचे मुल्यांकन १ प्रतीत

  
कार्यकारी अभियंता  
जि.प.सिंचन विभाग यवतमाळ

प्रतिलिपी:-

उप अभियंता लघु सिंचन उप विभाग यवतमाळ यांना माहिती करिता अग्रेषित.

गवणी क्रमांक (२६) दिनांक २०/१/१७  
श्री. रामे, यवतमाळ  
वि.पु.व.प.सि.स.  
यवतमाळ



NAME OF WORK - VALUTATION OF IRRIGATION WELL AT KALAMB KH NO 1  
 NAME OF OWNER - SHRI DINGAMBER DATTATRA UMRATKAR SURVEY NO 313

TQ - KALAMB

DIST - YAVATMAL

Year of Construction - 2011-12

Sr No		Qty	Rate	Per	Total
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION In Soft Strata LIFT - 0 to 1.50 M	42.39	269.00	Cum	11403.00
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION In Hard Strata LIFT - 1.5 to 3.00 M	42.39	589.00	Cum	24968.00
	LIFT - 3.00 to 4.50 M	42.39	611.00	Cum	25900.00
	LIFT - 4.50 to 6.00 M	42.39	633.00	Cum	26833.00
	LIFT - 6.00 to 7.50 M	8.48	655.00	Cum	5554.00
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4 For Bed Concrete	0	0.00	Cum	0.00
4	Providing and Constructing UCR Masonary in CM 1.6 MJP CSR 2015-16 Item NO 2 P.No.20 For WELL Staining	0	0.00	Cum	0.00
5	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48	0	0.00	Qt	0.00
6	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	0	0.00	Cum	0.00
	TOTAL				94658.00

Deduction Depreciation Cost

3Years @ 5 %

NET VALUTATION

14199

80459.00

Assistant Engineer (Grade-I)

M. S. Division

Executive Engineer  
Irrigation Division


NAME OF WORK - VALUTATION OF IRRIGATION WELL AT KALAMB KH NO 1  
 NAME OF OWNER - SHRI DINGAMBER DATTATRA UMRATKAR SURVEY NO 313


TQ - KALAMB

DIST - YAVATMAL

Year of Construction - 2011-12

Sr No		No	L	B	D	Quantity
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION  LIFT - 0 to 1.50 M	0.785	6.00	6.00	1.50	42.39
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION  LIFT - 1.5 to 3.00 M LIFT - 3.00 to 4.50 M LIFT - 4.50 to 6.00 M LIFT - 6.00 to 7.50 M	0.785 0.785 0.785 0.785	6.00 6.00 6.00 6.00	6.00 6.00 6.00 6.00	1.50 1.50 1.50 0.30	42.39 42.39 42.39 8.48
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4 For Bed Concrete	0	0.00	0.00	0.00	0
4	Providing and Constructing UCR Masonary in CM 1.6 MJP CSR 2015-16 Item NO 2 P.No.20 For WELL Staining	0	0.00	0.00	0.00	0
5	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48	60 Kg / Cum of concrete 0.00	0.00		QT	0
6	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	0	0.00	0.00	0.00	0

  
 Assistant Engineer(Grade-I)  
 M.I. Sub-Divison  
 Z.P.Yavatmal

  
 Executive Engineer  
 Irrigation Division  
 Z.P.Yavatmal