

जिल्हा परिषद सिंचन विभाग यवतमाळ

दालन क्र.२०७, दुसरा माळा, जिल्हा परिषद प्रशासकिय इमारत आर्णी रोड, यवतमाळ ४४५००१
दूरध्वनी क्र.०७२३२-२४५२५८ फॅक्स क्र.०७२३२-२४४३९७ ई-मेल eezpirytl@gmail.com

क्रमांक/यजिप/सिंचन/भुस/वशि/२२/१०९६

दिनांक :- १९/११/२०१६

प्रति,

✓ उपजिल्हाधिकारी (भुसंपादन)
रस्ते प्रकल्प यवतमाळ

विषय :- अनुसुचितील विहीर व इतर बांधकामाचे मुल्यांकन अहवाल सादर करण्याबाबत.

संदर्भ :- १. आपले पत्र क्र. अका/भु.स/रस्ते प्रकल्प/कावि/७५६/दि.५.८.२०१६
२. सहाय्यक अभियंता (श्रेणी-१) जि.प.सिंचन उपविभाग यवतमाळ यांचे पत्र क्र.८४३/दि.१८.११.२०१६

उपरोक्त संदर्भाकित विषयाचे अनुषंगाने अनुसुचितील विहीर व इतर बांधकामाचे मुल्यांकन अहवाल खालील प्रमाणे

अ.क्र	भसुपादन प्रकरण क्र.	गावाचे नाव	गट क्र जुना/ नवीन	शेतमालकाचे नाव	संबंधिताचे शेतीतील बाव
१.	४२/४७/२००९-१०	पारवा ✓	८० ✓	सौ शोभा पदमचंद बाफना आरीफ खॉन	१ विहीर
२.	४४/४७/२००९-१०	तळेगाव ✓	१००	फैजल अली खॉन काजी	१ विहीर
३.	४४/४७/२००९-१०	तळेगाव ✓	१०८	पुंडलिक नागोराव खोब्रागडे	१ विहीर
४.	४४/४७/२००९-१०	तळेगाव ✓	१०८	रुखमाबाई देवराव कांबळे	१ विहीर
५.	४१/४७/२००९-१०	काली ✓	१२३	महेश यशवं देशमुख	१ विहीर
६.	४१/४७/२००९-१०	काली	१२१	प्रशांत रामराव जिरापुरे +३	१ विहीर
७.	४१/४७/२००९-१०	काली	१२२	दत्ता शंकरराव गाढवे	१ विहीर
८.	४१/४७/२००९-१०	काली	१२८	सुर्यभान मुकिंदा यदमल	१ विहीर
९.	४४/४७/२००९-१०	तळेगाव ✓	१३०	सिताबाई सुरेश चारमलकर	१ विहीर
१०.	४४/४७/२००९-१०	तळेगाव /	१३०	मारोती सखाराम गोंडे	१ विहीर
११.	४४/४७/२००९-१०	तळेगाव /	१४३	श्रीमती गोदाबाई अजाबराव गदई	१ विहीर कच्ची

वरील लाभार्थ्यांचे विहीरीचे मुल्यांकन १ प्रतीत सादर करण्यात येत आहे.
सहपत्र :- ११ विहीरीचे मुल्यांकन १ प्रतीत

नांदणी क्रमांक - १२२ दिनांक १९/११/०९६

श्री. ग. ग. प्रशासक

कार्यकारी अभियंता

जि.प.सिंचन विभाग यवतमाळ

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT PARWA
NAME OF OWNER - SAU.SHOBHA PADMCHAND BAPHANA GUT NO 80

TQ - YAVATMAL

DIST - YAVATMAL

Year of Construction - 1999

Sr No		Qty	Rate	Per	Total
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION In Soft Strata				
	LIFT - 0 to 1.50 M	230.79	269.00	Cum	62083.00
	LIFT - 1.5 to 3.00 M	230.79	291.00	Cum	67160.00
	LIFT - 3.00 to 4.50 M	153.86	313.00	Cum	48158.00
	LIFT - 3.00 to 4.50 M	39.25	313.00	Cum	12285.00
	LIFT - 4.50 to 6.00 M	117.75	335.00	Cum	39446.00
	LIFT - 6.00 to 7.50 M	15.70	357.00	Cum	5605.00
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION In Hard Strata				
	LIFT - 1.5 to 3.00 M	0	0.00	Cum	0.00
	LIFT - 3.00 to 4.50 M	0	0.00	Cum	0.00
	LIFT - 4.50 to 6.00 M	0	0.00	Cum	0.00
	LIFT - 6.00 to 7.50 M	70.30	655.00	Cum	46047.00
	LIFT - 7.50 to 9.00 M	81.12	677.00	Cum	54918.00
	LIFT - 9.00 to 10.50 M	75.36	699.00	Cum	52677.00
	LIFT - 10.50 to 12.00 M	75.36	721.00	Cum	54335.00
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4 For Bed Concrete	1.85	4968.00	Cum	9191.00
4	Providing and Constructing B B Masonary in CM 1.6 MJP CSR 2015-16 Item NO 2a P.No.45 For WELL Staining	25.35	4500.00	Cum	114075.00
5	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48	1.11	4978.30	Qt	5526.00
6	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	8.95	61.00	Cum	546.00
	TOTAL				572052.00

Deduction Depreciation Cost

15 Years @ 5 %

NET VALUTATION

429039

143013.00

SECTIONAL ENGINEER

ASSITANT ENGINEER (GR.I)
Z.P.M.I.SUB DN.YAVATMAL

Executive Engineer
EXECUTIVE ENGINEER
(Irrigation Division)
Z.P.M.I. DN.YAVATMAL
Zilla Parishad Yavatmal

NAME OF WORK - VALUTATION OF IRRIGATION WELL AT PARWA
NAME OF OWNER - SAU.SHOBHA PADMCHAND BAPHANA GUT NO 80

TQ - YAVATMAL

DIST - YAVATMAL

Year of Construction - 1999

Sr No		No	L	B	D	Quantity
1	Excavation in SOFT STRATA of soil/lime/sand Hard Murum / Soft Rock including conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge MJP CSR 2015-16 Item NO 10 / Page NO 39 WELL EXCAVATION					
	LIFT - 0 to 1.50 M	0.785	14.00	14.00	1.50	230.79
	LIFT - 1.5 to 3.00 M	0.785	14.00	14.00	1.50	230.79
	LIFT - 3.00 to 4.50 M	0.785	14.00	14.00	1.00	153.86
	LIFT - 3.00 to 4.50 M	0.785	10.00	10.00	0.50	39.25
	LIFT - 4.50 to 6.00 M	0.785	10.00	10.00	1.50	117.75
	LIFT - 6.00 to 7.50 M	0.785	10.00	10.00	0.20	15.70
2	Excavation in HARD STRATA Of Hard Rock conveying excavated material with 10m lead & 1.5 m lift etc complete as directed by Engineer in charge Irr CSR Item no 4 P no 8) MJP CSR 2015-16 Item NO 11 / Page No 39 WELL EXCAVATION					
	LIFT - 1.5 to 3.00 M	0.785	4.70	4.70	0.00	0
	LIFT - 3.00 to 4.50 M	0.785	4.70	4.70	0.00	0
	LIFT - 4.50 to 6.00 M	0.785	4.70	4.70	0.00	0
	LIFT - 6.00 to 7.50 M	0.785	8.30	8.30	1.30	70.3
	LIFT - 7.50 to 9.00 M	0.785	8.30	8.30	1.50	81.12
	LIFT - 9.00 to 10.50 M	0.785	8.00	8.00	1.50	75.36
	LIFT - 10.50 to 12.00 M	0.785	8.00	8.00	1.50	75.36
3	Providing & laying situ following grades of cc of trap/granite/quartzite/gneiss metal for foundation and bedding including dewatering form work ,compacting and curing,finishing, MJP CSR 2015-16 Item NO 2a P.No.45 RCC 1:2:4 For Bed Concrete	0.785	9.20	8.30	0.15	1.85
4	Providing and Constructing B B Masonary in CM 1.6 MJP CSR 2015-16 Item NO 2a P.No.45 For WELL Staining	0.785	9.20	8.30	2.05	25.35
5	Providing and laying M.S.reinforcement including cutting,bending,hooking,binding wires or tuck welding including cost of binding wires & labour including fixing in position etc complete MJP CSR 2015-16 Item NO 8a P.No.48	60 Kg / Cum of concrete 1.85 x 0.60			QT	1.11
6	Providing backfilling behind head wall from approved material obtained from excavated material including dressing watering consolidation etc complete with all leads and lifts MJP CSR 2015-16 Item NO 16 P.No.41	0.785	6.00	5.70	2.90	8.95

SECTIONAL ENGINEER

ASSITANT ENGINEER (GR.I)
Z.P.M.I.SUB DN.YAVATMAL