

**OFFICE OF THE PANCHAYAT SAMITI ,BARIPADA,  
DIST-MAYURBHANJ**

**NAME OF WORK :-** \_\_\_\_\_

\_\_\_\_\_

**ISSUED TO:.....**

**CHECK LIST.**  
**(TO BE FILLED IN BY THE TENDERER)**  
**( Individual Application for Separate Works)**

1. Name of Tenderer: .....
2. Registration of License Valid up to: .....
3. Name of the work: .....
4. Amount put to tender (In percentage).....
5. EMD deposited by the tender in shape  
(N.S.C.)                      Rs.....Pledged/ Not pledged.
6. Tender paper Cost Submitted in shape (N.S.C./DD)                      Yes/ No.
7. Whether the Tenderer Furnished PAN Card:                      Yes/ No.
8. Whether the Tenderer furnished GST No:                      Yes/ No.
9. Whether the Tenderer furnished labour License:                      Yes/ No.
10. Date of submission of tender: .....
11. Documents and certificates submitted.....No. of sheets.
12. IT Return Certified Turn overfurnished                      Yes/ No.
13.  
A)Total over writing.                      Nos.  
B)Corrections(Both in figures and words:                      Nos.  
C) Interpolations(Both in figures and words).                      Nos.

**Declaration:** The above statement furnished in the Tender document for the work mentioned above are true to the best of my knowledge and belief.

# BILL OF QUANTITY

**Name of the Project :- Construction of new model  
AWC at Gopalpur**


**G.P.--Sankhabhanga**

SI No	item of Work	Quantity	Unit	Rate	Amount
1	Earth work in excavation of foundation in hard soil within initial lead and lift including rough dressing and breaking clods etc. complete	85.33	One cum	178.60	15239.71
2	Sand filling in foundation and plinth with well watered and remmend	38.69	One cum	390.05	15090.2
3	Cement concreet (1:3:6) with 4cm size hard grantie metal of approved quality and approved quarry in foundation including hoisting laying concrete with cost conveyance of materials including watering curing royalty all T&P required for the work etc complete as per direction of the Er. in charge.	16.53	One cum	4,178.40	69060.19
4	Flyash Bricks (25cmx12cmx8cm) masonary in cm (1:6) for Superstructure with all cost conveyancy Royalty etc.				
	a) In foundation	30.88	One cum	4,023.90	124266.9
	b) In Superstructure	50.62	One cum	4,102.00	207638.39
5	Flyash Bricks (25cmx12cmx8cm) masonary in cm (1:4) for Superstructure with all cost conveyancy Royalty etc.	0.43	One cum	4,451.27	1914.05
6	Reinforcement cement concrete M-20 grade with 20mm and down grade block hard granite (Crusher broken) stone chips including hoisting and laying including cost. Conveyance ,royalties. Taxes etc complete as per the direction of the eng. In charge.				
	a) Column Base	15.22	One cum	4,700.33	71553.23
	b) Plinth bend)	7.63	One cum	5,040.35	38479.53
	c) Lintel Band	2.57	One cum	8,082.60	20772.28
	d) Chajja	18.94	One sqmt	736.43	13948.03
	e) Column & Roof beam	8.03	One cum	10164.06	81638.06
	e) Slab	11.32	One cum	8,661.60	98049.31
7	Providing HYSD bar reinforcement for R.C.C work including straightening cutting, bending, binding, welding, tying the girls, lying and placing in proper position as per approved design and drawing including cost. Conveyance of 18 to 20 gauge binding wire cost and conveyance of HYSD bar complete in all respect as per specification for road & Bridge and dirction of Eng-In charge	40.12	One cum	6,006.50	240960.5
8	Grading work with 6mm size cbg chipes, etc.	100.20	One sqmt	274.40	27494.11
9	25mm thik A.S floring in cement concrete in cm (1:2:4) using 12mm size h.g.c.b chips including punning with all cost conveyancy Royalty etc complete.	69.48	One sqmt	287.10	19948.22
10	Fixing tiles in floors, treads and landings on 25mm thik bed of cement mortar (1:1) joined with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing including cost of tiles.	7.03	One sqmt	910.90	6399.16
11	Fixing tiles in dabos, skirting and in rises of steepos on 12 mm thik bed of cement plaster (1:3) joined with neat cement slurry mixed with pigmwnt to match the shade of the tiles including rubbing and polishing including cost of tile.	34.02	One sqmt	682.70	23227.98

12	16mm(5/8") thick cement plaster (1:6) in finishing smooth to inside rough surface of 10" thick brick walls after rcking out the joints including watering and curing with cost. Conveyance royalty , all tax of all materials and cost of all labour with T&P required for the work etc.	257.41	One Qntl	186.50	48007.33
13	12mm (1/2") thick cement plaster (1:6) in finishing smooth to outside smooth surface of brick walls after racing out joints including watering and curing etc. complete with cost. Conveyance royalties, all taxes and cost of all materials and cost. Of all labour with T&P required for the work.	238.50	One sqmt	130.70	31171.63
14	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slury treatment including punning including cost, conveyance & royalty of materials.	78.62	One sqmt	146.20	11493.61
15	12mm thick cement plaster in cement mortar (1:4) over brick work including cement punning and bitumen painting with cost, conveyance & royalty of materials.	42.53	One sqmt	158.10	6723.99
16	Supplying Fitting & fixing of MS Door & Window including cost of all materials etc complete as per the	780.88	One Kg	87.17	68071.31
17	Painting two coats with enamel paint over priming one coats with ready mixed zinc chromate yellow primer of approved brand on wood work including labour & material charges.	63.32	One sqmt	181.80	11512.11
18	Provision for fitting and fixing and cost of ventilator etc complete.				
	a) Ventilator	14.00	No	150.00	2100.00
19	Distempering two coat of walls with distemper of approved shade on new work to give and even shade including cost of Distempering	221.00	One sqmt	61.60	13613.7
20	Cement concrete in cm (1:2:4) using 12mm size h.g.c.b chips with all cost conveyance Royalty etc complete	0.37	One cum	5644.90	2105.87
21	10cm thik dry brick khao well watered & rammed to receive A.S flooring including all cost etc complete.	0.45	One cum	230.60	103.77
22	Finshing walls with water proofing cement cement paint of approved shade on new work one coats to give aneven shade over a caot of cement washing	344.27	One sqmt	31.70	10913.47
23	Add for Black Board				5000.00
24	Add for Bala Painting as per guidline to interior & exterior of building with boundary wall				19000.00
25	Add for Electrification & Sanitary work with over head tank and all fitting & fixing including playing equipments.				31293.00
26	Add for sign Board				2500.00
					1339289.64

(26 nos of items has been  
Technically sanncioned)

  
JE / GPTA  
Baripada Block

  
Asst. Ex-Engineer  
Baripada Block

APPROVED

  
Block Development Officer  
Baripada Block

# BILL OF QUANTITY

**Name of the Project :- Construction of new model  
AWC at Dumapada**

**G.P.--Khadisole**

SI No	item of Work	Quantity	Unit	Rate	Amount
1	Earth work in excavation of foundation in hard soil within initial lead and lift including rough dressing and breaking clods etc. complete	85.33	One cum	178.60	15239.71
2	Sand filling in foundation and plinth with well watered and remmend	38.69	One cum	390.05	15090.2
3	Cement concreet (1:3:6) with 4cm size hard grantie metal of approved quality and approved quarry in foundation including hoisting laying concrete with cost conveyance of materials including watering curing royalty all T&P required for the work etc complete as per direction of the Er. in charge.	16.53	One cum	4,178.40	69060.19
4	Flyash Bricks (25cmx12cmx8cm) masonry in cm (1:6) for Superstructure with all cost conveyancy Royalty etc.				
	a) In foundation	30.88	One cum	4,023.90	124266.9
	b) In Superstructure	50.62	One cum	4,102.00	207638.39
5	Flyash Bricks (25cmx12cmx8cm) masonry in cm (1:4) for Superstructure with all cost conveyancy Royalty etc.	0.43	One cum	4,451.27	1914.05
6	Reinforcement cement concrete M-20 grade with 20mm and down grade block hard granite (Crusher broken) stone chips including hoisting and laying including cost. Conveyance ,royalties. Taxes etc complete as per the direction of the eng. In charge.				
	a) Column Base	15.22	One cum	4,700.33	71553.23
	b) Plinth bend)	7.63	One cum	5,040.35	38479.53
	c) Lintel Band	2.57	One cum	8,082.60	20772.28
	d) Chajja	18.94	One sqmt	736.43	13948.03
	e) Column & Roof beam	8.03	One cum	10164.06	81638.06
	e) Slab	11.32	One cum	8,661.60	98049.31
7	Providing HYSD bar reinforcement for R.C.C work including straightening cutting, bending, binding, welding, tying the girls, lying and placing in proper position as per approved design and drawing including cost. Conveyance of 18 to 20 gauge binding wire cost and conveyance of HYSD bar complete in all respect as per specification for road & Bridge and dirction of Eng-In charge	40.12	One cum	6,006.50	240960.5
8	Grading work with 6mm size cbg chipes, etc.	100.20	One sqmt	274.40	27494.11
9	25mm thik A.S floring in cement concrete in cm (1:2:4) using 12mm size h.g.c.b chips including punning with all cost conveyancy Royalty etc complete.	69.48	One sqmt	287.10	19948.22
10	Fixing tiles in floors, treads and landings on 25mm thik bed of cement mortar (1:1) joined with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing including cost of tiles.	7.03	One sqmt	910.90	6399.16
11	Fixing tiles in dabos, skirting and in rises of steops on 12 mm thik bed of cement plaster (1:3) joined with neat cement slurry mixed with pigmwnt to match the shade of the tiles inluding rubbing and polishing including cost of tile.	34.02	One sqmt	682.70	23227.98

12	16mm(5/8") thick cement plaster (1:6) in finishing smooth to inside rough surface of 10" thick brick walls after rcking out the joints including watering and curing with cost. Convayance royalty , all tax of all materials and cost of all labour with T&P required for the work etc.	257.41	One Qntf	186.50	48007.33
13	12mm (1/2") thick cement plaster (1:6) in finishing smooth to outside smooth surface of brick walls after racing out joints including watering and curing etc. complete with cost. Conveyance royalties, all taxes and cost of all materials and cost. Of all labour with T&P required for the work.	238.50	One sqmt	130.70	31171.63
14	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slury treatment including punning including cost, conveyance & royalty of materials.	78.62	One sqmt	146.20	11493.61
15	12mm thick cement plaster in cement mortar (1:4) over brick work including cement punning and bitumen painting with cost, conveyance & royalty of materials.	42.53	One sqmt	158.10	6723.99
16	Supplying Fitting & fixing of MS Door & Window including cost of all materials etc complete as per the	780.88	One Kg	87.17	68071.31
17	Painting two coats with enamel paint over priming one coats with ready mixed zinc chromate yellow primer of approved brand on wood work including labour & material charges.	63.32	One sqmt	181.80	11512.11
18	Provision for fitting and fixing and cost of ventilator etc complete.				
	a) Ventilator	14.00	No	150.00	2100.00
19	Distempering two coat of walls with distemper of approved shade on new work to give and even shade including cost of Distempering	221.00	One sqmt	61.60	13613.7
20	Cement concrete in cm (1:2:4) using 12mm size h.g.c.b chips with all cost conveyance Royalty etc complete	0.37	One cum	5644.90	2105.87
21	10cm thick dry brick khao well watered & rammed to receive A.S flooring including all cost etc complete.	0.45	One cum	230.60	103.77
22	Finshing walls with water proofing cement cement paint of approved shade on new work one coats to give aneven shade over a caot of cement washing	344.27	One sqmt	31.70	10913.47
23	Add for Black Board				5000.00
24	Add for Bala Painting as per guidline to interior & exterior of building with boundary wall				19000.00
25	Add for Electrification & Sanitary work with over head tank and all fitting & fixing including playing equipments.				31293.00
26	Add for sign Board				2500.00
					1339289.64

(26 nos of items has been

Technically sanncioned)

*R. Mallik*  
12/04/21  
JE / GPTA  
Baripada Block

*Mid*  
12/04/21  
Asst. Ex-Engineer  
Baripada Block

APPROVED

*U. S. S.*  
12/04/21  
Block Development Officer  
Baripada Block

# BILL OF QUANTITY

**Name of the Project :- Construction of new model  
AWC at K.C.Pur-E**

**G.P.--Badjode**

SI No	item of Work	Quantity	Unit	Rate	Amount
1	Earth work in excavation of foundation in hard soil within initial lead and lift including rough dressing and breaking clods etc. complete	85.33	One cum	178.60	15239.71
2	Sand filling in foundation and plinth with well watered and remmend	38.69	One cum	390.05	15090.2
3	Cement concreet (1:3:6) with 4cm size hard grantie metal of approved quality and approved quarry in foundation including hoisting laying concrete with cost conveyance of materials including watering curing royalty all T&P required for the work etc complete as per direction of the Er. in charge.	16.53	One cum	4,178.40	69060.19
4	Flyash Bricks (25cmx12cmx8cm) masonry in cm (1:6) for Superstructure with all cost conveyancy Royalty etc.				
	a) In foundation	30.88	One cum	4,023.90	124266.9
	b) In Superstructure	50.62	One cum	4,102.00	207638.39
5	Flyash Bricks (25cmx12cmx8cm) masonry in cm (1:4) for Superstructure with all cost conveyancy Royalty etc.	0.43	One cum	4,451.27	1914.05
6	Reinforcement cement concrete M-20 grade with 20mm and down grade block hard granite (Crusher broken) stone chips including hoisting and laying including cost. Conveyance ,royalties. Taxes etc complete as per the direction of the eng. In charge.				
	a) Column Base	15.22	One cum	4,700.33	71553.23
	b) Plinth bend)	7.63	One cum	5,040.35	38479.53
	c) Lintel Band	2.57	One cum	8,082.60	20772.28
	d) Chajja	18.94	One sqmt	736.43	13948.03
	e) Cofumn & Roof beam	8.03	One cum	10164.06	81638.06
	e) Slab	11.32	One cum	8,661.60	98049.31
7	Providing HYSD bar reinforcement for R.C.C work including straightening cutting, bending, binding, welding, tying the girls, lying and placing in proper position as per approved design and drawing including cost. Conveyance of 18 to 20 gauge binding wire cost and conveyance of HYSD bar complete in all respect as per specification for road & Bridge and dirction of Eng-In charge	40.12	One cum	6,006.50	240960.5
8	Grading work with 6mm size cbg chipes, etc.	100.20	One sqmt	274.40	27494.11
9	25mm thik A.S floring in cement concrete in cm (1:2:4) using 12mm size h.g.c.b chips including punning with all cost conveyancy Royalty etc complete.	69.48	One sqmt	287.10	19948.22
10	Fixing tiles in floors, treads and landings on 25mm thik bed of cement mortar (1:1) joined with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing including cost of tiles.	7.03	One sqmt	910.90	6399.16
11	Fixing tiles in dabos, skirting and in rises of steops on 12 mm thik bed of cement plaster (1:3) joined with neat cement slurry mixed with pigmwnt to match the shade of the tiles inluding rubbing and polishing including cost of tile.	34.02	One sqmt	682.70	23227.98

12	16mm(5/8") thik cement plaster (1:6) in finishing smooth to inside rough surface of 10" thik brick walls after rcking out the joints including watering and curing with cost. Convayance royalty , all tax of all materials and cost of all labour with T&P required for the work etc.	257.41	One Qntl	186.50	48007.33
13	12mm (1/2") thick cement plaster (1:6) in finishing smooth to outside smooth surface of brick walls after racing out joints including watering and curing etc. complete with cost. Conveyance royalties, all taxes and cost of all materials and cost. Of all labour with T&P required for the work.	238.50	One sqmt	130.70	31171.63
14	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slury treatment including punning including cost, conveyance & royalty of materials.	78.62	One sqmt	146.20	11493.61
15	12mm thick cement plaster in cement mortar (1:4) over brick work including cement punning and bitumen painting with cost, conveyance & royalty of materials.	42.53	One sqmt	158.10	6723.99
16	Supplying Fitting & fixing of MS Door & Window including cost of all materials etc complete as per the	780.88	One Kg	87.17	68071.31
17	Painting two coats with enamel paint over priming one coats with ready mixed zinc chromate yellow primer of approved brand on wood work including labour & material charges.	63.32	One sqmt	181.80	11512.11
18	Provision for fitting and fixing and cost of ventilator etc complete.				
	a) Ventilator	14.00	No	150.00	2100.00
19	Distempering two coat of walls with distemper of approved shade on new work to give and even shade including cost of Distempering	221.00	One sqmt	61.60	13613.7
20	Cement concrete in cm (1:2:4) using 12mm size h.g.c.b chips with all cost conveyance Royalty etc complete	0.37	One cum	5644.90	2105.87
21	10cm thik dry brick khao well watered & rammed to receive A.S flooring including all cost etc complete.	0.45	One cum	230.60	103.77
22	Finshing walls with water proofing cement cement paint of approved shade on new work one coats to give aneven shade over a caot of cement washing	344.27	One sqmt	31.70	10913.47
23	Add for Black Board				5000.00
24	Add for Bala Painting as per guidline to interior & exterior of building with boundary wall				19000.00
25	Add for Electrification & Sanitary work with over head tank and all fitting & fixing including playing equipments.				31293.00
26	Add for sign Board				2500.00
					1339289.64

(26 nos of items has been

Technically sanncioned)

*Wallia*  
12/4/21  
JE / GPTA  
Baripada Block

*[Signature]*  
12/4/21  
Asst. Ex-Engineer  
Baripada Block

APPROVED

*[Signature]*  
12/4/21  
Block Development Officer  
Baripada Block



# BILL OF QUANTITY

**Name of the Project :- Construction of new model  
AWC at Meghamari**

**G.P.--Chandanpur**

SI No	Item of Work	Quantity	Unit	Rate	Amount
1	Earth work in excavation of foundation in hard soil within initial lead and lift including rough dressing and breaking clods etc. complete	85.33	One cum	178.60	15239.71
2	Sand filling in foundation and plinth with well watered and remmend	38.69	One cum	390.05	15090.2
3	Cement concreet (1:3:6) with 4cm size hard grantie metal of approved quality and approved quarry in foundation including hoisting laying concrete with cost conveyance of materials including watering curing royalty all T&P required for the work etc complete as per direction of the Er. in charge.	16.53	One cum	4,178.40	69060.19
4	Flyash Bricks (25cmx12cmx8cm) masonry in cm (1:6) for Superstructure with all cost conveyancy Royalty etc.				
	a) In foundation	30.88	One cum	4,023.90	124266.9
	b) In Superstructure	50.62	One cum	4,102.00	207638.39
5	Flyash Bricks (25cmx12cmx8cm) masonry in cm (1:4) for Superstructure with all cost conveyancy Royalty etc.	0.43	One cum	4,451.27	1914.05
6	Reinforcement cement concrete M-20 grade with 20mm and down grade block hard granite (Crusher broken) stone chips including hoisting and laying including cost. Conveyance ,royalties. Taxes etc complete as per the direction of the eng. In charge.				
	a) Column Base	15.22	One cum	4,700.33	71553.23
	b) Plinth bend)	7.63	One cum	5,040.35	38479.53
	c) Lintel Band	2.57	One cum	8,082.60	20772.28
	d) Chajja	18.94	One sqmt	736.43	13948.03
	e) Column & Roof beam	8.03	One cum	10164.06	81638.06
	e) Slab	11.32	One cum	8,661.60	98049.31
7	Providing HYSD bar reinforcement for R.C.C work including straightening cutting, bending, binding, welding, tying the girls, lying and placing in proper position as per approved design and drawing including cost. Conveyance of 18 to 20 gauge binding wire cost and conveyance of HYSD bar complete in all respect as per specification for road & Bridge and dirction of Eng-In charge	40.12	One cum	6,006.50	240960.5
8	Grading work with 6mm size cbg chipes, etc.	100.20	One sqmt	274.40	27494.11
9	25mm thik A.S floring in cement concrete in cm (1:2:4) using 12mm size h.g.c.b chips including punning with all cost conveyancy Royalty etc complete.	69.48	One sqmt	287.10	19948.22
10	Fixing tiles in floors, treads and landings on 25mm thik bed of cement mortar (1:1) joined with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing including cost of tiles.	7.03	One sqmt	910.90	6399.16
11	Fixing tiles in dabos, skirting and in rises of steops on 12 mm thik bed of cement plaster (1:3) joined with neat cement slurry mixed with pigmwnt to match the shade of the tiles inluding rubbing and polishing including cost of tile.	34.02	One sqmt	682.70	23227.98

12	16mm(5/8") thick cement plaster (1:6) in finishing smooth to inside rough surface of 10" thick brick walls after rcking out the joints including watering and curing with cost. Convayance royalty , all tax of all materials and cost of all labour with T&P required for the work etc.	257.41	One Qntl	186.50	48007.33
13	12mm (1/2") thick cement plaster (1:6) in finishing smooth to outside smooth surface of brick walls after racing out joints including watering and curing etc. complete with cost. Conveyance royalties, all taxes and cost of all materials and cost. Of all labour with T&P required for the work.	238.50	One sqmt	130.70	31171.63
14	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slury treatment including punning including cost, conveyance & royalty of materials.	78.62	One sqmt	146.20	11493.61
15	12mm thick cement plaster in cement mortar (1:4) over brick work including cement punning and bitumen painting with cost, conveyance & royalty of materials.	42.53	One sqmt	158.10	6723.99
16	Supplying Fitting & fixing of MS Door & Window including cost of all materials etc complete as per the	780.88	One Kg	87.17	68071.31
17	Painting two coats with enamel paint over priming one coats with ready mixed zinc chromate yellow primer of approved brand on wood work including labour & material charges.	63.32	One sqmt	181.80	11512.11
18	Provision for fitting and fixing and cost of ventilator etc complete.				
	a) Ventilator	14.00	No	150.00	2100.00
19	Distempering two coat of walls with distemper of approved shade on new work to give and even shade including cost of Distempering	221.00	One sqmt	61.60	13613.7
20	Cement concrete in cm (1:2:4) using 12mm size h.g.c.b chips with all cost conveyance Royalty etc complete	0.37	One cum	5644.90	2105.87
21	10cm thik dry brick khao well watered & rammed to receive A.S flooring including all cost etc complete.	0.45	One cum	230.60	103.77
22	Finshing walls with water proofing cement cement paint of approved shade on new work one coats to give aneven shade over a caot of cement washing	344.27	One sqmt	31.70	10913.47
23	Add for Black Board				5000.00
24	Add for Bala Painting as per guidline to interior & exterior of building with boundary wall				19000.00
25	Add for Electrification & Sanitary work with over head tank and all fitting & fixing including playing equipments.				31293.00
26	Add for sign Board				2500.00
					1339289.64

(26 nos of items has been

Technically sanncioned)

  
JE / GPTA  
Baripada Block

  
Asst. Ex-Engineer  
Baripada Block

APPROVED

  
Block Development Officer  
Baripada Block

# BILL OF QUANTITY

**Name of the Project :- Construction of new model  
AWC at Chandabilla**

**G.P.--Chandanpur**

SI No	Item of Work	Quantity	Unit	Rate	Amount
1	Earth work in excavation of foundation in hard soil within initial lead and lift including rough dressing and breaking clods etc. complete	85.33	One cum	178.60	15239.71
2	Sand filling in foundation and plinth with well watered and remmend	38.69	One cum	390.05	15090.2
3	Cement concreet (1:3:6) with 4cm size hard grantie metal of approved quality and approved quarry in foundation including hoisting laying concrete with cost conveyance of materials including watering curing royalty all T&P required for the work etc complete as per direction of the Er. in charge.	16.53	One cum	4,178.40	69060.19
4	Flyash Bricks (25cmx12cmx8cm) masonry in cm (1:6) for Superstructure with all cost conveyancy Royalty etc.				
	a) In foundation	30.88	One cum	4,023.90	124266.9
	b) In Superstructure	50.62	One cum	4,102.00	207638.39
5	Flyash Bricks (25cmx12cmx8cm) masonry in cm (1:4) for Superstructure with all cost conveyancy Royalty etc.	0.43	One cum	4,451.27	1914.05
6	Reinforcement cement concrete M-20 grade with 20mm and down grade block hard granite (Crusher broken) stone chips including hoisting and laying including cost. Conveyance ,royalties. Taxes etc complete as per the direction of the eng. In charge.				
	a) Column Base	15.22	One cum	4,700.33	71553.23
	b) Plinth bend)	7.63	One cum	5,040.35	38479.53
	c) Lintel Band	2.57	One cum	8,082.60	20772.28
	d) Chajja	18.94	One sqmt	736.43	13948.03
	e) Column & Roof beam	8.03	One cum	10164.06	81638.06
	e) Slab	11.32	One cum	8,661.60	98049.31
7	Providing HYSD bar reinforcement for R.C.C work including straightening cutting, bending, binding, welding, tying the girls, lying and placing in proper position as per approved design and drawing including cost. Conveyance of 18 to 20 gauge binding wire cost and conveyance of HYSD bar complete in all respect as per specification for road & Bridge and dirction of Eng-In charge	40.12	One cum	6,006.50	240960.5
8	Grading work with 6mm size cbg chipes,etc.	100.20	One sqmt	274.40	27494.11
9	25mm thik A.S flooring in cement concrete in cm (1:2:4) using 12mm size h.g.c.b chips including punning with all cost conveyancy Royalty etc complete.	69.48	One sqmt	287.10	19948.22
10	Fixing tiles in floors, treads and landings on 25mm thik bed of cement mortar (1:1) joined with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing including cost of tiles.	7.03	One sqmt	910.90	6399.16
11	Fixing tiles in dabos, skirting and in rises of steops on 12 mm thik bed of cement plaster (1:3) joined with neat cement slurry mixed with pigmwnt to match the shade of the tiles intuding rubbing and polishing including cost of tile.	34.02	One sqmt	682.70	23227.98

12	16mm(5/8") thick cement plaster (1:6) in finishing smooth to inside rough surface of 10" thick brick walls after rcking out the joints including watering and curing with cost. Conveyance royalty , all tax of all materials and cost of all labour with T&P required for the work etc.	257.41	One Qntl	186.50	48007.33
13	12mm (1/2") thick cement plaster (1:6) in finishing smooth to outside smooth surface of brick walls after racing out joints including watering and curing etc. complete with cost. Conveyance royalties, all taxes and cost of all materials and cost. Of all labour with T&P required for the work.	238.50	One sqmt	130.70	31171.63
14	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slury treatment including punning including cost, conveyance & royalty of materials.	78.62	One sqmt	146.20	11493.61
15	12mm thick cement plaster in cement mortar (1:4) over brick work including cement punning and bitumen painting with cost, conveyance & royalty of materials.	42.53	One sqmt	158.10	6723.99
16	Supplying Fitting & fixing of MS Door & Window including cost of all materials etc complete as per the	780.88	One Kg	87.17	68071.31
17	Painting two coats with enamel paint over priming one coats with ready mixed zinc chromate yellow primer of approved brand on wood work including labour & material charges.	63.32	One sqmt	181.80	11512.11
18	Provision for fitting and fixing and cost of ventilator etc complete.				
	a) Ventilator	14.00	No	150.00	2100.00
19	Distempering two coat of walls with distemper of approved shade on new work to give and even shade including cost of Distempering	221.00	One sqmt	61.60	13613.7
20	Cement concrete in cm (1:2:4) using 12mm size h.g.c.b chips with all cost conveyance Royalty etc complete	0.37	One cum	5644.90	2105.87
21	10cm thik dry brick khao well watered & rammed to receive A.S flooring including all cost etc complete.	0.45	One cum	230.60	103.77
22	Finshing walls with water proofing cement cement paint of approved shade on new work one coats to give aneven shade over a caot of cement washing	344.27	One sqmt	31.70	10913.47
23	Add for Black Board				5000.00
24	Add for Bala Painting as per guideline to interior & exterior of building with boundary wall				19000.00
25	Add for Electrification & Sanitary work with over head tank and all fitting & fixing including playing equipments.				31293.00
26	Add for sign Board				2500.00
					1339289.64

(26 nos of items has been  
Technically sannctioned)

APPROVED

  
12/04/21  
JE / GPTA  
Baripada Block

  
Asst. Ex-Engineer  
Baripada Block

  
12/04/21  
Block Development Officer  
Baripada Block

# BILL OF QUANTITY

**Name of the Project :- Construction of new model  
AWC at Dhansole**

**G.P.--Bhagabatchandrapur**

SI No	item of Work	Quantity	Unit	Rate	Amount
1	Earth work in excavation of foundation in hard soil within initial lead and lift including rough dressing and breaking clods etc. complete	85.33	One cum	178.60	15239.71
2	Sand filling in foundation and plinth with well watered and remmend	38.69	One cum	390.05	15090.2
3	Cement concreet (1:3:6) with 4cm size hard grantie metal of approved quality and approved quarry in foundation including hoisting laying concrete with cost conveyance of materials including watering curing royalty all T&P required for the work etc complete as per direction of the Er. in charge.	16.53	One cum	4,178.40	69060.19
4	Flyash Bricks (25cmx12cmx8cm) masonry in cm (1:6) for Superstructure with all cost conveyancy Royalty etc.				
	a) In foundation	30.88	One cum	4,023.90	124266.9
	b) In Superstructure	50.62	One cum	4,102.00	207638.39
5	Flyash Bricks (25cmx12cmx8cm) masonry in cm (1:4) for Superstructure with all cost conveyancy Royalty etc.	0.43	One cum	4,451.27	1914.05
6	Reinforcement cement concrete M-20 grade with 20mm and down grade block hard granite (Crusher broken) stone chips including hoisting and laying including cost. Conveyance ,royalties. Taxes etc complete as per the direction of the eng. In charge.				
	a) Column Base	15.22	One cum	4,700.33	71553.23
	b) Plinth bend)	7.63	One cum	5,040.35	38479.53
	c) Lintel Band	2.57	One cum	8,082.60	20772.28
	d) Chajja	18.94	One sqmt	736.43	13948.03
	e) Column & Roof beam	8.03	One cum	10164.06	81638.06
	e) Slab	11.32	One cum	8,661.60	98049.31
7	Providing HYSD bar reinforcement for R.C.C work including straightening cutting, bending, binding, welding, tying the girls, lying and placing in proper position as per approved design and drawing including cost. Conveyance of 18 to 20 gauge binding wire cost and conveyance of HYSD bar complete in all respect as per specification for road & Bridge and dirction of Eng-In charge	40.12	One cum	6,006.50	240960.5
8	Grading work with 6mm size cbg chipes,etc.	100.20	One sqmt	274.40	27494.11
9	25mm thik A.S floring in cement concrete in cm (1:2:4) using 12mm size h.g.c.b chips including punning with all cost conveyancy Royalty etc complete.	69.48	One sqmt	287.10	19948.22
10	Fixing tiles in floors, treads and landings on 25mm thik bed of cement mortar (1:1) joined with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing including cost of tiles.	7.03	One sqmt	910.90	6399.16
11	Fixing tiles in dabos, skirting and in rises of steops on 12 mm thik bed of cement plaster (1:3) joined with neat cement slurry mixed with pigmwnt to match the shade of the tiles inluding rubbing and polishing including cost of tile.	34.02	One sqmt	682.70	23227.98

12	16mm(5/8") thick cement plaster (1:6) in finishing smooth to inside rough surface of 10" thick brick walls after rcking out the joints including watering and curing with cost. Conveyance royalty , all tax of all materials and cost of all labour with T&P required for the work etc.	257.41	One Qntl	186.50	48007.33
13	12mm (1/2") thick cement plaster (1:6) in finishing smooth to outside smooth surface of brick walls after racing out joints including watering and curing etc. complete with cost. Conveyance royalties, all taxes and cost of all materials and cost. Of all labour with T&P required for the work.	238.50	One sqmt	130.70	31171.63
14	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slury treatment including punning including cost, conveyance & royalty of materials.	78.62	One sqmt	146.20	11493.61
15	12mm thick cement plaster in cement mortar (1:4) over brick work including cement punning and bitumen painting with cost, conveyance & royalty of materials.	42.53	One sqmt	158.10	6723.99
16	Supplying Fitting & fixing of MS Door & Window including cost of all materials etc complete as per the	780.88	One Kg	87.17	68071.31
17	Painting two coats with enamel paint over priming one coats with ready mixed zinc chromate yellow primer of approved brand on wood work including labour & material charges.	63.32	One sqmt	181.80	11512.11
18	Provision for fitting and fixing and cost of ventilator etc complete.				
	a) Ventilator	14.00	No	150.00	2100.00
19	Distempering two coat of walls with distemper of approved shade on new work to give and even shade including cost of Distempering	221.00	One sqmt	61.60	13613.7
20	Cement concrete in cm (1:2:4) using 12mm size h.g.c.b chips with all cost conveyance Royalty etc complete	0.37	One cum	5644.90	2105.87
21	10cm thik dry brick khao well watered & rammed to receive A.S flooring including all cost etc complete.	0.45	One cum	230.60	103.77
22	Finshing walls with water proofing cement cement paint of approved shade on new work one coats to give aneven shade over a caot of cement washing	344.27	One sqmt	31.70	10913.47
23	Add for Black Board				5000.00
24	Add for Bala Painting as per guideline to interior & exterior of building with boundary wall				19000.00
25	Add for Electrification & Sanitary work with over head tank and all fitting & fixing including playing equipments.				31293.00
26	Add for sign Board				2500.00
					1339289.64

(26 nos of items has been  
Technically sanncioned)

APPROVED

*10/12/21*  
JE / GPTA  
Baripada Block

*10/12/21*  
Asst. Ex-Engineer  
Baripada Block

*10/12/21*  
Block Development Officer  
Baripada Block

# BILL OF QUANTITY

**Name of the Project :- Construction of new model  
AWC at Bhagabandh**

**G.P.--Bhagabatchandrapur**

SI No	item of Work	Quantity	Unit	Rate	Amount
1	Earth work in excavation of foundation in hard soil within initial lead and lift including rough dressing and breaking clods etc. complete	85.33	One cum	178.60	15239.71
2	Sand filling in foundation and plinth with well watered and remmend	38.69	One cum	390.05	15090.2
3	Cement concreet (1:3:6) with 4cm size hard grantie metal of approved quality and approved quarry in foundation including hoisting laying concrete with cost conveyance of materials including watering curing royalty all T&P required for the work etc complete as per direction of the Er. in charge.	16.53	One cum	4,178.40	69060.19
4	Flyash Bricks (25cmx12cmx8cm) masonry in cm (1:6) for Superstructure with all cost conveyancy Royalty etc.				
	a) In foundation	30.88	One cum	4,023.90	124266.9
	b) In Superstructure	50.62	One cum	4,102.00	207638.39
5	Flyash Bricks (25cmx12cmx8cm) masonry in cm (1:4) for Superstructure with all cost conveyancy Royalty etc.	0.43	One cum	4,451.27	1914.05
6	Reinforcement cement concrete M-20 grade with 20mm and down grade block hard granite (Crusher broken) stone chips including hoisting and laying including cost. Conveyance ,royalties. Taxes etc complete as per the direction of the eng. In charge.				
	a) Column Base	15.22	One cum	4,700.33	71553.23
	b) Plinth bend)	7.63	One cum	5,040.35	38479.53
	c) Lintel Band	2.57	One cum	8,082.60	20772.28
	d) Chajja	18.94	One sqmt	736.43	13948.03
	e) Column & Roof beam	8.03	One cum	10164.06	81638.06
	e) Slab	11.32	One cum	8,661.60	98049.31
7	Providing HYSD bar reinforcement for R.C.C work including straightening cutting, bending, binding, welding, tying the girls, lying and placing in proper position as per approved design and drawing including cost. Conveyance of 18 to 20 gauge binding wire cost and conveyance of HYSD bar complete in all respect as per specification for road & Bridge and dirction of Eng-In charge	40.12	One cum	6,006.50	240960.5
8	Grading work with 6mm size cbg chipes,etc.	100.20	One sqmt	274.40	27494.11
9	25mm thik A.S flooring in cement concrete in cm (1:2:4) using 12mm size h.g.c.b chips including punning with all cost conveyancy Royalty etc complete.	69.48	One sqmt	287.10	19948.22
10	Fixing tiles in floors, treads and landings on 25mm thik bed of cement mortar (1:1) joined with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing including cost of tiles.	7.03	One sqmt	910.90	6399.16
11	Fixing tiles in dabos, skirting and in rises of steops on 12 mm thik bed of cement plaster (1:3) joined with neat cement slurry mixed with pigmwnt to match the shade of the tiles inluding rubbing and polishing including cost of tile.	34.02	One sqmt	682.70	23227.98

12	16mm(5/8") thick cement plaster (1:6) in finishing smooth to inside rough surface of 10" thick brick walls after rcking out the joints including watering and curing with cost. Convayance royalty , all tax of all materials and cost of all labour with T&P required for the work etc.	257.41	One Qntl	186.50	48007.33
13	12mm (1/2") thick cement plaster (1:6) in finishing smooth to outside smooth surface of brick walls after racing out joints including watering and curing etc. complete with cost. Conveyance royalties, all taxes and cost of all materials and cost. Of all labour with T&P required for the work.	238.50	One sqmt	130.70	31171.63
14	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slury treatment including punning including cost, conveyance & royalty of materials.	78.62	One sqmt	146.20	11493.61
15	12mm thick cement plaster in cement mortar (1:4) over brick work including cement punning and bitumen painting with cost, conveyance & royalty of materials.	42.53	One sqmt	158.10	6723.99
16	Supplying Fitting & fixing of MS Door & Window including cost of all materials etc complete as per the	780.88	One Kg	87.17	68071.31
17	Painting two coats with enamel paint over priming one coats with ready mixed zinc chromate yellow primer of approved brand on wood work including labour & material charges.	63.32	One sqmt	181.80	11512.11
18	Provision for fitting and fixing and cost of ventilator etc complete.				
	a) Ventilator	14.00	No	150.00	2100.00
19	Distempering two coat of walls with distemper of approved shade on new work to give and even shade including cost of Distempering	221.00	One sqmt	61.60	13613.7
20	Cement concrete in cm (1:2:4) using 12mm size h.g.c.b chips with all cost conveyance Royalty etc complete	0.37	One cum	5644.90	2105.87
21	10cm thik dry brick khao well watered & rammed to receive A.S flooring including all cost etc complete.	0.45	One cum	230.60	103.77
22	Finshing walls with water proofing cement cement paint of approved shade on new work one coats to give aneven shade over a caot of cement washing	344.27	One sqmt	31.70	10913.47
23	Add for Black Board				5000.00
24	Add for Bala Painting as per guideline to interior & exterior of building with boundary wall				19000.00
25	Add for Electrification & Sanitary work with over head tank and all fitting & fixing including playing equipments.				31293.00
26	Add for sign Board				2500.00
					1339289.64

(26 nos of items has been  
Technically sanncioned)

APPROVED

*Handwritten signature*  
JE / GPTA  
Baripada Block

*Handwritten signature*  
Asst. Ex-Engineer  
Baripada Block

*Handwritten signature*  
Block Development Officer  
Baripada Block



# BILL OF QUANTITY

**Name of the Project :- Construction of new model  
AWC at Sikarghati**

**G.P.--Sankhabhanga**

SI No	item of Work	Quantity	Unit	Rate	Amount
1	Earth work in excavation of foundation in hard soil within initial lead and lift including rough dressing and breaking clods etc. complete	85.33	One cum	178.60	15239.71
2	Sand filling in foundation and plinth with well watered and remmend	38.69	One cum	390.05	15090.2
3	Cement concreet (1:3:6) with 4cm size hard grantie metal of approved quality and approved quarry in foundation including hoisting laying concrete with cost conveyance of materials including watering curing royalty all T&P required for the work etc complete as per direction of the Er. in charge.	16.53	One cum	4,178.40	69060.19
4	Flyash Bricks (25cmx12cmx8cm) masonry in cm (1:6) for Superstructure with all cost conveyancy Royalty etc.				
	a) In foundation	30.88	One cum	4,023.90	124266.9
	b) In Superstructure	50.62	One cum	4,102.00	207638.39
5	Flyash Bricks (25cmx12cmx8cm) masonry in cm (1:4) for Superstructure with all cost conveyancy Royalty etc.	0.43	One cum	4,451.27	1914.05
6	Reinforcement cement concrete M-20 grade with 20mm and down grade block hard granite (Crusher broken) stone chips including hoisting and laying including cost. Conveyance ,royalties. Taxes etc complete as per the direction of the eng. In charge.				
	a) Column Base	15.22	One cum	4,700.33	71553.23
	b) Plinth bend)	7.63	One cum	5,040.35	38479.53
	c) Lintel Band	2.57	One cum	8,082.60	20772.28
	d) Chajja	18.94	One sqmt	736.43	13948.03
	e) Column & Roof beam	8.03	One cum	10164.06	81638.06
	e) Slab	11.32	One cum	8,661.60	98049.31
7	Providing HYSD bar reinforcement for R.C.C work including straightening cutting, bending, binding, welding, tying the girls, lying and placing in proper position as per approved design and drawing including cost. Conveyance of 18 to 20 gauge binding wire cost and conveyance of HYSD bar complete in all respect as per specification for road & Bridge and dirction of Eng-In charge	40.12	One cum	6,006.50	240960.5
8	Grading work with 6mm size cbg chipes,etc.	100.20	One sqmt	274.40	27494.11
9	25mm thik A.S floring in cement concrete in cm (1:2:4) using 12mm size h.g.c.b chips including punning with all cost conveyancy Royalty etc complete.	69.48	One sqmt	287.10	19948.22
10	Fixing tiles in floors, treads and landings on 25mm thik bed of cement mortar (1:1) joined with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing including cost of tiles.	7.03	One sqmt	910.90	6399.16
11	Fixing tiles in dabos, skirting and in rises of steops on 12 mm thik bed of cement plaster (1:3) joined with neat cement slurry mixed with pigmwnt to match the shade of the tiles including rubbing and polishing including cost of tile.	34.02	One sqmt	682.70	23227.98

12	16mm(5/8") thik cement plaster (1:6) in finishing smooth to inside rough surface of 10" thik brick walls after rcking out the joints including watering and curing with cost. Convayance royalty , all tax of all materials and cost of all labour with T&P required for the work etc.	257.41	One Qntl	186.50	48007.33
13	12mm (1/2") thick cement plaster (1:6) in finishing smooth to outside smooth surface of brick walls after racing out joints including watering and curing etc. complete with cost. Conveyance royalties, all taxes and cost of all materials and cost. Of all labour with T&P required for the work.	238.50	One sqmt	130.70	31171.63
14	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slury treatment including punning including cost, conveyance & royalty of materials.	78.62	One sqmt	146.20	11493.61
15	12mm thick cement plaster in cement mortar (1:4) over brick work including cement punning and bitumen painting with cost, conveyance & royalty of materials.	42.53	One sqmt	158.10	6723.99
16	Supplying Fitting & fixing of MS Door & Window including cost of all materials etc complete as per the	780.88	One Kg	87.17	68071.31
17	Painting two coats with enamel paint over priming one coats with ready mixed zinc chromate yellow primer of approved brand on wood work including labour & material charges.	63.32	One sqmt	181.80	11512.11
18	Provision for fitting and fixing and cost of ventilator etc complete.				
	a) Ventilator	14.00	No	150.00	2100.00
19	Distempering two coat of walls with distemper of approved shade on new work to give and even shade including cost of Distempering	221.00	One sqmt	61.60	13613.7
20	Cement concrete in cm (1:2:4) using 12mm size h.g.c.b chips with all cost conveyance Royalty etc complete	0.37	One cum	5644.90	2105.87
21	10cm thik dry brick khao well watered & rammed to receive A.S flooring including all cost etc complete.	0.45	One cum	230.60	103.77
22	Finshing walls with water proofing cement cement paint of approved shade on new work one coats to give aneven shade over a caot of cement washing	344.27	One sqmt	31.70	10913.47
23	Add for Black Board				5000.00
24	Add for Bala Painting as per guideline to interior & exterior of building with boundary wall				19000.00
25	Add for Electrification & Sanitary work with over head tank and all fitting & fixing including playing equipments.				31293.00
26	Add for sign Board				2500.00
					1339289.64

(26 nos of items has been

Technically sannctioned)

  
12/4/21  
JE / GPTA  
Baripada Block

  
12/4/21  
Asst. Ex-Engineer  
Baripada Block

APPROVED

  
12/4/21  
Block Development Officer  
Baripada Block

**OFFICE OF THE PANCHAYAT SAMITI ,BARIPADA,DIST-MAYURBHANJ**

No. 772

Date.: 12/04/2021

ANNEXURE - 'A'

**TENDER CALL NOTICE**

The Block Development Officer, Baripada on behalf of Government of Odisha invites sealed tender on percentage (%) rate basis from registered contractors of Odisha PWD/WR/RWD/NH/MI/CPWD for the following work in conformity with the detail tender call notice.

Sl No	Name of G.P	Name of Work	Name of the Scheme	Estimated amount put to tender (in Rs).	EMD to be deposited (in Rs)	Tender Paper including GST(5%)	Class of Contractor	Period of Completion
1	Bhagabat Ch. Pur	Construction of new model AWC at Bhagabandh	OMBADC	1339290.00	13400.00	6500.00	"C" & "D"	4 Months
2	Bhagabat Ch. Pur	Construction of new model AWC at Dhansole	OMBADC	1339290.00	13400.00	6500.00	"C" & "D"	4 Months
3	Khadisole	Construction of new model AWC at Dumapada	OMBADC	1339290.00	13400.00	6500.00	"C" & "D"	4 Months
4	Sankhabhanga	Construction of new model AWC at Sikharghaty	OMBADC	1339290.00	13400.00	6500.00	"C" & "D"	4 Months
5	Sankhabhanga	Construction of new model AWC at Goplapur	OMBADC	1339290.00	13400.00	6500.00	"C" & "D"	4 Months
6	Chandanpur	Construction of new model AWC at Chandabilla	OMBADC	1339290.00	13400.00	6500.00	"C" & "D"	4 Months
7	Chandanpur	Construction of new model AWC at Meghamari	OMBADC	1339290.00	13400.00	6500.00	"C" & "D"	4 Months
8	Badjode	Construction of new model AWC at K.C.Pur-E	OMBADC	1339290.00	13400.00	6500.00	"C" & "D"	4 Months

[1]

  
Block Development Office  
Baripada

<b>Term and Condition</b>							
1	The Details of tender paper can be obtained and downloaded from the Website WWW.Mayurbhanj.Nic.in.						
2	The sealed tender paper will be received on working days only till 5.00 PM on or before 29/04/2021 .The same should be submitted either through registered /speed post addressing to The BDO, Baripada. The sealed envelope shall be super scribing the project name for which the Tender is applying for (Name of the work).The undersigned will not be held responsible for any delay in the postal service.						
3	The tender paper will be opened at 9.00 AM of date 30/04/2021 in presence of the bidders or their authorized representatives and Block tender committee in the office chamber of BDO, Baripada.						
4	The EMD@ Rs.13,400/- is to be deposited in shape of NSC/KVP/POTD/deposit of any Nationalized Bank duly pledged in favour of the Block Development Officer ,Baripada.						
5	The following documents should be furnished along with the tender paper failing which the tender is liable for rejection.						
	a. EMD duly pledged in favour of the BDO, Baripada payable at Baripada						
	b. Self Attested copy of the valid Contractor registration Certificate.						
	c. Self Attested copy of PAN CARD and GST clearance Certificate with active GSTIN.						
	d. The Cost of Tender paper @ Rs.6500/- should be submitted in shape of DD of any nationalized Bank Payable at Baripada in the name of the BDO, Baripada						
	e. Attested copy of Caste certificate for SC/ST Contractor desirous of availing preference.						
	f. The Engineering Contractor desirous of availing exemption of EMD should submit an affidavit to the effect that he has not availed exemption of EMD facility more than three times in the current financial Year.						
7	g. The valid labour license should be submitted at the Time of Agreement.						
8	The Schedule Caste/Schedule Tribe/Physically handicapped Contractors desirous to avail the exemption of EMD and price preference (as applicable) ,should mention in the Affidavit.						
9	If the less rate quoted by the tenderer is more than 10% and within 14.99% the additional performance security is to be deposited in shape of NSC/KVP/Bank Draft which are duly pledged in favour of the BDO, Baripada at the time of agreement as per revised codal provision of Govt. in Works Department. N.B. With in 0 - 5% No differential amount to be deposited. Within 5-10 % , 50% of the differential amount is to be deposited. Beyond 10%, 150% of rhe differential amount is to be deposited . All to be deposited in shape of DD which are duly pledged in favour of the BDO, Baripada						
10	The EMD amount will be forfeited if the Tenderer backs out from the offer of acceptance of Tender by the Competent authority						
11	The Tenderer has to show all required original documents at the time of opening of the tender for verification.						